



***BID AND CONTRACT DOCUMENTS
AND SPECIFICATIONS
FOR***

2025 ASPHALT OVERLAY

PROJECT # 12525

***City of Federal Way
PUBLIC WORKS
33325 8th Avenue South
Federal Way, WA 98003***

**BID AND CONTRACT DOCUMENTS AND SPECIFICATIONS
FOR
2025 ASPHALT OVERLAY**

PROJECT # 12525

Bids Accepted Until 10:00 a.m., February 14th, 2025 at
City of Federal Way
33325 8th Avenue South
Federal Way, WA 98003

Prepared By:
City of Federal Way
Public Works



The contract plans and specifications for this Project have been reviewed and approved by:

A handwritten signature in blue ink that reads "Jenni S. Mullen".

Public Works Director / Deputy Public Works Director

TABLE OF CONTENTS

PAGE

ADVERTISEMENT FOR BIDS 1
INSTRUCTIONS TO BIDDERS & CHECKLISTS3
BID PROPOSAL5
BID BOND.....24
SUBCONTRACTOR LIST25
CONTRACTOR WAGE LAW COMPLIANCE CERTIFICATION26
PROPOSAL FOR INCORPORATING RECYCLED MATERIALS.....27
RETAINAGE OPTION28
PUBLIC WORKS CONTRACT29
SAMPLE CONTRACT CHANGE ORDER36
CERTIFICATE OF INSURANCE38
PERFORMANCE AND PAYMENT BOND39
RETAINAGE BOND TO CITY OF FEDERAL WAY41

SPECIAL PROVISIONS

APX A: STANDARD PLANS AND DETAILS

APX B: PREVAILING WAGES AND BENEFIT CODE KEY

PROJECT PLANS (BOUND SEPARATELY)

ADVERTISEMENT FOR BIDS **2025 ASPHALT OVERLAY**

SUBMITTAL OF SEALED BIDS: Notice is hereby given that the City of Federal Way will receive sealed bids through February 14th, 2025, at 10:00 a.m. at the City Hall Finance Department at 33325 8th Avenue South, Federal Way, Washington 98003. Proposals received after said date and time will not be considered. All timely bids will be opened and read publicly aloud in the Hylebos Meeting Room City Hall 33325 8th Avenue South, Federal Way, Washington 98003 at 10:05a.m. on February 14th, 2025.

This project shall consist of: Furnishing all materials, equipment, tools, labor, and other work or items incidental thereto (excepting any materials, equipment, utilities, or service, if any, specified herein to be furnished by the Owner or others), for the construction, sequencing, and traffic control plan for overlaying existing asphalt concrete pavement in seven (7) different locations within the City of Federal Way. The work shall include but is not limited to Hot Mix Asphalt (HMA Cl. ½" PG 58H-22) pavement overlay, roadway excavation, planing bituminous pavement, pavement repair, removal and replacement of curb and gutter, sidewalk, curb ramps, traffic curb, repairing or re-aligning manholes and catch basins, pedestrian push button, and foundation, channelization, restoration, utility adjustments, and all items necessary to complete the work as described in the Contract Documents.

The City anticipates awarding this project to the successful bidder and intends to give Notice to Proceed as soon as the Contract and all required documents are executed in full. Regardless of the date of award or Notice to Proceed, the Contractor must complete all work within 120 working days.

BID DOCUMENTS: Plans, Specifications, Addenda, and plan holders list are available on-line through Builders Exchange of Washington at www.bxwa.com. Click on: "Posted Projects," "Public Works," and "City of Federal Way." It is recommended that Bidders "Register" in order to receive automatic e-mail notification of future addenda and to place themselves on the "Bidders List." Bidders that do not register will need to periodically check on-line for addenda issued on this project. Contact Builders Exchange of Washington at (425) 258-1303 if you require assistance with access or registration. An informational copy of plans, specifications, and addenda are available for viewing only at the City of Federal Way Finance Department.

QUESTIONS: Any questions must be directed to John Cole, EIT, by email at John.Cole@federalwaywa.gov, or by letter addressed to same. Questions must be received by the City no later than 5:00 p.m. three business days preceding the bid opening to allow a written reply to reach all prospective Bidders before the submission of bids.

OTHER PROVISIONS: All bids and this Project shall be governed by the Contract, as defined by the Washington State Department of Transportation Standard Specifications for Road, Bridge, and Municipal Construction 2025 (Standard Specifications), which is incorporated by this reference as though set forth in full.

All bid proposals shall be in accordance with the Contract and all bid proposals shall be accompanied by a bid deposit or bond in the amount required in the Contract. Forfeiture of the proposal bond or deposit to the City shall be in accordance with the Contract.

The recipient, in accordance with Title VI of the Civil Rights Act of 1964, (78 Stat. 252, 42 U.S.C. 2000d to 2000d-4) and the Regulations, hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award. The City encourages minority and women-owned firms to submit bids consistent with the City's policy to ensure that such firms are afforded the maximum practicable opportunity to compete for and obtain public contracts.

The City of Federal Way reserves the right to reject any and all bids, waive any informalities or minor irregularities in the bidding, and determine which bid or bidder meets the criteria set forth in the bid documents.

DATES OF PUBLICATION:

CITY OF FEDERAL WAY

RFB-1
CFW RFB VERSION 2024-OCT

2025 ASPHALT OVERLAY
PROJECT #12525 / RFB #25-001

Daily Journal of Commerce
Federal Way Mirror

Publish January 24, 2025 and January 31, 2025
Publish January 24, 2025 and January 31, 2025

INSTRUCTIONS TO BIDDERS & CHECKLISTS

(1) **ADVERTISEMENT FOR BIDS AND CONTRACT DOCUMENTS**

The Advertisement for Bids and Contract Documents contain bidder instructions that must be complied with.

(2) **EXAMINATION OF BID AND CONTRACT DOCUMENTS – BIDDER RESPONSIBILITIES**

The submission of a bid shall constitute an acknowledgment upon which the City may rely that the bidder has thoroughly examined and is familiar with the bid and Contract Documents, the Project site, the availability of materials and labor, publically available information, and has reviewed and inspected all applicable federal, state, and local statutes, regulations, ordinances and resolutions dealing with or related to the equipment and/or services to be provided herein. The failure or neglect of a bidder to examine such documents, statutes, regulations, ordinances or resolutions shall in no way relieve the bidder from any obligations with respect to the bidder's bid or the contract documents. No claim for additional compensation will be allowed which is based upon a lack of knowledge of any contract documents, statutes, regulations, ordinances or resolutions. Bidders shall visit delivery and service locations(s) as required. Bidders shall become familiar with and verify any environmental factors, which may impact current or future prices for this requirement.

(3) **INTERPRETATION OF BID AND CONTRACT DOCUMENTS**

No oral clarifications, interpretations, or representation will be made to any bidder as to the meaning of the bid or Contract Documents. Bidders shall not rely upon any oral statement or conversation they may have with City's employees, agents, representatives, consultants, or design professionals regarding the Contract Documents, whether at the pre-bid meeting or otherwise and no oral communications will be binding upon the City. Any questions must be directed to John Cole, by email at John.Cole@federalwaywa.gov, or by letter addressed to same. The questions must be received by the City no later than 5:00 p.m. three business days preceding the bid opening to allow a written reply to reach all prospective Bidders before the submission of their bids. Any interpretation deemed necessary by the City will be in the form of an Addendum to the bid documents and when issued will be sent as promptly as is practical to all parties to whom the bid documents have been issued. All such Addenda shall become part of the bid.

(4) **BID PRICE**

The bid price shall include everything necessary for the completion of the Contract and the Work including, but not limited to, furnishing all materials, equipment, tools, freight charges, facilities and all management, superintendence, labor and service, except as may be provided otherwise in the Contract Documents. All Washington State sales tax and all other government taxes, assessments and charges shall be included in the various Bid item prices as required by law. The offer shall remain in effect ninety (90) days after the bid opening.

(5) **POSTPONEMENT OF BID OPENING**

The City reserves the right to postpone the date and time for the opening of bids by Addendum at any time prior to the bid opening date and time announced in these documents.

(6) **REJECTION OF BIDS**

The City reserves the right to reject any bid for any reason including, but not limited to, the reasons listed in Special Provisions Section 1-02.13. The City further reserves the right to reject any portion of any bid and/or to reject all bids. In consideration for the City's review and evaluation of its bid, the bidder waives and releases any claims against the City arising from any rejection of any or all bids. If, in the opinion of the City, there is reason to believe that collusion exists among bidders, none of the bids of the participants in such collusion will be considered.

(7) **RECYCLED PRODUCTS**

The Contractor shall use recycled paper for proposals and for any printed or photocopied material created pursuant to a contract with the City whenever practicable and use both sides of paper sheets for reports submitted to the City whenever practicable.

(8) BIDDER'S CHECKLIST

The bidder's attention is especially called to the following forms, which must be executed in full as required. Failure to comply may result in rejection of any bid not so complying.

- Bid Proposal:** The Bid Proposal shall be completed and fully executed, including filling in the total bid amount.
- Bid Bond:** This form is to be executed by the bidder (and the surety company as appropriate, depending upon the option selected by the bidder).
- Subcontractor List:** The Subcontractor List shall be filled in by the bidder.
- Contractor Certification – Wage Law Compliance:** This form shall be filled in and fully executed by the bidder.
- Proposal for Incorporating Recycled Materials:** This form shall be filled in and executed by the bidder.
- Retainage Option:** This form shall be filled in and executed by the bidder to inform the City of their Retainage Option in the event they are the lowest, responsive, responsible bidder..

(9) CONTRACT CHECKLIST

The following documents are to be executed and delivered to the City after the Bid is awarded:

- Public Works Contract:** The successful bidder will fully execute and deliver to the City the Public Works Contract ("Contract") from these Bid Documents.
- Certificate of Insurance:** The successful bidder will provide a Certificate of Insurance evidencing the insurance requirement set forth in the Contract.
- Performance/Payment Bond:** The successful bidder will provide a fully executed Performance/Payment Bond as appropriate.
- Contractor's Retainage Bond:** If the retainage bond option is chosen, then the successful bidder will fully execute and deliver to the City the Contractor's Retainage Bond.
- Business License:** The successful bidder will provide a copy of a current Business License with the City of Federal Way.

BID PROPOSAL
2025 ASPHALT OVERLAY

PROPOSAL SUBMITTED TO:

City of Federal Way
33325 8th Ave South
Federal Way, Washington 98003-6325

PROPOSAL SUBMITTED BY:

Bidder: _____
Full Legal Name of Firm

Contact: _____
Individual with Legal Authority to sign Bid and Contract

Address: _____
Street Address

City, State Zip

Phone: _____

E-Mail: _____

- Select One of the Following:
- Corporation
 - Partnership.
 - Individual
 - Other

State Contractor's License No.: _____

State Contractor's License Expiration Date: _____ / _____ / _____
Month Day Year

State UBI No.: _____

State Worker's Comp. Account No.: _____

NOTE: All entries shall be written in ink or typed. Unit prices for all items, all extensions, and total amount of bid shall be shown. Enter unit prices in numerical figures only, in dollars and cents to two (2) decimal places (including for whole dollar amounts). All figures must be clearly legible. Bids with illegible figures in the unit price column will be regarded as nonresponsive. Where conflict occurs between the unit price and the total amount specified for any item, the unit price shall prevail, and totals shall be corrected to conform thereto. The Bidder shall complete this entire Bid Form or this bid may be considered non-responsive. The City may correct obvious mathematical errors. The City of Federal Way reserves the right to reject any and all bids, waive any informalities or minor irregularities in the bidding, and determine which bid or bidder meets the criteria set forth in the bid documents.

2025 ASPHALT OVERLAY PROJECT-WIDE ITEMS						
<i>All unit prices shall include applicable sales tax (Roadway Improvements)</i>						
Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-07	APPRENTICESHIP INCENTIVE	CALC	1	\$2,000.00	\$2,000.00
2	1-07	APPRENTICESHIP PENALTY	CALC	-1	\$2,000.00	-\$2,000.00
TOTAL – PROJECT-WIDE ITEMS						\$0.00

CAMPUS HIGHLANDS WEST: ROADWAY IMPROVEMENTS						
<i>All unit prices shall include applicable sales tax (Roadway Improvements)</i>						
Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$5,000.00	\$5,000.00
2	1-05	ADA FEATURES SURVEYING	1	1		
3	1-05	ROADWAY SURVEYING	1	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		

9	1-10	FLAGGERS	HR	1200		
10	1-10	OTHER TRAFFIC CONTROL LABOR	HR	100		
11	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$6,850.00	\$6,850.00
12	2-01	ROADSIDE CLEANUP	FA	1	\$3,000.00	\$3,000.00
13	2-02	ASPHALT/CEMENT CONCRETE SAWCUTTING	LF	3200		
14	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	400		
15	5-04	PAVEMENT REPAIR EXCAVATION INCL. HAUL	CY	250		
16	5-04	PLANING BITUMINOUS PAVEMENT	SY	19650		
17	5-04	HMA CL. 1/2" PG 58H-22	TN	3400		
18	5-04	HMA CL. 1/2" PG 58H-22 FOR PAVEMENT REPAIR	TN	475		
19	5-04	REMOVE AND REPLACE HMA SPEED HUMP, COMPLETE	EA	4		
20	7-05	ADJUST MANHOLE	EA	13		
21	7-05	ADJUST SANITARY SEWER MANHOLE	EA	33		
22	7-05	ADJUST LUD WATER VALVE	EA	19		
23	8-01	EROSION/WATER POLLUTION CONTROL	FA	1	\$3,000.00	\$3,000.00
24	8-01	INLET PROTECTION INSERT	EA	63		
25	8-02	SOD INSTALLATION	SY	250		
26	8-02	TOPSOIL TYPE 3-WAY MIX	SY	50		
27	8-02	PROPERTY RESTORATION	FA	1	\$3,000.00	\$3,000.00
28	8-04	CEMENT CONC. CURB & GUTTER	LF	1350		
29	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	1250		
30	8-09	HYDRANT MARKER, TYPE 2BB	EA	9		

31	8-13	ADJUST MONUMENT CASE AND COVER	EA	45		
32	8-14	CEMENT CONC. SIDEWALK	SY	220		
33	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL A	EA	55		
34	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL B	EA	2		
35	8-22	PAINT SHARED LANE MARKING	EA	8		
36	8-22	PLASTIC CROSSWALK SYMBOL	SF	250		
TOTAL – CAMPUS HIGHLANDS WEST						\$

CAMPUS HIGHLANDS EAST: ROADWAY IMPROVEMENTS						
<i>All unit prices shall include applicable sales tax (Roadway Improvements)</i>						
Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$5,000.00	\$5,000.00
2	1-05	ADA FEATURES SURVEYING	LS	1		
3	1-05	ROADWAY SURVEYING	LS	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		
9	1-10	FLAGGERS	HR	1500		
10	1-10	OTHER TRAFFIC CONTROL LABOR	HR	100		

11	1-10	PORTABLE CHANGEABLE MESSAGE SIGN	HR	100		
12	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$6,500.00	\$6,500.00
13	2-01	ROADSIDE CLEANUP	FA	1	\$3,000.00	\$3,000.00
14	2-02	ASPHALT/CEMENT CONCRETE SAWCUTTING	LF	2000		
15	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	275		
16	5-04	PAVEMENT REPAIR EXCAVATION INCL. HAUL	CY	145		
17	5-04	PLANING BITUMINOUS PAVEMENT	SY	16850		
18	5-04	HMA CL. 1/2" PG 58H-22	TN	3200		
19	5-04	HMA CL. 1/2" PG 58H-22 FOR PAVEMENT REPAIR	TN	300		
20	5-04	REMOVE AND REPLACE HMA SPEED HUMP, COMPLETE	EA	3		
21	7-05	ADJUST MANHOLE	EA	8		
22	7-05	ADJUST SANITARY SEWER MANHOLE	EA	29		
23	7-05	HIGH IMPACT RISER	EA	6		
24	7-05	ADJUST LUD WATER VALVE	EA	24		
25	8-01	EROSION/WATER POLLUTION CONTROL	FA	1	\$3,000.00	\$3,000.00
26	8-01	INLET PROTECTION INSERT	EA	54		
27	8-02	SOD INSTALLATION	SY	145		
28	8-02	TOPSOIL TYPE 3-WAY MIX	SY	50		
29	8-02	PROPERTY RESTORATION	FA	1	\$3,000.00	\$3,000.00
30	8-04	CEMENT CONC. CURB & GUTTER	LF	1000		
31	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	750		
32	8-09	RAISED PAVEMENT MARKER, TYPE 2	HUN	1.1		

33	8-09	HYDRANT MARKER, TYPE 2BB	EA	9		
34	8-13	ADJUST MONUMENT CASE AND COVER	EA	16		
35	8-14	CEMENT CONC. SIDEWALK	SY	165		
36	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL A	EA	39		
37	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL B	EA	1		
38	8-20	UTILITY ADJUSTMENT	EA	24		
39	8-20	DETECTION LOOPS	EA	7		
40	8-22	PAINT LINE	LF	2000		
41	8-22	PAINTED WIDE LINE	LF	50		
42	8-22	PLASTIC STOP LINE	LF	25		
43	8-22	PAINTED SHARED LANE MARKING	EA	20		
44	8-22	PAINTED TRAFFIC ARROW	EA	2		
45	8-23	REMOVE PAVEMENT MARKINGS	LS	1		
46	8-23	TEMPORARY PAVEMENT MARKING - SHORT DURATION	LF	4000		
47	8-23	TEMPORARY STOP LINE - SHORT DURATION	LF	25		
TOTAL – CAMPUS HIGHLANDS EAST						\$
12TH AVE SW: ROADWAY IMPROVEMENTS <i>All unit prices shall include applicable sales tax (Roadway Improvements)</i>						
Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$5,000.00	\$5,000.00
2	1-04	ADA FEATURES SURVEYING	LS	1		

3	1-05	ROADWAY SURVEYING	LS	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	FLAGGERS	HR	800		
9	1-10	OTHER TRAFFIC CONTROL LABOR	HR	40		
10	1-10	PORTABLE CHANGEABLE MESSAGE SIGN	HR	240		
11	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		
12	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$6,500.00	\$6,500.00
13	2-02	REMOVE EXISTING CATCH BASIN	EA	1		
14	2-02	SAWCUTTING	LF	4,200		
15	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	450		
16	4-04	CRUSHED SURFACING TOP COURSE	TN	420		
17	5-04	HMA CL. 1/2" PG 58H22	TN	2,900		
18	5-04	HMA FOR PAVEMENT REPAIR CL.1/2" PG 58H-22	TN	910		
19	5-04	PAVEMENT REPAIR EXCAVATION INCL. HAUL	CY	450		
20	5-04	PLANING BITUMINOUS PAVEMENT	SY	14,000		
21	5-04	REMOVE AND REPLACE HMA SPEED HUMP, COMPLETE	EA	4		
22	5-04	REMOVE AND REPLACE RAISED CROSSWALK, COMPLETE	EA	1		
23	7-04	DUCTILE IRON STORM SEWER PIPE 12 IN. DIAM	LF	100		
24	7-05	ADJUST MANHOLE	EA	2		

25	7-05	NON-SLIP MMA COATING FOR LIDS	LS	1		
26	7-05	CATCH BASIN TYPE 1	EA	5		
27	7-12	ADJUST WATER VALVE TO GRADE	EA	15		
28	7-17	ADJUST SANITARY SEWER MANHOLE	EA	13		
29	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	LS	1		
30	8-02	TOPSOIL TYPE 3-WAY MIX	SY	250		
31	8-02	SEEDED LAWN INSTALLATION	SY	100		
32	8-02	BARK OR WOOD CHIP MULCH	SY	150		
33	8-02	PROPERTY RESTORATION	FA	1	\$10,000.00	\$10,000.00
34	8-04	CEMENT CONC. TRAFFIC CURB AND GUTTER	LF	3,350		
35	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	1,675		
36	8-29	RAISED PAVEMENT MARKER TYPE 2	HUN	4.7		
37	8-13	MONUMENT CASE AND COVER	EA	1		
38	8-13	ADJUST MONUMENT CASE AND COVER	EA	18		
39	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL	EA	54		
40	8-14	CEMENT CONC. SIDEWALK	SY	250		
41	8-14	DETECTABLE WARNING SURFACE	SF	35		
42	8-14	BLACK DETECTABLE WARNING SURFACE	SF	100		
43	8-21	PERMANENT SIGNING	LS	1		
44	8-22	PAINT LINE	LF	9600		
45	8-22	PLASTIC STOP LINE	LF	90		
46	8-22	PLASTIC CROSSWALK LINE	SF	500		

47	8-22	PAINTED BICYCLE LANE SYMBOL	EA	11		
48	8-23	TEMPORARY PAVEMENT MARKING - SHORT DURATION	LF	9600		
49	8-23	TEMPORARY MISC. PAVEMENT MARKING - SHORT DURATION	EA	11		
50	8-23	TEMPORARY STOP LINE - SHORT DURATION	LF	90		
51	8-23	TEMPORARY CROSSWALK LINE - SHORT DURATION	SF	500		

TOTAL – 12TH AVE SW \$

SCARBOROUGH: ROADWAY IMPROVEMENTS

All unit prices shall include applicable sales tax (Roadway Improvements)

Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$ 5,000.00	\$ 5,000.00
2	1-04	ADA FEATURES SURVEYING	LS	1		
3	1-05	ROADWAY SURVEYING	LS	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	FLAGGERS	HR	300		
9	1-10	OTHER TRAFFIC CONTROL LABOR	HR	30		
10	1-10	PORTABLE CHANGEABLE MESSAGE SIGN	HR	240		
11	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		
12	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$ 2,800.00	\$ 2,800.00

13	2-01	ROADSIDE CLEANUP	FA	1	\$ 3,000.00	\$ 3,000.00
14	2-02	SAWCUTTING	LF	1,200		
15	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	1,200		
16	4-04	CRUSHED SURFACING TOP COURSE	TN	450		
17	4-04	CRUSHED SURFACING BASE COURSE	TN	900		
18	5-04	HMA CL. 1/2" PG 58H-22	TN	1,700		
19	5-04	PLANING BITUMINOUS PAVEMENT	SY	8,750		
20	5-04	REMOVE AND REPLACE HMA SPEED HUMP, COMPLETE	EA	2		
21	7-05	ADJUST CATCH BASIN	EA	2		
22	7-12	ADJUST WATER VALVE TO GRADE	EA	6		
23	7-17	ADJUST SANITARY SEWER MANHOLE	EA	13		
24	7-20	MODULAR WETLAND UNIT	EA	1		
25	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	LS	1		
26	8-02	SOD INSTALLATION	SY	5		
27	8-02	TOPSOIL TYPE 3-WAY MIX	SY	50		
28	8-02	BARK OR WOOD CHIP MULCH	SY	5		
29	8-02	PROPERTY RESTORATION	FA	1	\$ 2,000.00	\$ 2,000.00
30	8-04	ROLLED CEMENT CONC. TRAFFIC CURB	LF	850		
31	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	50		
32	8-09	RAISED PAVEMENT MARKER TYPE 2	HUN	1		
33	8-13	ADJUST MONUMENT CASE AND COVER	EA	16		
34	8-14	CEMENT CONC. SIDEWALK	SY	60		

35	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL A	EA	21		
36	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL B	EA	3		
37	8-22	PROFILED PLASTIC LINE	LF	1,400		
38	8-22	SHARED LANE MARKING	EA	9		
39	8-23	TEMPORARY PAVEMENT MARKING - SHORT DURATION	LF	1,400		
40	8-23	TEMPORARY MISC. PAVEMENT MARKING - SHORT DURATION	EA	9		
41	8-33	RESOLUTION OF UTILITY CONFLICTS	FA	1	\$ 2,500.00	\$ 2,500.00
TOTAL – SCARBOROUGH						\$
EMBERWOOD: ROADWAY IMPROVEMENTS						
<i>All unit prices shall include applicable sales tax (Roadway Improvements)</i>						
Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$5,000.00	\$5,000.00
2	1-04	ADA FEATURES SURVEYING	LS	1		
3	1-05	ROADWAY SURVEYING	LS	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	FLAGGERS	HR	470		
9	1-10	OTHER TRAFFIC CONTROL LABOR	HR	50		
10	1-10	PORTABLE CHANGEABLE MESSAGE SIGN	HR	315		

11	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		
12	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$3,100.00	\$3,100.00
13	2-01	ROADSIDE CLEANUP	FA	1	\$3,000.00	\$3,000.00
14	2-02	SAWCUTTING	LF	850		
15	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	150		
16	4-04	CRUSHED SURFACING TOP COURSE	TN	45		
17	5-04	HMA CL. 1/2 IN. PG 58H-22	TN	1,700		
18	5-04	PLANING BITUMINOUS PAVEMENT	SY	9,600		
19	5-04	PAVEMENT REPAIR EXCAVATION INCL. HAUL	CY	250		
20	5-04	HMA FOR PAVEMENT REPAIR CL. 1/2 IN. PG 58H-22	TN	475		
21	5-04	PLANING BITUMINOUS PAVEMENT	SY	9,600		
22	5-04	REMOVE AND REPLACE HMA SPEED HUMP, COMPLETE	EA	6		
23	7-17	ADJUST SANITARY SEWER MANHOLE	EA	11		
24	8-02	PROPERTY RESTORATION	FA	1	\$4,000.00	\$4,000.00
25	8-02	SOD INSTALLATION	SY	70		
26	8-02	TOPSOIL TYPE 3-WAY MIX	SY	50		
27	8-04	CEMENT CONC. TRAFFIC CURB AND GUTTER	LF	850		
28	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	425		
29	8-13	MONUMENT CASE AND COVER	EA	3		
30	8-13	ADJUST MONUMENT CASE AND COVER	EA	10		
31	8-14	CEMENT CONC. SIDEWALK	SY	110		
32	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL	EA	14		

33	8-22	PAINTED SHARED LANE MARKING	EA	19		
TOTAL – EMBERWOOD						\$
18TH AVE S: ROADWAY IMPROVEMENTS <i>All unit prices shall include applicable sales tax (Roadway Improvements)</i>						
Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$5,000.00	\$5,000.00
2	1-04	ADA FEATURES SURVEYING	LS	1		
3	1-05	ROADWAY SURVEYING	LS	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	FLAGGERS	HR	300		
9	1-10	OTHER TRAFFIC CONTROL LABOR	HR	30		
10	1-10	PORTABLE CHANGEABLE MESSAGE SIGN	HR	200		
11	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		
12	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$2,700.00	\$2,700.00
13	2-01	ROADSIDE CLEANUP	FA	1	\$2,500.00	\$2,500.00
14	2-02	SAWCUTTING	LF	240		
15	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	28		
16	4-04	CRUSHED SURFACING TOP COURSE	TN	100		

17	5-04	HMA CL.1/2 PG 58H-22	TN	1,000		
18	5-04	HMA FOR PRELEVELING CL.1/2 PG 58H-22	TN	100		
19	5-04	PLANING BITUMINOUS PAVEMENT	SY	10,000		
20	5-04	REMOVE AND REPLACE HMA SPEED HUMP, COMPLETE	EA	6		
21	7-05	ADJUST MANHOLE	EA	2		
22	7-12	ADJUST WATER VALVE TO GRADE	EA	6		
23	7-17	ADJUST SANITARY SEWER MANHOLE	EA	8		
24	8-01	EROSION CONTROL AND WATER POLLUTION PREVENTION	LS	1		
25	8-02	SEEDING, FERTILIZING, AND MULCHING	SY	4		
26	8-02	BARK OR WOOD CHIP MULCH	SY	4		
27	8-02	PROPERTY RESTORATION	FA	1	\$2,000.00	\$2,000.00
28	8-04	CEMENT CONC. TRAFFIC CURB AND GUTTER	LF	160		
29	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	80		
30	8-13	MONUMENT CASE AND COVER	EA	2		
31	8-13	ADJUST MONUMENT CASE AND COVER	EA	1		
32	8-14	CEMENT CONC. SIDEWALK	SY	8		
33	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL	EA	4		
34	8-20	INDUCTION LOOP VEHICLE DETECTION SYSTEM	LS	1		
35	8-22	PAINT LINE	LF	88		
36	8-22	PLASTIC STOP LINE	LF	32		
37	8-22	PLASTIC CROSSWALK LINE	SF	60		
38	8-22	PLASTIC TRAFFIC ARROW	EA	1		

39	8-22	PAINTED BICYCLE LANE SYMBOL	EA	33		
40	8-22	REMOVING PAVEMENT MARKINGS	LS	1		
41	8-23	TEMPORARY PAVEMENT MARKING - SHORT DURATION	LF	100		
42	8-23	TEMPORARY MISC. PAVEMENT MARKING - SHORT DURATION	EA	34		
43	8-23	TEMPORARY STOP LINE - SHORT DURATION	LF	32		
44	8-23	TEMPORARY CROSSWALK LINE - SHORT DURATION	SF	60		
45	8-33	RESOLUTION OF UTILITY CONFLICTS	FA	1	\$2,000.00	\$2,000.00

TOTAL – 18TH AVE S \$

S 369TH ST: ROADWAY IMPROVEMENTS

All unit prices shall include applicable sales tax (Roadway Improvements)

Item No.	Spec. Div.	Bid Item Description	Unit	Plan Qty	Unit Price	Amount
1	1-04	MINOR CHANGE	FA	1	\$10,000.00	\$10,000.00
2	1-04	ADA FEATURES SURVEYING	LS	1		
3	1-05	ROADWAY SURVEYING	LS	1		
4	1-06	MATERIAL TESTING	LS	1		
5	1-07	SPCC PLAN	LS	1		
6	1-09	MOBILIZATION	LS	1		
7	1-10	TRAFFIC CONTROL SUPERVISOR	LS	1		
8	1-10	FLAGGERS	HR	475		
9	1-10	OTHER TRAFFIC CONTROL LABOR	HR	50		
10	1-10	PORTABLE CHANGEABLE MESSAGE SIGN	HR	350		

11	1-10	OTHER TEMPORARY TRAFFIC CONTROL DEVICES	LS	1		
12	1-10	WORK ZONE SAFETY CONTINGENCY	FA	1	\$3,200.00	\$3,200.00
13	2-01	ROADSIDE CLEANUP	FA	1	\$3,000.00	\$3,000.00
14	2-02	SAWCUTTING	LF	850		
15	2-03	ROADWAY EXCAVATION INCL. HAUL	CY	160		
16	4-04	CRUSHED SURFACING TOP COURSE	TN	75		
17	5-04	HMA CL. 1/2 IN. PG 58H-22	TN	3,000		
18	5-04	PLANING BITUMINOUS PAVEMENT	SY	1,100		
19	5-04	PAVEMENT REPAIR EXCAVATION INCL. HAUL	CY	350		
20	5-04	HMA FOR PAVEMENT REPAIR CL. 1/2 IN. PG 58H-22	TN	175		
21	7-05	ADJUST MANHOLE	EA	5		
22	7-05	REPLACE SOLID LOCKING RECTANGULAR FRAME AND GRATE	EA	1		
23	7-12	ADJUST WATER VALVE TO GRADE	EA	9		
24	7-17	ADJUST SANITARY SEWER MANHOLE	EA	20		
25	8-02	PROPERTY RESTORATION	FA	1	\$2,000.00	\$2,000.00
26	8-02	SOD INSTALLATION	SY	120		
27	8-02	TOPSOIL TYPE 3-WAY MIX	SY	50		
28	8-04	CEMENT CONC. TRAFFIC CURB AND GUTTER	LF	1,200		
29	8-04	CEMENT CONC. PEDESTRIAN CURB	LF	700		
30	8-09	RAISED PAVEMENT MARKER TYPE 2	HUN	0.24		
31	8-09	RAISED PAVEMENT MARKER TYPE 2B	HUN	0.10		
32	8-13	ADJUST MONUMENT CASE AND COVER	EA	22		

33	8-14	CEMENT CONC. SIDEWALK	SY	135		
34	8-14	CEMENT CONC. CURB RAMP TYPE PARALLEL	EA	32		
35	8-22	PAINT LINE	LF	425		
36	8-22	PLASTIC STOP LINE	LF	30		
37	8-23	TEMPORARY MISC. PAVEMENT MARKING - SHORT DURATION	LF	425		
38	8-23	TEMPORARY STOP LINE - SHORT DURATION	LF	30		
TOTAL – S 369TH ST						\$

BID SUMMARY	
ITEM	BID AMOUNT
CAMPUS HIGHLANDS WEST	\$
CAMPUS HIGHLANDS EAST	\$
12TH AVE SW	\$
SCARBOROUGH	\$
EMBERWOOD	\$
18TH AVE S	\$
S 369TH ST	\$
TOTAL BID AMOUNT <i>(including Washington State sales tax, all other government taxes, assessments and charges)</i>	\$

The documents incorporated by reference, as if fully set forth, are the Advertisement for Bids, the Instructions to Bidders and Checklists, the Contractor's Bid Proposal (including all forms and supplemental information listed on the Bidders Checklist), the Contract Documents (including Project Plans, Specifications, and all Appendices,

Amendments, and Supplemental Reports & Information), the Contract Provisions (including all forms and supplemental information listed on the Contract Checklist), the version of the Washington State Standard Specifications for Road, Bridge, and Municipal Construction identified herein, and any other documents provided to bidders and/or referenced in or referred to by the Contract Documents.

Pursuant to and in compliance with the Advertisement for Bids for the Project, and other documents relating thereto, the undersigned has carefully examined all of the bid and contract documents, considered conditions which may affect the delivery, supply and maintenance for the Project, and hereby proposes to furnish all labor, materials and perform all work as required in strict accordance with the contract documents, for the referenced bid amount, inclusive of Washington State sales tax and all other government taxes, assessments and charges as required by law.

NON-COLLUSION AFFIDAVIT

By signing this proposal, the undersigned acknowledges that the person(s), firm, association, or corporation has (have) not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this project.

To report rigging activities, call 1-800-424-9071. The U.S. Department of Transportation (USDOT) operates the toll-free hotline Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidder collusion, or other fraudulent activities should use the hotline to report such activities. The hotline is part of USDOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the USDOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

CONFLICTS OF INTEREST, GRATUITIES, & NON-COMPETITIVE PRACTICES

By signing this proposal, the undersigned agrees as follows:

- (1) That it has no direct or indirect pecuniary or proprietary interest, that it shall not acquire any interest which conflicts in any manner or degree with the work, services, equipment or materials required to be performed and/or provided under this contract and that it shall not employ any person or agent having any such interests. In the event that the Contractor or its agents, employees or representatives hereafter acquires such a conflict of interest, it shall immediately disclose such interest to the City and take action immediately to eliminate the conflict or to withdraw from this contract, as the City may require; and
- (2) That no person or selling agency except bona fide employees or designated agents or representatives of the Contractor have been employed or retained to solicit or secure this contract with an agreement or understanding that a commission, percentage, brokerage, or contingent fee would be paid; and
- (3) That no gratuities in the form of entertainment, gifts or otherwise, were offered or given by the Contractor or any of its agents, employees or representatives, to any official, member or employee of the City or other governmental agency with a view toward securing this contract or securing favorable treatment with respect to the awarding or amending, or the making of any determination with respect to the performance of this contract.

AFFIDAVIT OF ELIGIBILITY

The Contractor certifies that it is properly licensed and registered under the laws of the State of Washington and has not been determined to have been in violation of RCW 50.12.070(1)(b), RCW 51.16.070(1)(b), or RCW 82.32.070(2) within the last two years. The Contractor further certifies that it has not been determined, within the last one year, to have committed any combination of two of the following violations or infractions within a five year period: (1) Violated RCW 51.48.020(1) or 51.48.103; or (2) Committed an infraction or violation under Chapter 18.27 RCW.

CERTIFICATION OF LAWFUL EMPLOYMENT

The Contractor hereby certifies that it has complied with all provisions of the Immigration and Nationality Act now or as herein after amended, 8 U.S.C. 1101 et. Seq., and that all employees, including subcontractor

employees, are lawfully permitted to perform work in the United States as provided in this agreement with the City of Federal Way.

Receipt of the following Addendums is hereby acknowledged:

Addendum No. ____	Date Issued: _____
Addendum No. ____	Date Issued: _____
Addendum No. ____	Date Issued: _____
Addendum No. ____	Date Issued: _____
Addendum No. ____	Date Issued: _____
Addendum No. ____	Date Issued: _____

The undersigned individual represents and warrants that he or she is dully authorized to execute the bid and all bid documents on behalf of any partnership, joint venture or corporation.

By: _____
Signature

_____ *Printed Name*

_____ *Title*

Subscribed and sworn to before me this ____ day of _____, 20__.

Signature of Notary

Printed name of Notary
Notary Public in and for the State of Washington
My commission expires: _____

BID BOND
2025 ASPHALT OVERLAY

OPTION 1: BID BOND DEPOSIT

Attached is a deposit in the form of a certified check, cashier’s check, or cash in the amount of \$_____, which amount is not less than five percent (5%) of the total bid.

Principal – Signature of Authorized Official *Date*

Title

—OR—

OPTION 2: BID BOND

KNOW ALL PERSONS BY THESE PRESENTS that we,
_____, as Principal, and
_____, as Surety, are held and firmly bound unto the
City of Federal Way, as Obligee, in the sum of five (5) percent of the total amount of the bid proposal for the payment of which the Principal and the Surety bond themselves, their heirs and executors, administrators, successors and assigns, jointly and severally, by these presents.

The condition of this obligation is such that if the Obligee shall make any award to the Principal for the above-mentioned Project according to the terms of the proposal or bid made by the Principal therefore, and the Principal shall duly make and enter into a contract with the Obligee in accordance with the terms of said proposal or bid and award and shall give bond for the faithful performance thereof, with Surety or Sureties approved by the Obligee; or if the Principal shall in case of failure so to do, pay and forfeit to the Obligee the penal amount of the deposit specified in the call for bids, then this obligation shall be null and void; otherwise, it shall be, and remain in full force and effect, and the Surety shall forthwith pay and forfeit to the Obligee as penalty and liquidated damages, the amount of this bond.

SIGNED, SEALED AND DATED THIS _____ DAY OF _____, 20_____.

Principal – Signature of Authorized Official

Surety – Attorney in Fact
(Attach Power of Attorney)

Title

Name and Address of Local Office/Agent of Surety Company is:

SUBCONTRACTOR LIST

CITY OF FEDERAL WAY
33325 8TH AVENUE S FEDERAL WAY, WA 98003-6325

Local Agency Subcontractor List

Prepared in compliance with RCW 39.30.060 as amended

To Be Submitted with the Bid Proposal

Project Name _____

Failure to list subcontractors with whom the bidder, if awarded the contract, will directly subcontract for performance of the work of structural steel installation, rebar installation, heating, ventilation and air conditioning, plumbing, as described in Chapter 18.106 RCW, and electrical, as described in Chapter 19.28 RCW or naming more than one subcontractor to perform the same work will result in your bid being non-responsive and therefore void.

Subcontractor(s) with whom the bidder will directly subcontract that are proposed to perform the work of structural steel installation, rebar installation, heating, ventilation and air conditioning, plumbing, as described in Chapter 18.106 RCW, and electrical as described in Chapter 19.28 RCW must be listed below. The work to be performed is to be listed below the subcontractor(s) name.

To the extent the Project includes one or more categories of work referenced in RCW 39.30.060, and no subcontractor is listed below to perform such work, the bidder certifies that the work will either (i) be performed by the bidder itself, or (ii) be performed by a lower tier subcontractor who will not contract directly with the bidder.

Subcontractor Name _____

Work to be performed _____

Subcontractor Name _____

Work to be performed _____

Subcontractor Name _____

Work to be performed _____

Subcontractor Name _____

Work to be performed _____

Subcontractor Name _____

Work to be performed _____

* Bidder's are notified that it is the opinion of the enforcement agency that PVC or metal conduit, junction boxes, etc, are considered electrical equipment and therefore considered part of electrical work, even if the installation is for future use and no wiring or electrical current is connected during the project.

DOT Form 271-015A
Revised 06/2020

CONTRACTOR WAGE LAW COMPLIANCE CERTIFICATION

FAILURE TO RETURN THIS CERTIFICATION AS PART OF THE BID PROPOSAL PACKAGE WILL MAKE THIS BID NONRESPONSIVE AND INELIGIBLE FOR AWARD.

I hereby certify, under penalty of perjury under the laws of the State of Washington, on behalf of the firm identified below that, to the best of my knowledge and belief, this firm has **NOT** been determined by a final and binding citation and notice of assessment issued by the Washington State Department of Labor and Industries or through a civil judgment entered by a court of limited or general jurisdiction to have willfully violated, as defined in RCW 49.48.082, any provision of Chapters 49.46, 49.48, and 49.52 RCW within three (3) years prior to the date of the Request for Bids.

Bidder Name: _____
Print Full Legal Name of Firm

By: _____
Signature of Authorized Person *Print Name of Person Making Certifications for Firm*

Title: _____
Title of Person Signing Certificate Place: _____
Print City and State Where Signed

Date: _____

PROPOSAL FOR INCORPORATING RECYCLED MATERIALS



APWA-WA Division 1 Committee

rev. 5/13/2022

Proposal for Incorporating Recycled Materials into the Project

In compliance with RCW 70A.205.700, the Bidder shall propose below, the total percent of construction aggregate and concrete materials to be incorporated into the Project that are recycled materials. Calculated percentages must be within the amounts allowed in Section 9-03.21(1)E, Table on Maximum Allowable Percent (By Weight) of Recycled Material, of the Standard Specifications.

Proposed total percentage: _____ percent.

Note: Use of recycled materials is highly encouraged within the limits shown above, but does not constitute a Bidder Preference, and will not affect the determination of award, unless two or more lowest responsive Bid totals are exactly equal, in which case proposed recycling percentages will be used as a tie-breaker, per the APWA GSP in Section 1-03.1 of the Special Provisions. Regardless, the Bidder's stated proposed percentages will become a goal the Contractor should do its best to accomplish. Bidders will be required to report on recycled materials actually incorporated into the Project, in accordance with the APWA GSP in Section 1-06.6 of the Special Provisions.

Bidder: _____

Signature of Authorized Official: _____

Date: _____

RETAINAGE OPTION

IDENTIFICATION AND DESCRIPTION

Project Title: 2025 Asphalt Overlay

RFB No: 25-001

Contractor: _____

GENERAL REQUIREMENTS

1. In accordance with applicable State Statutes, a contract retainage not to exceed five percent of the moneys earned by the contractor will be reserved by the City.
2. All investments selected are subject to City approval.
3. The final disposition of the contract retainage will be made in accordance with applicable State Statutes.

BIDDER'S INSTRUCTIONS

If deemed to be the lowest responsive, responsible bidder and pursuant to RCW 60.28.011, I hereby notify the City of Federal Way of my instructions for the retainage withheld under the terms of the contract and further request the appropriate forms be included in the Contract documents prepared for execution.

- Option 1:** Retained in a fund by the City of Federal Way. No interest will be paid to the contractor.
- Option 2:** Deposited in an interest bearing account in a bank, mutual savings bank, or savings and loan association. Interest paid to the contractor. Contractor shall have the bank (or other) execute a separate "City of Federal Way Retainage Bank Acceptance Agreement" upon contract award. The City will provide the agreement to the Contractor if this option is selected.
- Option 3:** Placed in escrow with a bank or trust company. Contractor shall execute, and have escrow account holder execute a separate "City of Federal Way Construction Retainage Escrow Agreement" upon contract award. The City will provide the agreement to the Contractor if this option is selected. All investments are subject to City approval. The cost of the investment program, and risk thereof, is to be borne entirely by the contractor.
- Option 4:** Contractor shall submit a "Retainage Bond" on City-provided form included in these Contract Documents.

Signature

Date

PUBLIC WORKS CONTRACT

THIS PUBLIC WORKS CONTRACT ("Contract") is dated effective this ____ day of _____, 20__ and is made by and between the City of Federal Way, a Washington municipal corporation ("City or Owner"), and _____, a _____ ("Contractor"), for the project known as the 2025 Asphalt Overlay (the "Project").

A. The City desires to retain an independent contractor to furnish all labor and materials necessary to perform work necessary to complete the Project; and

B. The Contractor has the requisite skill and experience to perform such work.

NOW, THEREFORE, the parties ("Parties") agree to the following terms and conditions:

1. SERVICES BY CONTRACTOR

Contractor shall perform all Work and furnish all tools, materials, supplies, equipment, labor and other items incidental thereto necessary for the construction and completion of the Project. Contractor shall perform the Work in a manner consistent with accepted practices for other properly licensed contractors and in accordance with and as described in the Contract Documents, which Work shall be completed to the City's satisfaction, within the time period prescribed by the City and pursuant to the direction of the Mayor or his or her designee.

2. TERM

2.1 This Contract shall commence on the effective date of this Contract and continue until the Project is formally accepted as complete by the City Council, Notice of Project Completion is filed with State agencies, and all bonds for the Project are released by the City.

2.2 The Contractor must complete the Work in accordance with the number of Working Days for the Project as identified in the Contract Documents. With regard to obtaining Substantial Completion and the Completion Date by the Contractor, time is of the essence. In the event the Work is not substantially completed within the time specified in the Contract Documents, Contractor agrees to pay to the City liquidated damages in the amount set forth in the Contract Documents. The parties acknowledge that delays inconvenience the public and cost taxpayers undue sums of money, adding time needed for administration, inspection, and supervision of the Project and diverting City resources from other projects and obligations.

2.3 If the Contractor is unreasonably delayed by others, notification shall be made in writing to the Engineer in accordance with the Contract Documents. Any request for a time extension or additional compensation (including expectancy or consequential damages) allegedly resulting from such delay shall be made in accordance with the procedures of the Contract Documents. Failure to follow the notice procedures in the Contract Documents is a full and complete waiver of Contractor's right to additional time, money, damages, or other relief (including expectancy or consequential damages) as a result of the event or condition giving rise to such request.

3. COMPENSATION

3.1 In consideration of the Contractor performing the Work, the City agrees to pay the Contractor an amount not to exceed _____ and ____/100 Dollars (\$ _____), which amount shall constitute full and complete payment by the City ("Total Compensation"). The Contractor shall be solely responsible for the payment of any taxes imposed by any lawful jurisdiction as a result of the performance and payment of this Contract.

3.2 The City shall pay the Contractor for Work performed under this Contract as detailed in the Bid Proposal, which is incorporated herein and made a part hereof by this reference, and as detailed in the Contract Documents. The City shall have the right to withhold payment to the Contractor for any of the Work not completed in a satisfactory manner, in the City's sole and absolute discretion, which shall be withheld until such time as Contractor modifies or repairs the Work so that the Work is acceptable to the City. Payment to the Contractor for partial estimates, final estimates, and retained percentages shall be subject to controlling laws.

3.3 In addition to the requirements set forth in the Contract Documents, the Contractor shall maintain Project cost records by cost codes and shall contemporaneously segregate and separately record, at the time incurred, all costs (1) directly associated with each work activity, (2) directly or indirectly resulting from any event, occurrence, condition, or direction for which Contractor seeks an adjustment in Contract price Contract time, or related to any other Claim or protest. Any work performed for which Contractor intends to seek an adjustment in Contract Price or Contract Time, or related to any other Claim or protest, shall be recorded on the same day the work is performed and kept separate so as to distinguish it from Contract Work.

4. INDEPENDENT CONTRACTOR

4.1 It is the intention and understanding of the Parties that the Contractor shall be an independent contractor and that the City shall be neither liable nor obligated to pay Contractor sick leave, vacation pay or any other benefit of employment, nor to pay any social security or other tax which may arise as an incident of employment. The Contractor shall not conduct itself as nor claim to be an officer or employee of the City. The Contractor shall pay all income and other taxes due. Industrial or any other insurance that is purchased for the benefit of the City, regardless of whether such may provide a secondary or incidental benefit to the Contractor, shall not be deemed to convert this Agreement to an employment contract. It is recognized that Contractor may or will be performing professional services during the Term for other parties; provided, however, that such performance of other services shall not conflict with or interfere with Contractor's ability to perform the Services. Contractor agrees to resolve any such conflicts of interest in favor of the City. Nothing contained in this Contract shall create a contractual or direct relationship with or a cause of action in favor of a Subcontractor or third party against the City, or by the Contractor against the Engineer, or against any of their agents, employees, engineers, or consultants.

4.2 If the Contractor is a sole proprietorship or if this is a contract with an individual, the contractor agrees to notify the City and complete any required form if the Contractor retired under a State of Washington retirement system and agrees to indemnify any losses the City may sustain through the Contractor's failure to do so.

5. INDEMNIFICATION

5.1 Contractor Indemnification.

5.1.1 The Contractor shall indemnify, defend, and hold the City, its elected officials, officers, employees, agents, consultants, and volunteers (collectively "the Indemnified Parties") harmless from any costs or losses, and pay and damages or judgments, related to any claim brought by any person employed in any capacity by the Contractor or subcontractor or supplier (of any tier) performing the Work, with respect to the payment of wages, salaries, or other compensation or benefits including but not limited to benefits such as medical, health, retirement, vacation, sick leave, etc.

5.1.2. To the fullest extent permitted by law, the Contractor shall defend, release, indemnify, and hold harmless the City and the Indemnified Parties for, from, and against any and all claims, demands, losses, costs, damages, suits, actions, expenses, fines, penalties, response costs, and liabilities (including costs and all attorney and expert fees and internal personnel costs of investigation) of whatsoever kind or nature to the extent arising from, resulting from, connected with, or incident to the Contractor's performance or failure to perform this Contract or the Work or its breach of this Contract; provided, however, that if the provisions of RCW 4.24.155 apply to the Work and any injuries to persons or property arising out of the performance of this Contract are caused by or result from the concurrent negligence of the Contractor or its subcontractors, agents, employees, or anyone for whom they are legally liable, and an Indemnified Party, the indemnification and defense obligations under this Section 5.1.2 apply only to the extent of the negligence of the Contractor, its subcontractors, agents, employees, and anyone for whom they are legally liable.

5.1.3 Contractor specifically assumes potential liability for actions brought by the Contractor's own employees or former employees against any Indemnified Party, and for that purpose Contractor waives any immunity that may be granted to it under the Washington State Industrial Insurance Act, Title 51 RCW. Contractor's indemnification shall not be limited in any way by any limitation on the amount of damages, compensation or benefits payable to or by any third party under workers' compensation acts, disability benefit acts or any other benefits acts or programs. Provided, however, the Contractor's waiver of immunity by the

provisions of this paragraph extends only to claims against the Contractor by any Indemnified party, and does not include, or extend to, any claims by the Contractor's employee directly against the Contractor. The Contractor recognizes that this waiver was specifically entered into.

5.2 Contractor Release. Any deviation, alteration, variation, addition, or omission in the Work by Contractor from the Contract Documents shall preclude Contractor from bringing any Claim or request for additional time or compensation on the basis of an alleged defect or error in the Contract Documents related to or arising, in any way, from that deviation, alteration, variation, addition, or omission. The Contractor further warrants that any alteration, variation, deletion, or omission fully complies with or exceeds all requirements of the Contract Documents and assumes all risk thereof.

5.3 Survival. The provisions of this Section shall (1) survive the expiration or termination of this Contract with respect to any event occurring prior to such expiration or termination, final payment hereunder, and any applicable statute of repose with respect to claims, fines, costs or damages brought or made against any Indemnified Party; (2) shall not be limited by RCW 4.16326(g); and (3) are in addition to any other rights or remedies which the City and/or any of the Indemnified Parties may have by law or under this Contract.

5.4 Offset. In the event of any claim or demand made against any Indemnified Party hereunder, the City may, in its sole discretion, reserve, retain or apply any monies due to the Contractor under the Contract or any other agreement or contract with the City for the purpose of resolving such claims; provided, however, that the City may, in the City's sole discretion, release such funds if the Contractor provides the City with adequate assurance of the protection of the City's and the other Indemnified Parties interests.

5.5 The Contractor shall ensure that each Subcontract includes a provision requiring each Subcontractor to indemnify and defend the City and the Indemnified Parties in the same manner, to the same extent, and for the same duration as Contractor agrees to indemnify and defend the City and the Indemnified Parties in this Section 5.

6. OWNERSHIP OF DOCUMENTS

All originals and copies of work product, including plans, sketches, layouts, designs, design specifications, records, files, computer disks, magnetic media, all finished or unfinished documents or material which may be produced or modified by Contractor while performing the Work, whether or not required to be furnished to the City, shall become the property of the City, shall be delivered to the City at its request, and may be used by the City without restriction.

7. PATENTS, COPYRIGHTS, AND RIGHTS IN DATA

7.1 Any patentable result or material suitable for copyright arising out of this Contract shall be owned by and made available to the City for public use, unless the City shall, in a specific case where it is legally permissible, determine that it is in the public interest that it not be so owned or available.

7.2 The Contractor agrees that the ownership of any plans, drawings, designs, specifications, computer programs, technical reports, operating manuals, calculations, notes and other work submitted or which is specified to be delivered under this Contract, whether or not complete (referred to in this subsection as "Subject Data"), is hereby irrevocably transferred and assigned to the City and shall be vested in the City or such other local, state or federal agency, if any, as may be provided by separate contract with the City. The Contractor shall execute and deliver such instruments and take such other action(s) as may be requested by the City to perfect or protect the City's rights to such Subject Data and work product, and to perfect the assignments and transfers contemplated in Sections 6 and 7.

7.3 All such Subject Data furnished by the Contractor pursuant to this Contract, other than documents exclusively for internal use by the City, shall carry such notations on the front cover or a title page (or in such case of maps, in the same block) as may be requested by the City. The Contractor shall also place their endorsement on all Subject Data furnished by them. All such identification details shall be subject to approval by the City prior to printing.

7.4 The Contractor shall ensure that substantially the foregoing paragraphs in Sections 6 and 7 are included in each subcontract for the work on the Project.

8. GENERAL PROVISIONS

8.1 Entire Contract. The Contract Documents contain all of the agreements of the Parties with respect to any matter covered or mentioned in this Contract and no prior agreements or understandings pertaining to any such matters shall be effective for any purpose. In entering into this Contract, neither party has relied upon any statement, estimate, forecast, projection, representation, warranty, action or agreement of the other party except for those expressly contained in the Contract Documents.

8.2 Documents. The documents incorporated by reference, as if fully set forth in this Contract, are the Advertisement for Bids, the Instructions to Bidders and Checklists, the Contractor's Bid Proposal (including all forms and supplemental information listed on the Bidders Checklist), the Contract Documents (including Project Plans, Specifications, and all Appendices, Amendments, and Supplemental Reports & Information), the Contract Provisions (including all forms and supplemental information listed on the Contract Checklist), the version of the Washington State Standard Specifications for Road, Bridge, and Municipal Construction identified herein, and any other documents provided to bidders and/or referenced in or referred to by the Contract Documents.

8.3 Modification. No provisions of this Contract, including this provision, may be amended or added to except by agreement in writing signed by the Parties or their respective successors in interest in accordance with the Contract Documents.

8.4 Change Orders. In addition to its rights under the Contract Documents, the City may unilaterally issue a Change Order at any time making changes within the general scope of the Contract, without invalidating the Contract and without providing notice to sureties. The City's issuance of a unilateral Change Order shall not be construed as a waiver of any rights afforded the City, including its right to reject a prior protest or request for change or Claim due to untimeliness or the Contractor's failure to fully comply with the requirements of the Contract Documents, or to void the unilateral Change Order due to unilateral mistake, misrepresentation, or fraud.

8.5 Total Cost Method / Claims. In no event shall a Total Cost Method or a modified Total Cost Method be used by the Contractor to calculate any adjustments to the Contract price. For the purpose of this provision, any cost method, or variety of cost methods, using the difference between the actual cost of the Work and the Bid or Contract price of the Work to calculate any additional compensation or money owed to the Contractor shall be considered a Total Cost Method. In addition, the City shall not be responsible for, and the Contractor shall not be entitled to, any compensation for unallowable costs. Unallowable costs include, but are not limited to: (i) interest or attorneys' fees, except as mandated by statute; (ii) Claim preparation or filing costs; (iii) the costs of preparing notices or protests; (iv) lost profits, lost income, or lost earnings; (v) costs for idle equipment when such equipment is not at the Site, has not been employed in the Work, or is not scheduled to be used at the Site; (vi) claims consulting costs; (vii) expert fees and costs; (viii) loss of other business; and/or (ix) any other special, consequential, expectancy, incidental, or indirect damages incurred by the Contractor, Subcontractors, or suppliers.

8.6 Warranties and Guarantees. In addition to the requirements of the Contract Documents, the Contractor warrants that all portions of the Work that will be covered by a manufacturer's or supplier's guarantee or warranty shall be performed in such a manner so as to preserve all rights under such guarantees or warranties. If the City attempts to enforce a claim based upon a manufacturer's or supplier's guarantee or warranty and such manufacturer or supplier refuses to honor such guarantee or warranty based, in whole or in part, on a claim of defective installation by the Contractor or a Subcontractor, the Contractor shall be responsible for any resulting loss or damage, and repairs, incurred by the City as a result of the manufacturer's or supplier's refusal to honor such guarantee or warranty. This obligation survives termination of this Contract.

8.7 Full Force and Effect. Any provision of this Contract, which is declared invalid, void or illegal, shall in no way affect, impair, or invalidate any other provision hereof and such other provisions shall remain in full force and effect.

8.8 Assignment. The Contractor shall not transfer or assign, in whole or in part, any or all of its obligations and rights hereunder without the prior written consent of the City. In the event the City consents to any such assignment or transfer, such consent shall in no way release the Contractor from any of its obligations or liabilities under this Contract.

8.9 Successors In Interest. Subject to the preceding Subsection, this Contract shall be binding upon and inure to the benefit of the Parties' successors in interest, heirs and assigns.

8.10 Time Limitation and Venue. For the convenience of the parties to the Contract it is mutually agreed by the parties that any claims, causes of action, or disputes which the Contractor has against the City arising from the Contract shall be brought within the following time period: (i) 180 calendar days from the date of Substantial Completion for those claims, causes of action, or disputes arising prior to the date of Substantial Completion, and (ii) 180 calendar days from the date of Final Acceptance of the Contract by the City for those claims, causes of action, or dispute arising after the date of Substantial Completion. It is further agreed that the venue for any claim, cause of action, or dispute related to this Contract shall be King County, Washington, which shall have exclusive jurisdiction over any such case, controversy, or dispute. The parties understand and agree that the Contractor's failure to bring suit within the time period provided, shall be a complete bar to any such claims or causes of action. It is further mutually agreed by the parties that when any claims, causes of action, or disputes which the Contractor asserts against the City arising from the Contract are filed with the City or initiated in court, the Contractor shall permit the City to have timely access to any records deemed necessary by the City to assist in evaluating the claims, action, or dispute.

8.11 No Waiver. Failure of the City to declare any breach or default immediately upon occurrence thereof, or delay in taking any action in connection with, shall not waive such breach or default. Failure of the City to declare one breach or default does not act as a waiver of the City's right to declare another breach or default.

8.12 Sole Authority/Discretion/Judgment. Where the Contract Documents provide the City or its Engineer with "sole" authority, discretion, or judgment, such authority, discretion, or judgment shall be considered unconditional and absolute.

8.13 Governing Law. This Contract shall be made in and shall be governed by and interpreted in accordance with the laws of the State of Washington.

8.14 Authority. Each individual executing this Contract on behalf of the City and Contractor represents and warrants that such individuals are duly authorized to execute and deliver this Contract on behalf of the Contractor or City.

8.15 Engineer. The Engineer is the City's representative who directly supervises the engineering and administration of a construction Contract. The Engineer's authorities, duties, and responsibilities are limited to those specifically identified in the Contract Documents. Designation of an individual or entity as the Engineer for the Project is solely to identify the representative of the City as the entity to act as the Engineer as described in the Contract Documents. Using the term "engineer" does not imply that such entity or person is a licensed professional engineer or an engineering company and does not import any additional obligations upon the actions of the Engineer that may govern licensed professional engineers when performing engineering services.

The Engineer for this Project is designated as: Jonathan Strong, EIT

8.16 Notices. Any notices required to be given to Contractor or to the Engineer shall be delivered to the Parties at the addresses set forth below. Any notices may be delivered personally to the addressee of the notice or may be deposited in the United States mail, postage prepaid, to the address set forth herein. Any notice so posted in the United States mail shall be deemed received three (3) days after the date of mailing.

CONTRACTOR: Company
 Attn: Individual to receive notices
 Street Address

City, State, Zip

ENGINEER: City of Federal Way
Attn: Jonathan Strong EIT
33325 8th Ave S
Federal Way, WA 98003

8.17 Captions. The respective captions of the Sections of this Contract are inserted for convenience of reference only and shall not be deemed to modify or otherwise affect in any respect any of the provisions of this Contract.

8.18 Performance. Time is of the essence of this Contract and each and all of its provisions in which performance is a factor. Adherence to completion dates is essential to the Contractor's performance of this Contract.

8.19 Compliance with Ethics Code. If a violation of the City's Ethics Resolution No. 91-54, as amended, occurs as a result of the formation and/or performance of this Contract, this Contract may be rendered null and void, at the City's option.

9. PERFORMANCE/PAYMENT BOND

Pursuant to RCW 39.08.010, the Contractor's payment and performance bonds must be conditioned upon: (i) faithful performance of all of the provisions of the Contract, including warranty obligations; (ii) the payment of all laborers, mechanics, Subcontractors, and Suppliers, and all persons who supply such persons with provisions or supplies in carrying out the Work; and (iii) payment of any taxes, liabilities, increases, or penalties incurred on the Project under Titles 50, 51, and 82 RCW which may be due on (a) projects referred to in RCW 60.28.011(1)(b), and (b) projects for which the bond is conditioned on the payment of such taxes, liabilities, increases, or penalties. Contractor's obligations under this Contract shall not be limited to the dollar amount of the bond.

DATED the day and year set forth above.

CITY OF FEDERAL WAY:

CONTRACTOR:

Jim Ferrell, Mayor
33325 8th Avenue South
Federal Way, WA 98003-6325

Signature of Authorized Individual

ATTEST:

Printed Name of Authorized Individual

Stephanie Courtney, MMC, CPRO, City Clerk

Street Address

APPROVED AS TO FORM:

City, State, Zip

J. Ryan Call, City Attorney

NOTARY OF CONTRACTOR'S SIGNATURE:

STATE OF WASHINGTON)
) ss.
COUNTY OF _____)

STAFF - USE FOR CORPORATE NOTARY OR DELETE

On this day personally appeared before me _____, to me known to be the _____ of _____ that executed the within and foregoing instrument, and acknowledged the said instrument to be the free and voluntary act and deed of said corporation, for the uses and purposes therein mentioned, and on oath stated that he or she was authorized to execute said instrument and that the seal affixed, if any, is the corporate seal of said corporation.

GIVEN under my hand and official seal this _____ day of _____, 20__.

Notary's signature _____
Notary's printed name _____
Notary Public in and for the State of Washington.
My commission expires _____

STAFF - USE FOR INDIVIDUAL NOTARY OR DELETE

On this day personally appeared before me, _____, to me known to be the individual, or individuals described in and who executed the within and foregoing instrument, and acknowledged that he/she/they signed the name as his/her/their free and voluntary act and deed, for the uses and purposes therein mentioned.

GIVEN under my hand and official seal this _____ day of _____, 20__.

Notary's signature _____
Notary's printed name _____
Notary Public in and for the State of Washington.
My commission expires _____

STAFF - USE FOR LIMITED LIABILITY NOTARY OR DELETE.

On this day personally appeared before me, _____, that executed the within and foregoing instrument, and acknowledged the said instrument to be the free and voluntary act and deed of said limited liability company, for the uses and purposes therein mentioned, and on oath stated that he or she was authorized to execute said instrument.

GIVEN under my hand and official seal this _____ day of _____, 20__.

Notary's signature _____
Notary's printed name _____
Notary Public in and for the State of Washington.
My commission expires _____

SAMPLE CONTRACT CHANGE ORDER

PROJECT NUMBER	AGREEMENT NUMBER	CHANGE ORDER NUMBER	EFFECTIVE DATE
----------------	------------------	---------------------	----------------

PROJECT TITLE	CONTRACTOR
---------------	------------

SUMMARY OF PROPOSED CHANGES:

This Change Order covers the work changes summarized below:

The time provided for completion in the Contract is

- Unchanged
- Increased by ___ Working Day(s)
- Decreased by ___ Working Day(s)

This Document shall become an Amendment to the Contract and all provisions of the Contract not amended herein will apply to this Change Order.

Will this change affect expiration or extent of Insurance coverage? Yes No
If "Yes" Will the Policies Be Extended? Yes No

MODIFICATIONS TO UNIT PRICES:

<u>ITEM NO.</u>	<u>ITEM</u>	<u>QTY</u>	<u>PREVIOUS UNIT PRICE</u>	<u>REVISED UNIT PRICE</u>	<u>ADD OR DELETE</u>
-----------------	-------------	------------	--------------------------------	-------------------------------	----------------------

THESE ITEMS ARE APPROXIMATE OR ESTIMATED QUANTITIES INVOLVED IN THIS CHANGE:

<u>ITEM NO.</u>	<u>ITEM</u>	<u>QTY</u>	<u>UNIT PRICE</u>	<u>ADD OR DELETE</u>
-----------------	-------------	------------	-------------------	----------------------

TOTAL NET CONTRACT: INCREASE \$ DECREASE \$

DEPARTMENT RECAP TO DATE:

ORIGINAL CONTRACT AMOUNT	\$ _____
PREVIOUS CHANGE ORDERS	\$ _____
THIS CHANGE ORDER	\$ _____
NEW CONTRACT AMOUNT	\$ _____

STATEMENT:

Payment for the above work will be in accordance with applicable portions of the standard specifications, and with the understanding that all materials, workmanship and measurements shall be in accordance with the provisions of the standard specifications, the contract plans, and the special provisions governing the types of construction. The execution of this Change Order shall constitute full satisfaction and a waiver of any and all

claims by the Contractor arising out of, or relating in any way to, the Work identified, to be performed, or deleted pursuant to Change Order except as specifically described in this Change Order.

CONTRACTOR'S SIGNATURE DATE

PUBLIC WORKS DIRECTOR DATE

*Contract Change Order
provided for Contractor's
reference. Change orders
executed during the project
will use this form.*

CERTIFICATE OF INSURANCE

*Contractor's Certificate of
Insurance to be inserted
here during Contract
Execution*

LOCAL OFFICE/AGENT OF SURETY:

Name

Street Address

City, State, Zip

Telephone

BOND NO.: _____

APPROVED AS TO FORM: _____
J. Ryan Call, City Attorney

RETAINAGE BOND TO CITY OF FEDERAL WAY
2025 ASPHALT OVERLAY

KNOW ALL PERSONS BY THESE PRESENTS that we, the undersigned, _____, as principal ("Principal"), and _____, a Corporation organized and existing under the laws of the State of _____, as a surety Corporation, and qualified under the laws of the State of Washington to become surety upon bonds of Contractors with Municipal Corporations, as surety ("Surety"), are jointly and severally held and firmly bonded to the City of Federal Way ("City") in the penal sum of: _____ (\$ _____) for the payment of which sum we bind ourselves and our successors, heirs, administrators or personal representatives, as the case may be.

A. This obligation is entered into in pursuant to the statutes of the State of Washington and the ordinances, regulations, standards and policies of the City, as now existing or hereafter amended or adopted.

B. Pursuant to proper authorization, the Mayor is authorized to enter into a certain contract with the Principal, providing for the above-referenced Project, which contract is incorporated herein by this reference ("Contract"), and

C. Pursuant to State law, Chapter 60.28 RCW, the City is required to reserve from the monies earned by the Principal pursuant to the contract, a sum not to exceed five percent (5%), said sum to be retained by the City as a trust fund for the protection and payment of any person or persons, mechanic, subcontractor or material men who shall perform any labor upon such contract or the doing of such work, and all persons who shall supply such person or persons or subcontractors with provisions and supplies for the carrying on of such work, and the State with the respect to taxes imposed pursuant to Title 82 RCW which may be due from said Principal. Every person performing labor or furnishing supplies towards completion of said improvement or work shall have a lien on said monies so reserved, provided that such notice of the lien of such claimant shall be given in the manner and within the time provided in RCW 39.08.030 as now existing and in accordance with any amendments that may hereafter be provided thereto; and

D. State law further provides that with the consent of the City, the Principal may submit a bond for all or any portion of the amount of funds retained by the public body in a form acceptable to the public body conditioned upon such bond any proceeds therefrom being made subject to all claims and liens and in the same manner and priority as set forth retained percentages pursuant to Chapter 60.28 RCW; and

E. The Principal has accepted, or is about to accept, the Contract, and undertake to perform the work therein provided for in the manner and within the time set forth, for the amount of \$ _____; and

F. The City is prepared to release any required retainage money previously paid by the Principal prior to acceptance and successful operation and fulfillment of all other terms of said contract upon being indemnified by these presents,

NOW, THEREFORE, if the Principal shall perform all the provisions of the Contract in the manner and within the time period prescribed by the City, or within such extensions of time as may be granted under the Contract, and shall pay all laborers, mechanics, subcontractors and material men or women, and all persons who shall supply the Principal or subcontractors with provisions and supplies for the carrying on of said work, and if the Principal shall pay to the State all taxes imposed pursuant to Title 82 RCW which may be due from such Principal as a result of this contract then and in the event this obligation shall be void; but otherwise it shall be and remain in full force and effect.

And the Surety, for value received, hereby further stipulates and agrees that no change, extension of time, alteration or addition to the terms of the Contract or to the work to be performed thereunder or the specifications accompanying the same shall in any way affect its obligation on this bond, and it does hereby waive notice of any change, extension of time, alterations or additions to the terms of the Contract or to the Work.

The Surety hereby agrees that modifications and changes may be made in the terms and provisions of the Contract without notice to Surety, and any such modifications or changes increasing the total amount to be paid the Principal shall automatically increase the obligation of the Surety on this Retainage Bond in a like amount, such increase, however, not to exceed twenty-five percent (25%) of the original amount of this bond without consent of the Surety.

Within forty-five (45) days of receiving notice that the Principal has defaulted on all or part of the terms of the Contract, the Surety shall make written commitment to the City that it will either: (a) cure the default itself within a reasonable time period, or (b) tender to the City, the amount necessary for the City to remedy the default, including legal fees incurred by the City, or (c) in the event that Surety's evaluation of the dispute is not complete or in the event the Surety disputes the City's claim of default, the Surety shall notify the City of its finding and its intent, if any, to interplead. The Surety shall then fulfill its obligations under this bond, according to the option it has elected. Should Surety elect option (a) to cure the default, the penal sum of the Bond shall be reduced in an amount equal to the costs actually incurred by the Surety in curing the default. If the Surety elects option (b), then upon completion of the necessary work, the City shall notify the Surety of its actual costs. The City shall return, without interest, any overpayment made by the Surety and the Surety shall pay to the City any actual costs which exceed the City estimate, limited to the bond amount. Should the Surety elect option (c), the Parties shall first complete participation in mediation, described in the below paragraph, prior to any interplead action.

In the event a dispute should arise between the Parties to this Bond with respect to the City's declaration of default by the Principal, the Parties agree to participate in at least four hours of mediation to resolve said dispute. The Parties shall proportionately share in the cost of the mediation. The mediation shall be administered by Judicial Dispute Resolution, LLC, 1425 Fourth Avenue, Suite 300, Seattle, Washington 98101. The Surety shall not interplead prior to completion of the mediation.

The parties have executed this instrument under their separate seals this ____ day of _____, 20____, the name and corporate seal of each corporate party hereto affixed, and these presents duly signed by its undersigned representatives pursuant to authority of its governing body.

CORPORATE SEAL:

PRINCIPAL:

By: _____

Title: _____

Address: _____

CERTIFICATE AS TO CORPORATE SEAL

I hereby certify that I am the (Assistant) Secretary of the Corporation named as Principal in the within bond; that _____, who signed the said bond on behalf of the Principal, was _____ of said Corporation; that I know his or her signature thereto is genuine, and that said bond was duly signed, sealed, and attested for and in behalf of said Corporation by authority of its governing body.

Secretary of Principal

CORPORATE SEAL:

SURETY:

By: _____
Attorney-in-Fact
(Attach Power of Attorney)

Title: _____

Address: _____

CERTIFICATE AS TO CORPORATE SEAL

I hereby certify that I am the (Assistant) Secretary of the Corporation named as Surety in the within bond; that _____, who signed the said bond on behalf of the Surety, was _____ of the said Corporation; that I know his or her signature thereto is genuine, and that said bond was duly signed, sealed, and attested for and in behalf of said Corporation by authority of its governing body.

Secretary of Surety

APPROVED AS TO FORM:

J. Ryan Call, City Attorney

INTRODUCTION TO THE SPECIAL PROVISIONS

(January 4, 2024 APWA GSP, Option A)

The work on this project shall be accomplished in accordance with the Standard Specifications for Road, Bridge and Municipal Construction, 2025 edition, as issued by the Washington State Department of Transportation (WSDOT) and the American Public Works Association (APWA), Washington State Chapter (hereafter “Standard Specifications”). The Standard Specifications, as modified or supplemented by these Special Provisions, all of which are made a part of the Contract Documents, shall govern all of the Work.

These Special Provisions are made up of both General Special Provisions (GSPs) from various sources, which may have project-specific fill-ins; and project-specific Special Provisions. Each Provision either supplements, modifies, or replaces the comparable Standard Specification, or is a new Provision. The deletion, amendment, alteration, or addition to any subsection or portion of the Standard Specifications is meant to pertain only to that particular portion of the section, and in no way should it be interpreted that the balance of the section does not apply.

The GSPs are labeled under the headers of each GSP, with the effective date of the GSP and its source. For example:

(March 8, 2013 APWA GSP)
(April 1, 2013 WSDOT GSP)
(May 1, 2013 CFW GSP) City of Federal Way Special Provision

Project specific special provisions are labeled without a date as such:
*(*****)*

Also incorporated into the Contract Documents by reference are:

- *Manual on Uniform Traffic Control Devices for Streets and Highways*, currently adopted edition, with Washington State modifications, if any
- *Standard Plans for Road, Bridge and Municipal Construction*, WSDOT Manual M21-01, current edition
- *City of Federal Way Public Works Development Standards*
- *National Electric Code*, current edition

Contractor shall obtain copies of these publications, at Contractor’s own expense.

DIVISION 1 GENERAL REQUIREMENTS

DESCRIPTION OF WORK

(March 13, 1995 WSDOT GSP)

This Contract provides for the improvement of the 2025 Asphalt Overlay Improvements and other work, all in accordance with the attached Contract Plans, these Contract Provisions, and the Standard Specifications.

1-01.3 Definitions

(January 19, 2022 APWA GSP)

Delete the heading **Completion Dates** and the three paragraphs that follow it, and replace them with the following:

Dates

Bid Opening Date

The date on which the Contracting Agency publicly opens and reads the Bids.

Award Date

The date of the formal decision of the Contracting Agency to accept the lowest responsible and responsive Bidder for the Work.

Contract Execution Date

The date the Contracting Agency officially binds the Agency to the Contract.

Notice to Proceed Date

The date stated in the Notice to Proceed on which the Contract time begins.

Substantial Completion Date

The day the Engineer determines the Contracting Agency has full and unrestricted use and benefit of the facilities, both from the operational and safety standpoint, any remaining traffic disruptions will be rare and brief, and only minor incidental work, replacement of temporary substitute facilities, plant establishment periods, or correction or repair remains for the Physical Completion of the total Contract.

Physical Completion Date

The day all of the Work is physically completed on the project. All documentation required by the Contract and required by law does not necessarily need to be furnished by the Contractor by this date.

Completion Date

The day all the Work specified in the Contract is completed and all the obligations of the Contractor under the contract are fulfilled by the Contractor. All documentation required by the Contract and required by law must be furnished by the Contractor before establishment of this date.

Final Acceptance Date

The date on which the Contracting Agency accepts the Work as complete.

Supplement this Section with the following:

All references in the Standard Specifications, Amendments, or WSDOT General Special Provisions, to the terms "Department of Transportation", "Washington State Transportation Commission", "Commission", "Secretary of Transportation", "Secretary", "Headquarters", and "State Treasurer" shall be revised to read "Contracting Agency."

All references to the terms “State” or “state” shall be revised to read “Contracting Agency” unless the reference is to an administrative agency of the State of Washington, a State statute or regulation, or the context reasonably indicates otherwise.

All references to “State Materials Laboratory” shall be revised to read “Contracting Agency designated location.”

All references to “final contract voucher certification” shall be interpreted to mean the Contracting Agency form(s) by which final payment is authorized, and final completion and acceptance granted.

Additive

A supplemental unit of work or group of bid items, identified separately in the Bid Proposal, which may, at the discretion of the Contracting Agency, be awarded in addition to the base bid.

Alternate

One of two or more units of work or groups of bid items, identified separately in the Bid Proposal, from which the Contracting Agency may make a choice between different methods or material of construction for performing the same work.

Business Day

A business day is any day from Monday through Friday except holidays as listed in Section 1-08.5.

Contract Bond

The definition in the Standard Specifications for “Contract Bond” applies to whatever bond form(s) are required by the Contract Documents, which may be a combination of a Payment Bond and a Performance Bond.

Contract Documents

See definition for “Contract.”

Contract Time

The period of time established by the terms and conditions of the Contract within which the Work must be physically completed.

Notice of Award

The written notice from the Contracting Agency to the successful Bidder signifying the Contracting Agency’s acceptance of the Bid Proposal.

Notice to Proceed

The written notice from the Contracting Agency or Engineer to the Contractor authorizing and directing the Contractor to proceed with the Work and establishing the date on which the Contract time begins.

Traffic

Both vehicular and non-vehicular traffic, such as pedestrians, bicyclists, wheelchairs, and equestrian traffic.

1-02 BID PROCEDURES AND CONDITIONS

1-02.1 Prequalification of Bidders

Delete this Section and replace it with the following:

1-02.1 Qualifications of Bidder

(January 24, 2011 APWA GSP)

Before award of a public works Contract, a bidder must meet at least the minimum qualifications of RCW 39.04.350(1) to be considered a responsible bidder and qualified to be awarded a public works project.

1-02.2 Plans and Specifications

(June 27, 2011 APWA GSP)

Delete this section and replace it with the following:

Information as to where Bid Documents can be obtained or reviewed can be found in the Call for Bids (Advertisement for Bids) for the work.

After award of the Contract, Plans and specifications will be issued to the Contractor at no cost as detailed below:

To Prime Contractor	No. of Sets	Basis of Distribution
Reduced Plans (11" x 17")	1	Furnished automatically upon award.
Contract Provisions	1	Furnished automatically upon award.
Large Plans (e.g., 22" x 34")	1	Furnished only upon request.

Additional Plans and Contract Provisions may be obtained by the Contractor from the source stated in the Call for Bids, at the Contractor’s own expense.

1-02.4 Examination of Plans, Specifications, and Site Work

(June 27, 2011 APWA GSP)

1-02.4(1) General

(December 30, 2022 APWA GSP, Option B)

The first sentence of the ninth paragraph, beginning with “Prospective Bidder desiring...”, is revised to read:

Prospective Bidders desiring an explanation or interpretation of the Bid Documents, shall request the explanation or interpretation in writing by close of business three (3) business days preceding the bid opening to allow a written reply to reach all prospective Bidders before the submission of their Bids.

1-02.4(2) Subsurface Information

(January 19, 2022 APWA GSP)

The third and fourth sentences in the first paragraph are revised to read:

The Summary of Geotechnical Conditions and the boring logs, if and when included as an appendix to the Special Provisions, shall be considered as part of the Contract. The boring logs and associated data, if and when included as an appendix to the Special Provisions, shall be considered as part of the Contract.

1-02.5 Proposal Forms

(July 31, 2017 APWA GSP)

Delete this section and replace it with the following:

The Proposal Form will identify the project and its location and describe the work. It will also list estimated quantities, units of measurement, the items of work, and the materials to be furnished at the unit bid prices. The bidder shall complete spaces on the proposal form that call for, but are not limited to, unit prices; extensions; summations; the total bid amount; signatures; date; and, where applicable, retail sales taxes and acknowledgment of addenda; the bidder's name, address, telephone number, and signature; the bidder's UBDE/DBE/M/WBE commitment, if applicable; a State of Washington Contractor's Registration Number; and a Business License Number, if applicable. Bids shall be completed by typing or shall be printed in ink by hand, preferably in black ink. The required certifications are included as part of the Proposal Form.

The Contracting Agency reserves the right to arrange the proposal forms with alternates and additives, if such be to the advantage of the Contracting Agency. The bidder shall bid on all alternates and additives set forth in the Proposal Form unless otherwise specified.

1-02.6 Preparation of Proposal
(January 4, 2024 APWA GSP, OPTION B)

Supplement the second paragraph with the following:

4. If a minimum bid amount has been established for any item, the unit or lump sum price must equal or exceed the minimum amount stated.
5. Any correction to a bid made by interlineation, alteration, or erasure, shall be initialed by the signer of the bid.

Delete the last two paragraphs
, and replace them with the following:

The Bidder shall submit with their Bid a completed Contractor Certification Wage Law Compliance form, provided by the Contracting Agency. Failure to return this certification as part of the Bid Proposal package will make this Bid Nonresponsive and ineligible for Award. A Contractor Certification of Wage Law Compliance form is included in the Proposal Forms.

The Bidder shall make no stipulation on the Bid Form, nor qualify the bid in any manner.

A bid by a corporation shall be executed in the corporate name, by the president or a vice president (or other corporate officer accompanied by evidence of authority to sign).

A bid by a partnership shall be executed in the partnership name, and signed by a partner. A copy of the partnership agreement shall be submitted with the Bid Form if any DBE requirements are to be satisfied through such an agreement.

A bid by a joint venture shall be executed in the joint venture name and signed by a member of the joint venture. A copy of the joint venture agreement shall be submitted with the Bid Form if any DBE requirements are to be satisfied through such an agreement.

Bidding Procedures

To be considered responsive the Bidder shall submit a price on each and every Bid item included in the Base Bid.

Add the following new section:

1-02.6(1) Recycled Materials Proposal
(January 4, 2016 APWA GSP)

The Bidder shall submit with the Bid, its proposal for incorporating recycled materials into the project, using the form provided in the Contract Provisions.

1-02.7 Bid Deposit
(March 8, 2013 APWA GSP)

Supplement this section with the following:

Bid bonds shall contain the following:

1. Contracting Agency-assigned number for the project;
2. Name of the project;
3. The Contracting Agency named as obligee;
4. The amount of the bid bond stated either as a dollar figure or as a percentage which represents five percent of the maximum bid amount that could be awarded;
5. Signature of the bidder's officer empowered to sign official statements. The signature of the person authorized to submit the bid should agree with the signature on the bond, and the title of the person must accompany the said signature;
6. The signature of the surety's officer empowered to sign the bond and the power of attorney.

If so stated in the Contract Provisions, bidder must use the bond form included in the Contract Provisions.

If so stated in the Contract Provisions, cash will not be accepted for a bid deposit.

1-02.14 Disqualification of Bidders
(May 17, 2018 APWA GSP, OPTION B)

Delete this section and replace it with the following:

A Bidder will be deemed not responsible if the Bidder does not meet the mandatory bidder responsibility criteria in RCW 39.04.350(1), as amended; or does not meet Supplemental Criteria 1-7 listed in this Section.

Contracting Agency will verify that the Bidder meets the mandatory bidder responsibility criteria in RCW 39.04.350(1), and Supplemental Criteria 1-2. Evidence that the Bidder meets Supplemental Criteria 3-7 shall be provided by the Bidder as stated later in this Section.

1. **Delinquent State Taxes**

- A. Criterion: The Bidder shall not owe delinquent taxes to the Washington State Department of Revenue without a payment plan approved by the Department of Revenue.
- B. Documentation: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder does not owe delinquent taxes to the Washington State Department of Revenue, or if delinquent taxes are owed to the Washington State Department

of Revenue, the Bidder must submit a written payment plan approved by the Department of Revenue, to the Contracting Agency by the deadline listed below.

2. **Federal Debarment**

- A. Criterion: The Bidder shall not currently be debarred or suspended by the Federal government.
- B. Documentation: The Bidder shall not be listed as having an “active exclusion” on the U.S. government’s “System for Award Management” database (www.sam.gov).

3. **Subcontractor Responsibility**

- A. Criterion: The Bidder’s standard subcontract form shall include the subcontractor responsibility language required by RCW 39.06.020, and the Bidder shall have an established procedure which it utilizes to validate the responsibility of each of its subcontractors. The Bidder’s subcontract form shall also include a requirement that each of its subcontractors shall have and document a similar procedure to determine whether the sub-tier subcontractors with whom it contracts are also “responsible” subcontractors as defined by RCW 39.06.020.
- B. Documentation: The Bidder, if and when required as detailed below, shall submit a copy of its standard subcontract form for review by the Contracting Agency, and a written description of its procedure for validating the responsibility of subcontractors with which it contracts.

4. **Claims Against Retainage and Bonds**

- A. Criterion: The Bidder shall not have a record of excessive claims filed against the retainage or payment bonds for public works projects in the three years prior to the bid submittal date, that demonstrate a lack of effective management by the Bidder of making timely and appropriate payments to its subcontractors, suppliers, and workers, unless there are extenuating circumstances and such circumstances are deemed acceptable to the Contracting Agency.
- B. Documentation: The Bidder, if and when required as detailed below, shall submit a list of the public works projects completed in the three years prior to the bid submittal date that have had claims against retainage and bonds and include for each project the following information:
- Name of project
 - The owner and contact information for the owner;
 - A list of claims filed against the retainage and/or payment bond for any of the projects listed;
 - A written explanation of the circumstances surrounding each claim and the ultimate resolution of the claim.

5. **Public Bidding Crime**

- A. Criterion: The Bidder and/or its owners shall not have been convicted of a crime involving bidding on a public works contract in the five years prior to the bid submittal date.

- B. Documentation: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder and/or its owners have not been convicted of a crime involving bidding on a public works contract.

6. **Termination for Cause / Termination for Default**

- A. Criterion: The Bidder shall not have had any public works contract terminated for cause or terminated for default by a government agency in the five years prior to the bid submittal date, unless there are extenuating circumstances and such circumstances are deemed acceptable to the Contracting Agency.
- B. Documentation: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder has not had any public works contract terminated for cause or terminated for default by a government agency in the five years prior to the bid submittal date; or if Bidder was terminated, describe the circumstances.

7. **Lawsuits**

- A. Criterion: The Bidder shall not have lawsuits with judgments entered against the Bidder in the five years prior to the bid submittal date that demonstrate a pattern of failing to meet the terms of contracts, unless there are extenuating circumstances and such circumstances are deemed acceptable to the Contracting Agency
- B. Documentation: The Bidder, if and when required as detailed below, shall sign a statement (on a form to be provided by the Contracting Agency) that the Bidder has not had any lawsuits with judgments entered against the Bidder in the five years prior to the bid submittal date that demonstrate a pattern of failing to meet the terms of contracts, or shall submit a list of all lawsuits with judgments entered against the Bidder in the five years prior to the bid submittal date, along with a written explanation of the circumstances surrounding each such lawsuit. The Contracting Agency shall evaluate these explanations to determine whether the lawsuits demonstrate a pattern of failing to meet of terms of construction related contracts.

As evidence that the Bidder meets the Supplemental Criteria stated above, the apparent low Bidder must submit to the Contracting Agency by 12:00 P.M. (noon) of the second business day following the bid submittal deadline, a written statement verifying that the Bidder meets the supplemental criteria together with supporting documentation (sufficient in the sole judgment of the Contracting Agency) demonstrating compliance with the Supplemental Criteria. The Contracting Agency reserves the right to request further documentation as needed from the low Bidder and documentation from other Bidders as well to assess Bidder responsibility and compliance with all bidder responsibility criteria. The Contracting Agency also reserves the right to obtain information from third-parties and independent sources of information concerning a Bidder's compliance with the mandatory and supplemental criteria, and to use that information in their evaluation. The Contracting Agency may consider mitigating factors in determining whether the Bidder complies with the requirements of the supplemental criteria.

The basis for evaluation of Bidder compliance with these mandatory and supplemental criteria shall include any documents or facts obtained by Contracting Agency (whether from the Bidder or third parties) including but not limited to: (i) financial, historical, or operational data from the Bidder; (ii) information obtained directly by the Contracting Agency from others for whom the Bidder has worked, or other public agencies or private enterprises; and (iii) any additional information obtained by the Contracting Agency which is believed to be relevant to the matter.

If the Contracting Agency determines the Bidder does not meet the bidder responsibility criteria above and is therefore not a responsible Bidder, the Contracting Agency shall notify the Bidder in writing, with the reasons for its determination. If the Bidder disagrees with this determination, it may appeal the determination within two (2) business days of the Contracting Agency's determination by presenting its appeal and any additional information to the Contracting Agency. The Contracting Agency will consider the appeal and any additional information before issuing its final determination. If the final determination affirms that the Bidder is not responsible, the Contracting Agency will not execute a contract with any other Bidder until at least two business days after the Bidder determined to be not responsible has received the Contracting Agency's final determination.

Request to Change Supplemental Bidder Responsibility Criteria Prior To Bid: Bidders with concerns about the relevancy or restrictiveness of the Supplemental Bidder Responsibility Criteria may make or submit requests to the Contracting Agency to modify the criteria. Such requests shall be in writing, describe the nature of the concerns, and propose specific modifications to the criteria. Bidders shall submit such requests to the Contracting Agency no later than five (5) business days prior to the bid submittal deadline and address the request to the Project Engineer or such other person designated by the Contracting Agency in the Bid Documents.

1-03 AWARD AND EXECUTION OF CONTRACT

1-03.1 Consideration of Bids

(December 30, 2022 APWA GSP)

Revise the first paragraph to read:

After opening and reading proposals, the Contracting Agency will check them for correctness of extensions of the prices per unit and the total price. If a discrepancy exists between the price per unit and the extended amount of any bid item, the price per unit will control. If a minimum bid amount has been established for any item and the bidder's unit or lump sum price is less than the minimum specified amount, the Contracting Agency will unilaterally revise the unit or lump sum price, to the minimum specified amount and recalculate the extension. The total of extensions, corrected where necessary, including sales taxes where applicable and such additives and/or alternates as selected by the Contracting Agency, will be used by the Contracting Agency for award purposes and to fix the Awarded Contract Price amount and the amount of the contract bond.

(January 19, 2024 CFW GSP)

Section 1-03.1 is supplemented with the following:

The owner reserves the right to reject bids on any or all schedules or alternates of the proposal. After reviewing the bids, the Owner may elect to delete any one or combination of schedules from the proposal.

1-03.1(1) Identical Bid Totals
(December 30, 2022 APWA GSP)

Revise this section to read:

After opening Bids, if two or more lowest responsive Bid totals are exactly equal, then the tie-breaker will be the Bidder with an equal lowest bid, that proposed to use the highest percentage of recycled materials in the Project, per the form submitted with the Bid Proposal. If those percentages are also exactly equal, then the tie-breaker will be determined by drawing as follows: Two or more slips of paper will be marked as follows: one marked "Winner" and the other(s) marked "unsuccessful." The slips will be folded to make the marking unseen. The slips will be placed inside a box. One authorized representative of each Bidder shall draw a slip from the box. Bidders shall draw in alphabetic order by the name of the firm as registered with the Washington State Department of Licensing. The slips shall be unfolded and the firm with the slip marked "Winner" will be determined to be the successful Bidder and eligible for Award of the Contract. Only those Bidders who submitted a Bid total that is exactly equal to the lowest responsive Bid, and with a proposed recycled materials percentage that is exactly equal to the highest proposed recycled materials amount, are eligible to draw.

1-03.3 Execution of Contract
(July 8, 2024 APWA GSP, Option A)

Revise this section to read:

Within 3 calendar days of Award date (not including Saturdays, Sundays, and Holidays), the successful Bidder shall provide the information necessary to execute the Contract to the Contracting Agency. The Bidder shall send the contact information, including the full name, email address, and phone number, for the authorized signer and bonding agent to the Contracting Agency.

Copies of the Contract Provisions, including the unsigned Form of Contract, will be available for signature by the successful bidder on the first business day following award. The number of copies to be executed by the Contractor will be determined by the Contracting Agency.

Within 10 calendar days after the award date, the successful bidder shall return the signed Contracting Agency-prepared contract, an insurance certification as required by Section 1-07.18, and a satisfactory bond as required by law and Section 1-03.4, the Transfer of Coverage form for the Construction Stormwater General Permit with sections I, III, and VIII completed when provided. Before execution of the contract by the Contracting Agency, the successful bidder shall provide any pre-award information the Contracting Agency may require under Section 1-02.15.

Until the Contracting Agency executes a contract, no proposal shall bind the Contracting Agency nor shall any work begin within the project limits or within Contracting Agency-furnished sites. The Contractor shall bear all risks for any work begun outside such areas and for any materials ordered before the contract is executed by the Contracting Agency.

If the bidder experiences circumstances beyond their control that prevents return of the contract documents within the calendar days after the award date stated above, the Contracting Agency may grant up to a maximum of 5 additional calendar days for return of the documents, provided the Contracting Agency deems the circumstances warrant it.

1-03.4 Contract Bond
(July 23, 2015 APWA GSP)

Delete the first paragraph and replace it with the following:

The successful bidder shall provide executed payment and performance bond(s) for the full contract amount. The bond may be a combined payment and performance bond; or be separate payment and performance bonds. In the case of separate payment and performance bonds, each shall be for the full contract amount. The bond(s) shall:

1. Be on Contracting Agency-furnished form(s);
2. Be signed by an approved surety (or sureties) that:
 - a. Is registered with the Washington State Insurance Commissioner, and
 - b. Appears on the current Authorized Insurance List in the State of Washington published by the Office of the Insurance Commissioner,
3. Guarantee that the Contractor will perform and comply with all obligations, duties, and conditions under the Contract, including but not limited to the duty and obligation to indemnify, defend, and protect the Contracting Agency against all losses and claims related directly or indirectly from any failure:
 - a. Of the Contractor (or any of the employees, subcontractors, or lower tier subcontractors of the Contractor) to faithfully perform and comply with all contract obligations, conditions, and duties, or
 - b. Of the Contractor (or the subcontractors or lower tier subcontractors of the Contractor) to pay all laborers, mechanics, subcontractors, lower tier subcontractors, material person, or any other person who provides supplies or provisions for carrying out the work;
4. Be conditioned upon the payment of taxes, increases, and penalties incurred on the project under titles 50, 51, and 82 RCW; and
5. Be accompanied by a power of attorney for the Surety's officer empowered to sign the bond; and
6. Be signed by an officer of the Contractor empowered to sign official statements (sole proprietor or partner). If the Contractor is a corporation, the bond(s) must be signed by the president or vice president, unless accompanied by written proof of the authority of the individual signing the bond(s) to bind the corporation (i.e., corporate resolution, power of attorney, or a letter to such effect signed by the president or vice president).

1-03.7 Judicial Review
(December 30, 2022 APWA GSP)

Revise this section to read:

All decision made by the Contracting Agency regarding the Award and execution of the Contract or Bid rejection shall be conclusive subject to the scope of judicial review permitted under Washington Law. Such review, if any, shall be timely filed in the Superior Court of the county where the Contracting Agency headquarters is located, provided that where an action is asserted against a county, RCW 36.01.050 shall control venue and jurisdiction.

1-04 SCOPE OF THE WORK

1-04.2 Coordination of Contract Documents, Plans, Special Provisions, Specifications, and Addenda

(January 8, 2021 CFW GSP)

Revise the second paragraph to read:

Any inconsistency in the parts of the contract shall be resolved by following this order of precedence (e.g., 1 presiding over 2, 2 over 3, 3 over 4, and so forth):

1. Contract,
2. Change Orders, with those of a later date taking precedence of those of an earlier date,
3. Addenda, with those of a later date taking precedence of those of an earlier date,
4. Proposal Form,
5. Special Provisions,
6. Contract Plans,
7. Standard Specifications,
8. Contracting Agency's Standard Plans or Details (if any), and
9. WSDOT Standard Plans for Road, Bridge, and Municipal Construction.

1-04.4 Changes

(January 19, 2022 APWA GSP)

The first two sentences of the last paragraph of Section 1-04.4 are deleted.

1-05 CONTROL OF WORK

(January 13, 2021 WSDOT GSP, OPTION 2)

Section 1-05.4 is supplemented with the following:

Contractor Surveying – Roadway

The Contracting Agency has provided primary survey control in the Plans.

The Contractor shall be responsible for setting, maintaining, and resetting all alignment stakes, slope stakes, and grades necessary for the construction of the roadbed, drainage, surfacing, paving, channelization and pavement marking, illumination and signals, guardrails and barriers, and signing. Except for the survey control data to be furnished by the Contracting Agency, calculations, surveying, and measuring required for setting and maintaining the necessary lines and grades shall be the Contractor's responsibility.

The Contractor shall inform the Engineer when monuments are discovered that were not identified in the Plans and construction activity may disturb or damage the monuments. All monuments noted on the plans "DO NOT DISTURB" shall be protected throughout the length of the project or be replaced at the Contractors expense.

Detailed survey records shall be maintained, including a description of the work performed on each shift, the methods utilized, and the control points used. The record shall be adequate to allow the survey to be reproduced. A copy of each day's record shall be provided to the Engineer within three working days after the end of the shift.

The meaning of words and terms used in this provision shall be as listed in "Definitions of Surveying and Associated Terms" current edition, published by the American Congress on Surveying and Mapping and the American Society of Civil Engineers.

The survey work shall include but not be limited to the following:

1. Verify the primary horizontal and vertical control furnished by the Contracting Agency, and expand into secondary control by adding stakes and hubs as well as additional survey control needed for the project. Provide descriptions of secondary control to the Contracting Agency. The description shall include coordinates and elevations of all secondary control points.
2. Establish the centerlines of all alignments, by placing hubs, stakes, or marks on centerline or on offsets to centerline at all curve points (PCs, PTs, and PIs) and at points on the alignments spaced no further than 50 feet.
3. Establish clearing limits, placing stakes at all angle points and at intermediate points not more than 50 feet apart. The clearing and grubbing limits shall be 5 feet beyond the toe of a fill and 10 feet beyond the top of a cut unless otherwise shown in the Plans.
4. Establish grading limits, placing slope stakes at centerline increments not more than 50 feet apart. Establish offset reference to all slope stakes. If Global Positioning Satellite (GPS) Machine Controls are used to provide grade control, then slope stakes may be omitted at the discretion of the Contractor.
5. Establish the horizontal and vertical location of all drainage features, placing offset stakes to all drainage structures and to pipes at a horizontal interval not greater than 25 feet.
6. Establish roadbed and surfacing elevations by placing stakes at the top of subgrade and at the top of each course of surfacing. Subgrade and surfacing stakes shall be set at horizontal intervals not greater than 50 feet in tangent sections, 25 feet in curve sections with a radius less than 300 feet, and at 10-foot intervals in intersection radii with a radius less than 10 feet. Transversely, stakes shall be placed at all locations where the roadway slope changes and at additional points such that the transverse spacing of stakes is not more than 12 feet. If GPS Machine Controls are used to provide grade control, then roadbed and surfacing stakes may be omitted at the discretion of the Contractor.
7. Establish intermediate elevation benchmarks as needed to check work throughout the project.
8. Provide references for paving pins at 25-foot intervals or provide simultaneous surveying to establish location and elevation of paving pins as they are being placed.
9. For all other types of construction included in this provision, (including but not limited to channelization and pavement marking, illumination and signals, guardrails and barriers, and signing) provide staking and layout as necessary to adequately locate, construct, and check the specific construction activity.

10. Contractor shall determine if changes are needed to the profiles or roadway sections shown in the Contract Plans in order to achieve proper smoothness and drainage where matching into existing features, such as a smooth transition from new pavement to existing pavement. The Contractor shall submit these changes to the Engineer for review and approval 10 days prior to the beginning of work.

The Contractor shall provide the Contracting Agency copies of any calculations and staking data when requested by the Engineer.

The Contractor shall ensure a surveying accuracy within the following tolerances:

	<u>Vertical</u>	<u>Horizontal</u>
Slope stakes	±0.10 feet	±0.10 feet
Subgrade grade stakes set 0.04 feet below grade	±0.01 feet	±0.5 feet (parallel to alignment) ±0.1 feet (normal to alignment)
Stationing on roadway	N/A	±0.1 feet
Alignment on roadway	N/A	±0.04 feet
Surfacing grade stakes	±0.01 feet	±0.5 feet (parallel to alignment) ±0.1 feet (normal to alignment)
Roadway paving pins for surfacing or paving	±0.01 feet	±0.2 feet (parallel to alignment) ±0.1 feet (normal to alignment)

The Contracting Agency may spot-check the Contractor's surveying. These spot-checks will not change the requirements for normal checking by the Contractor.

When staking roadway alignment and stationing, the Contractor shall perform independent checks from different secondary control to ensure that the points staked are within the specified survey accuracy tolerances.

The Contractor shall calculate coordinates for the alignment. The Contracting Agency will verify these coordinates prior to issuing approval to the Contractor for commencing with the work. The Contracting Agency will require up to seven calendar days from the date the data is received.

Contract work to be performed using contractor-provided stakes shall not begin until the stakes are approved by the Contracting Agency. Such approval shall not relieve the Contractor of responsibility for the accuracy of the stakes.

Stakes shall be marked in accordance with Standard Plan A-10.10. When stakes are needed that are not described in the Plans, then those stakes shall be marked, at no additional cost to the Contracting Agency as ordered by the Engineer.

Payment

Payment will be made for the following bid item when included in the proposal:

"Roadway Surveying", lump sum.

The lump sum contract price for "Roadway Surveying" shall be full pay for all labor, equipment, materials, and supervision utilized to perform the Work specified, including any resurveying, checking, correction of errors, replacement of missing or damaged stakes, and coordination efforts.

(March 9, 2023, WSDOT GSP, OPTION 4)

Section 1-05.4 is supplemented with the following:

Contractor Surveying - ADA Features

ADA Feature Staking Requirements

The Contractor shall be responsible for setting, maintaining, and resetting all alignment stakes, and grades necessary for the construction of the ADA features. Calculations, surveying, and measuring required for setting and maintaining the necessary lines and grades shall be the Contractor's responsibility. The Contractor shall build the ADA features within the specifications in the Standard Plans and contract documents.

ADA Feature Contract Compliance

The Contractor shall be responsible for completing measurements to verify all ADA features comply with the Contract in the presence of the Engineer.

ADA Feature As-Built Measurements

The Contractor shall be responsible for providing the latitude and longitude of each ADA feature as indicated on the ADA Inspection Form(s) (WSDOT Form 224-020).

The completed ADA Inspection Form(s) (WSDOT Form 224-020) shall be submitted as a Type 3 Working Drawing and transmitted to the Engineer within 30 calendar days of completing the ADA feature. After acceptance, the Contracting Agency will submit the final form(s) to the WSDOT ADA Steward.

Payment

Payment will be made for the following bid item that is included in the Proposal:

"ADA Features Surveying", lump sum.

The lump sum Contract price for "ADA Features Surveying" shall be full pay for all the Work as specified.

In the instance where an ADA feature does not meet accessibility requirements, all work to replace non-compliant work and then to measure, record the as-built measurements, and transmit the electronic forms to the Engineer shall be completed at no additional cost to the Contracting Agency.

1-05.7 Removal of Defective and Unauthorized Work

(October 1, 2005 APWA GSP)

Supplement this section with the following:

If the Contractor fails to remedy defective or unauthorized work within the time specified in a written notice from the Engineer, or fails to perform any part of the work required by the Contract Documents, the Engineer may correct and remedy such work as may be identified in the written notice, with Contracting Agency forces or by such other means as the Contracting Agency may deem necessary.

If the Contractor fails to comply with a written order to remedy what the Engineer determines to be an emergency situation, the Engineer may have the defective and unauthorized work corrected immediately, have the rejected work removed and replaced, or have work the Contractor refuses to perform completed by using Contracting Agency or other forces. An emergency situation is any situation when, in the opinion of the Engineer, a delay in its remedy could be potentially unsafe, or might cause serious risk of loss or damage to the public.

Direct or indirect costs incurred by the Contracting Agency attributable to correcting and remedying defective or unauthorized work, or work the Contractor failed or refused to perform, shall be paid by the Contractor. Payment will be deducted by the Engineer from monies due, or to become due, the Contractor. Such direct and indirect costs shall include in particular, but without limitation, compensation for additional professional services required, and costs for repair and replacement of work of others destroyed or damaged by correction, removal, or replacement of the Contractor's unauthorized work.

No adjustment in Contract time or compensation will be allowed because of the delay in the performance of the work attributable to the exercise of the Contracting Agency's rights provided by this section.

The rights exercised under the provisions of this section shall not diminish the Contracting Agency's right to pursue any other avenue for additional remedy or damages with respect to the Contractor's failure to perform the work as required.

1-05.10 Guarantees

(January 19, 2024 CFW GSP)

Section 1-05.10 is supplemented with the following:

All work performed by the Contractor shall maintain a warranty. The warranty period shall be established by the Contract Documents. When not specified in the Contract Documents, the warranty period shall be one year. Conducting of tests and inspections, review of specifications or plans, payment for goods or services, or acceptance by the City does not constitute waiver, modification, or exclusion of any express or implied warranty or any right under law. This warranty shall survive termination of this Contract.

The Contractor shall, at its own sole cost and expense, be responsible for correcting all defects in workmanship and material discovered within one year after acceptance of this work by the City of Federal Way. When corrections of defects are made, the Contractor shall be responsible for correcting all defects in workmanship and/or materials in the corrected work for one year after acceptance of the corrections by the Owner.

If within one year after the date of Project Acceptance by the Owner, defective and/or unauthorized Work is discovered, the Owner shall notify the Contractor in writing (either e-mail or USPS mail). The Contractor shall start work to remedy such defects within seven

(7) calendar days of notice of discovery by the Owner and shall complete such work within a reasonable time. The Contractor shall either correct such Work, or if such Work has been rejected by the Engineer, remove it from the Project Site and replace it with non-defective and authorized Work, all without cost to the Owner.

In emergencies, where damage may result from delay or where loss of services may result, such corrections may be made by the Owner, in which case the cost shall be borne by the Contractor. If the Contractor does not promptly comply with the written request to correct defective and authorized Work, or if an emergency exists, the Owner reserves the right to have defective and/or unauthorized Work corrected or rejected, and replaced pursuant to the provisions of Section 1-05.7 of these Specifications. The Owner will pursue payment for the incurred costs from the project Performance and Payment Bond. The Contractor shall be liable for any costs, losses, expenses, or damages, including consequential damages suffered by the Owner resulting from defects in the Contractor's work including, but not limited to, cost of materials and labor extended by Owner in making emergency repairs and cost of engineering, inspection and supervision by the Owner or the Engineer. The Contractor shall hold the Owner harmless from any and all claims which may be made against the Owner as a result of any defective work, and the Contractor shall defend any such claims at his own expense.

The Contractor agrees the above one year warranty shall not exclude or diminish the Owner's rights under any law to obtain damages and recover costs resulting from defective and unauthorized work discovered after one year but prior to the expiration of the legal time period set forth in RCW 4.16.040 limiting actions upon a contract in writing or liability, expressed or implied, arising out of a written agreement. This warranty may also extend beyond the one year time period pursuant to any other warranties specified in the Special Provisions, Contract Plans, other parts of the Contract Documents, or incorporated by this reference.

The Contract performance and payment bond shall remain in effect throughout the above stated warranty period.

1-05.11 Final Inspection
(October 1, 2005 APWA GSP)

Delete this section and replace it with the following:

1-05.11 Final Inspections and Operational Testing

1-05.11(1) Substantial Completion Date

When the Contractor considers the work to be substantially complete, the Contractor shall so notify the Engineer and request the Engineer establish the Substantial Completion Date. The Contractor's request shall list the specific items of work that remain to be completed in order to reach physical completion. The Engineer will schedule an inspection of the work with the Contractor to determine the status of completion. The Engineer may also establish the Substantial Completion Date unilaterally.

If, after this inspection, the Engineer concurs with the Contractor that the work is substantially complete and ready for its intended use, the Engineer, by written notice to the Contractor, will set the Substantial Completion Date. If, after this inspection the Engineer does not consider the work substantially complete and ready for its intended

use, the Engineer will, by written notice, so notify the Contractor giving the reasons therefore.

Upon receipt of written notice concurring in or denying substantial completion, whichever is applicable, the Contractor shall pursue vigorously, diligently and without unauthorized interruption, the work necessary to reach Substantial and Physical Completion. The Contractor shall provide the Engineer with a revised schedule indicating when the Contractor expects to reach substantial and physical completion of the work.

The above process shall be repeated until the Engineer establishes the Substantial Completion Date and the Contractor considers the work physically complete and ready for final inspection.

1-05.11(2) Final Inspection and Physical Completion Date

When the Contractor considers the work physically complete and ready for final inspection, the Contractor by written notice, shall request the Engineer to schedule a final inspection. The Engineer will set a date for final inspection. The Engineer and the Contractor will then make a final inspection and the Engineer will notify the Contractor in writing of all particulars in which the final inspection reveals the work incomplete or unacceptable. The Contractor shall immediately take such corrective measures as are necessary to remedy the listed deficiencies. Corrective work shall be pursued vigorously, diligently, and without interruption until physical completion of the listed deficiencies. This process will continue until the Engineer is satisfied the listed deficiencies have been corrected.

If action to correct the listed deficiencies is not initiated within 7 days after receipt of the written notice listing the deficiencies, the Engineer may, upon written notice to the Contractor, take whatever steps are necessary to correct those deficiencies pursuant to Section 1-05.7.

The Contractor will not be allowed an extension of Contract time because of a delay in the performance of the work attributable to the exercise of the Engineer's right hereunder.

Upon correction of all deficiencies, the Engineer will notify the Contractor and the Contracting Agency, in writing, of the date upon which the work was considered physically complete. That date shall constitute the Physical Completion Date of the Contract, but shall not imply acceptance of the work or that all the obligations of the Contractor under the Contract have been fulfilled.

1-05.11(3) Operational Testing

It is the intent of the Contracting Agency to have at the Physical Completion Date a complete and operable system. Therefore when the work involves the installation of machinery or other mechanical equipment; street lighting, electrical distribution or signal systems; irrigation systems; buildings; or other similar work it may be desirable for the Engineer to have the Contractor operate and test the work for a period of time after final inspection but prior to the physical completion date. Whenever items of work are listed in the Contract Provisions for operational testing they shall be fully tested under operating conditions for the time period specified to ensure their acceptability prior to the Physical Completion Date. During and following the test period, the Contractor shall correct any items of workmanship, materials, or equipment which prove faulty, or that are not in first class operating condition. Equipment, electrical controls, meters, or other devices and

equipment to be tested during this period shall be tested under the observation of the Engineer, so that the Engineer may determine their suitability for the purpose for which they were installed. The Physical Completion Date cannot be established until testing and corrections have been completed to the satisfaction of the Engineer.

The costs for power, gas, labor, material, supplies, and everything else needed to successfully complete operational testing, shall be included in the unit Contract prices related to the system being tested, unless specifically set forth otherwise in the Proposal.

Operational and test periods, when required by the Engineer, shall not affect a manufacturer's guaranties or warranties furnished under the terms of the Contract.

1-05.12 Final Acceptance

(April 12, 2019 CFW GSP)

Delete the third and fourth sentences in the first paragraph and replace it with the following:

Final acceptance date of the work shall be the date the Federal Way City Council accepts the project as complete.

1-05.12(1) One-Year Guarantee Period

(March 8, 2013 APWA GSP)

Add the following new section.

The Contractor shall return to the project and repair or replace all defects in workmanship and material discovered within one year after Final Acceptance of the Work. The Contractor shall start work to remedy any such defects within 7 calendar days of receiving Contracting Agency's written notice of a defect, and shall complete such work within the time stated in the Contracting Agency's notice. In case of an emergency, where damage may result from delay or where loss of services may result, such corrections may be made by the Contracting Agency's own forces or another contractor, in which case the cost of corrections shall be paid by the Contractor. In the event the Contractor does not accomplish corrections within the time specified, the work will be otherwise accomplished and the cost of same shall be paid by the Contractor.

When corrections of defects are made, the Contractor shall then be responsible for correcting all defects in workmanship and materials in the corrected work for one year after acceptance of the corrections by Contracting Agency.

This guarantee is supplemental to and does not limit or affect the requirements that the Contractor's work comply with the requirements of the Contract or any other legal rights or remedies of the Contracting Agency.

1-05.13 Superintendents, Labor and Equipment of Contractor

(August 14, 2013 APWA GSP)

Delete the sixth and seventh paragraphs of this section.

1-05.15 Method of Serving Notices

(January 4, 2024 APWA GSP)

Revise the second paragraph to read:

All correspondence from the Contractor shall be served and directed to the Engineer. All correspondence from the Contractor constituting any notification, notice of protest, notice of dispute, or other correspondence constituting notification required to be furnished under

the Contract, must be written in paper format, hand delivered or sent via certified mail delivery service with return receipt requested to the Engineer's office. Electronic copies such as e-mails or electronically delivered copies of correspondence will not constitute such notice and will not comply with the requirements of the Contract.

1-05.16 Water and Power
(October 1, 2005 APWA GSP)

Add the following new section:

The Contractor shall make necessary arrangements, and shall bear the costs for power and water necessary for the performance of the work, unless the Contract includes power and water as a pay item.

1-05.17 As-Built Survey and Record Drawings
(March 22, 2023 CFW GSP)

Section 1-05.17 is a new section:

As-Built Survey

After construction has been completed the Contractor shall perform an as-built survey and provide the information (including point files) in a format compatible with AutoCAD 2019 or later version file to the Engineer.

The applicable tolerance limits for the as-built survey include, but are not limited to the following:

	Vertical	Horizontal
As-built sanitary & storm invert and grate elevations	± 0.01 foot	± 0.01 foot
As-built monumentation	± 0.001 foot	± 0.001 foot
As-built waterlines, inverts, valves, hydrants	± 0.10 foot	± 0.10 foot
As-built ponds/swales/water features	± 0.10 foot	± 0.10 foot
As-built buildings (fin. Floor elev.)	± 0.01 foot	± 0.10 foot
As-built gas lines, power, TV, Tel, Com	± 0.10 foot	± 0.10 foot
As-built signs, signals, etc.	N/A	± 0.10 foot

This as-built survey shall consist of the following:

- Survey of rim elevation, sump elevations, and invert elevations of all storm drainage structures installed, modified or left in place within the limits of this contract. Storm pipe diameter and material; drainage structure type, size, lid type (solid cover or grate, standard or heavy duty), and lid shape; model No. of CB water quality treatment inserts installed, flowline of open channel conveyance systems at 50-foot max. intervals, and retaining wall footing drains, including cleanouts.
- Survey of all monuments shown on the plans or discovered within the project limits. City of Federal Way Monument Record forms shall be completed by a Professional Land Surveyor and submitted to the Project Engineer for each monument.
- Finished grade shots on all utility appurtenances within the limits of this contract, including, but not limited to vaults, handholes, valves, fire hydrants, water meters,

junction boxes, signal poles, etc. Appurtenances with round covers should have one survey shot in the center of the manhole or valve cover, or at the center of the fire hydrant. Utility handholes and boxes shall have two shots on opposite corners of the cover.

- Final curb elevations, with a minimum of 8 shots at each curb return. Also, final shots along all curb and gutter, block curb, integral curb and extruded curb installed in this contract (at flowline of the curbs).
- Final elevations at the front and back of walk throughout the project limits.
- Final wall elevations at the face and top of all walls installed in this contract.
- Shots of all signs, trees, illumination and signal equipment installed as part of this contract.
- Shots to delineate all channelization installed in this contract.

Record Drawings

Throughout construction, the Contractor shall be responsible for tracking all relevant field changes to the approved construction drawings. These changes shall be clearly identified in red ink in a comprehensive manner on one set of full size Plans. These Record Drawing shall be kept separate from other Plan sheets, and shall be clearly marked as Record Drawings. The Record Drawings shall be kept on site, and shall be available for review by the Contracting Agency at all times. The Contractor shall bring the Record Drawings to each progress meeting for review.

Upon completion of construction, the Contractor shall submit to the City a clean set of marked-up drawings in electronic PDF format that are signed and certified by the Contractor or their surveyor. The Certification on each page of the record drawings shall state that said drawings are an accurate depiction of built conditions. City acceptance of the Record Drawings is one of the requirements for achieving Physical Completion.

The certified Record Drawings shall, at a minimum, consist of the following:

- Existing or abandoned utilities that were encountered during construction that were not shown on the approved construction drawings.
- Accurate locations of storm drainage (including invert elevations), sanitary sewer, water mains and other water appurtenances, structures, conduits, light standards, vaults, width of roadways, sidewalks, landscaping areas, channelization and pavement markings, etc. Record drawings shall reflect actual dimensions, arrangement, and materials used when different than shown in the Plans. As-built survey information shall be used to confirm information shown on record drawings.
- Changes made by Change Order or Field Directive.
- Changes made by the Contractor as approved by the Engineer.
- Pothole information gathered by the Contractor.

Payment

"As-Built Survey and Record Drawings", lump sum.

The lump sum contract price for "As-Built Survey and Record Drawings " shall be full pay for all labor, equipment, materials, and supervision utilized to perform the work specified, including any surveying, checking, correction of errors, preparation of record drawings, and coordination efforts. Payment will be made after AutoCad files and record drawings are submitted to and approved by the City. No partial payments will be made.

1-05.18 Contractor's Daily Diary
(March 22, 2023 CFW GSP)

Section 1-05.18 is a new section:

The Contractor and subcontractors, as additional consideration for payment for this contract work, hereby agree to maintain and provide to the Owner and the Engineer a Daily Diary Record of this Work. The diary must be kept and maintained by the Contractor's designated project superintendent. Entries must be made on a daily basis and must accurately represent all of the project activities on each day.

At a minimum, the diary shall show on a daily basis:

- The day and date.
- The weather conditions, including changes throughout the day.
- A complete description of work accomplished during the day with adequate references to the Plans and Specifications so that the reader can easily and accurately identify said work in the Plans.
- An entry for each and every changed condition, dispute or potential dispute, incident, accident, or occurrence of any nature whatsoever which might affect the Contract, Owner, or any third party in any manner.
- Listing of any materials received and stored on or off-site by the Contractor for future installation, to include the manner of storage and protection of the same.
- Listing of materials installed during each day.
- List of all subcontractors working on-site during each day.
- Listing of the number of Contractor's employees working during each day by category of employment.
- Listing of Contractor's equipment working on the site during each day. Idle equipment on the site shall be listed and designated as idle.
- Notations to explain inspections, testing, stake-out, and all other services furnished to the Contractor by the Owner or other during each day.
- Entries to verify the daily (including non-work days) inspection and maintenance of traffic control devices and condition of the traveled roadway surfaces. The Contractor shall not allow any conditions to develop that would be hazardous to the public.
- Any other information that serves to give an accurate and complete record of the nature, quantity, and quality of the Contractor's progress on each day.
- Summary of total number of working days to date, and total number of delay days to date.

The Contractor's designated project superintendent must sign the diary at the end of each working day. The Contractor must provide a copy of the diary to the Owner and the Engineer each morning for the preceding workday. All copies must be legible.

It is expressly agreed between the contractor and the owner that the daily diary maintained by the Contractor shall be the “Contractor’s Book of Original Entry” for the documentation of any potential claims or disputes that might arise during this contract. Failure of the Contractor to maintain this diary in the manner described above will constitute a waiver of any such claims or disputes by the Contractor. The daily diary maintained by the Contractor does not constitute the official record of the project. The official record of the project is prepared and maintained exclusively by the engineer.

1-06 CONTROL OF MATERIAL

1-06.2 Acceptance of Materials

1-06.2(1) Samples and Tests for Acceptance ***(September 20, 2024 CFW GSP)***

Section 1-06.2(1) is supplemented as follows:

The Contractor shall be responsible to hire an independent, third-party testing company to conduct testing for the project, including but not limited to, gradation, concrete compressive strength, and compaction testing for aggregates and hot mix asphalt. The testing company shall be designated as a WSDOT-certified testing firm.

The testing company shall provide prompt results. Original test results shall be sent directly from the testing company to the City’s Project Engineer at jonathan.strong@cityoffederalway.com. Copies of test results shall also be sent to the Contractor.

Contractor shall cooperate with testing company’s personnel and provide access to work to be tested. Contractor shall be responsible to notify testing company in advance of operations requiring testing and inspection services. If Contractor does not coordinate for testing services with sufficient advance notice, they are responsible for any delays caused by the inability to proceed with work due to lack of testing. This will not be grounds for assignment of a non-working day.

Required tests and frequency shall be in conformance with the WSDOT Construction Manual.

The bid item “Material Testing” shall be measured on a lump sum basis and shall include all material testing required for the project. When the bid item for “Material Testing” appears on the proposal, the lump sum contract price for “Material Testing” shall include all costs associated with all Bid Schedules unless noted otherwise.

1-06.6 Recycled Materials ***(January 4, 2016 APWA GSP)***

Delete this section, including its subsections, and replace it with the following:

The Contractor shall make their best effort to utilize recycled materials in the construction of the project. Approval of such material use shall be as detailed elsewhere in the Standard Specifications.

Prior to Physical Completion the Contractor shall report the quantity of recycled materials that were utilized in the construction of the project for each of the items listed in Section 9-03.21. The report shall include hot mix asphalt, recycled concrete aggregate, recycled

glass, steel furnace slag and other recycled materials (e.g. utilization of on-site material and aggregates from concrete returned to the supplier). The Contractor's report shall be provided on DOT form 350-075 Recycled Materials Reporting.

1-07 LEGAL RELATIONS AND RESPONSIBILITIES TO THE PUBLIC

1-07.1 Laws to be Observed

(October 1, 2005 APWA GSP)

Supplement this section with the following:

In cases of conflict between different safety regulations, the more stringent regulation shall apply.

The Washington State Department of Labor and Industries shall be the sole and paramount administrative agency responsible for the administration of the provisions of the Washington Industrial Safety and Health Act of 1973 (WISHA).

The Contractor shall maintain at the project site office, or other well-known place at the project site, all articles necessary for providing first aid to the injured. The Contractor shall establish, publish, and make known to all employees, procedures for ensuring immediate removal to a hospital, or doctor's care, persons, including employees, who may have been injured on the project site. Employees should not be permitted to work on the project site before the Contractor has established and made known procedures for removal of injured persons to a hospital or a doctor's care.

The Contractor shall have sole responsibility for the safety, efficiency, and adequacy of the Contractor's Plant, appliances, and methods, and for any damage or injury resulting from their failure, or improper maintenance, use, or operation. The Contractor shall be solely and completely responsible for the conditions of the project site, including safety for all persons and property in the performance of the work. This requirement shall apply continuously, and not be limited to normal working hours. The required or implied duty of the Engineer to conduct construction review of the Contractor's performance does not, and shall not, be intended to include review and adequacy of the Contractor's safety measures in, on, or near the project site.

1-07.1(2) Health and Safety.

(April 12, 2019 CFW GSP)

Section 1-07.1(2) is supplemented with the following:

Confined Space

Confined spaces are known to exist at the following locations:

Existing storm drainage, sanitary sewer, and other utility systems, vaults, and structures, along with all new similar new construction items that meet the requirements of WAC 296-809-100.

The Contractor shall be fully responsible for the safety and health of all on-site workers and compliant with Washington Administrative Code (WAC 296-809).

The Contractor shall prepare and implement a confined space program for each of the confined spaces identified above. The Contractors Confined Space program shall be sent to the contracting agency at least 5 days prior to the Contractor beginning work in or adjacent to the confined space. No work shall be performed in or adjacent to the confined space until the plan is submitted to the Engineer as required. The Contractor shall

communicate with the Engineer to ensure a coordinated effort for providing and maintaining a safe worksite for both the Contracting Agency's and Contractor's workers when working in or near a confined space.

All costs to prepare and implement the confined space program shall be included in the bid prices for the various items associated with the confined space work.

1-07.2 State Taxes
(June 27, 2011 APWA GSP)

Delete this section, including its sub-sections, in its entirety and replace it with the following:

1-07.2 State Sales Tax

The Washington State Department of Revenue has issued special rules on the State sales tax. Sections 1-07.2(1) through 1-07.2(3) are meant to clarify those rules. The Contractor should contact the Washington State Department of Revenue for answers to questions in this area. The Contracting Agency will not adjust its payment if the Contractor bases a Bid on a misunderstood tax liability.

The Contractor shall include all Contractor-paid taxes in the unit Bid prices or other Contract amounts. In some cases, however, state retail sales tax will not be included. Section 1-07.2(2) describes this exception.

The Contracting Agency will pay the retained percentage (or release the Contract Bond if a FHWA-funded Project) only if the Contractor has obtained from the Washington State Department of Revenue a certificate showing that all Contract-related taxes have been paid (RCW 60.28.051). The Contracting Agency may deduct from its payments to the Contractor any amount the Contractor may owe the Washington State Department of Revenue, whether the amount owed relates to this Contract or not. Any amount so deducted will be paid into the proper State fund.

1-07.2(1) State Sales Tax — Rule 171

WAC 458-20-171, and its related rules, apply to building, repairing, or improving streets, roads, etc., which are owned by a municipal corporation, or political subdivision of the state, or by the United States, and which are used primarily for foot or vehicular traffic. This includes storm or combined sewer systems within and included as a part of the street or road drainage system and power lines when such are part of the roadway lighting system. For work performed in such cases, the Contractor shall include Washington State Retail Sales Taxes in the various unit Bid item prices, or other Contract amounts, including those that the Contractor pays on the purchase of the materials, equipment, or supplies used or consumed in doing the work.

1-07.2(2) State Sales Tax — Rule 170

WAC 458-20-170, and its related rules, apply to the constructing and repairing of new or existing buildings, or other structures, upon real property. This includes, but is not limited to, the construction of streets, roads, highways, etc., owned by the state of Washington; water mains and their appurtenances; sanitary sewers and sewage disposal systems unless such sewers and disposal systems are within, and a part of, a street or road drainage system; telephone, telegraph, electrical power distribution lines, or other conduits or lines in or above streets or roads, unless such power lines become a part of a street or road lighting system;

and installing or attaching of any article of tangible personal property in or to real property, whether or not such personal property becomes a part of the realty by virtue of installation.

For work performed in such cases, the Contractor shall collect from the Contracting Agency, retail sales tax on the full Contract price. The Contracting Agency will automatically add this sales tax to each payment to the Contractor. For this reason, the Contractor shall not include the retail sales tax in the unit Bid item prices, or in any other Contract amount subject to Rule 170, with the following exception.

Exception: The Contracting Agency will not add in sales tax for a payment the Contractor or a subcontractor makes on the purchase or rental of tools, machinery, equipment, or consumable supplies not integrated into the project. Such sales taxes shall be included in the unit Bid item prices or in any other Contract amount.

1-07.2(3) Services

The Contractor shall not collect retail sales tax from the Contracting Agency on any Contract wholly for professional or other services (as defined in Washington State Department of Revenue Rules 138 and 244).

1-07.6 Permits and Licenses

(April 12, 2018 CFW GSP)

Section 1-07.6 is supplemented with the following:

Survey Monuments

In accordance with RCW 58.24.040(8), no cadastral or geodetic survey monument may be disturbed without a valid permit to remove or destroy a survey monument, issued by the Washington State Department of Natural Resources. Permit applications can be obtained on the DNR Public Land Survey Office website. The permit application must be stamped by a registered Washington State Land Surveyor. The Contractor shall obtain the permit to Remove or Destroy a Survey Monument as necessary. All costs to obtain and comply with the permit shall be considered incidental to other bid items and no additional payment will be made.

(December 16, 2022 CFW GSP)

Section 1-07.6 is supplemented with the following:

Oversized Loads

The Contractor must obtain a permit from the City of Federal Way (Development Services Division) for any Oversize / Overweight Loads. Loads are classified as oversized / overweight if they exceed the following criteria:

Size

- 8'6" wide, 14' tall, 53' length (tractor/trailer)
- 40' single unit
- 75' overall with a truck and trailer
- 3' of front overhang and 15' of rear overhang

Weight

- Heavy loads require a permit for overweight if they exceed the vehicle weight table published by WSDOT. The gross vehicle weight for a vehicle or a vehicle combination is determined by an overlapping set of three criteria: tire size, axle weight, and the weight table.

1-07.7 Load Limits

(March 13, 1995 WSDOT GSP, OPTION 6)

Section 1-07.7 is supplemented with the following:

If the sources of materials provided by the Contractor necessitate hauling over roads other than State Highways, the Contractor shall, at the Contractor's expense, make all arrangements for the use of the haul routes.

1-07.9(3) Apprentices

(July 8, 2024 APWA GSP)

Section 1-07.9(3) is supplemented with the following:

Apprentice Utilization

This Contract includes an Apprentice Utilization Requirement. Fifteen percent or more of project Labor Hours shall be performed by Apprentices unless Good Faith Efforts are accepted. Apprentice Utilization will be determined using the Department of Labor and Industries (L&I) online Prevailing Wage Intent & Affidavit (PWIA) system.

Definitions

For the purposes of this specification the following definitions apply:

1. Apprentice is a person enrolled in a State-approved Apprenticeship Training Program.
2. Apprentice Utilization is the apprentice labor hours, on the project, expressed as a percentage of project Labor Hours based on certified payrolls or the affidavits of wages paid, whichever is least. The percentage is not rounded up.
3. Apprentice Utilization Requirement is the minimum percentage of apprentice labor hours required by the Contract.
4. Good Faith Effort(s) (GFE) describes the Contractor's efforts to meet the Apprentice Utilization Requirement including but not limited to the specific steps as described elsewhere in this specification.
5. Labor Hours are the total hours performed by all workers receiving an hourly wage who are subject to prevailing wage requirements for work performed on the Contract as defined by RCW 39.04.310. Labor Hours are determined based on the scope of work performed by the individuals, rather than the title of their occupations in accordance with WAC 296-127.
6. State-approved Apprenticeship Training Program is an apprenticeship training program approved by the Washington State Apprenticeship Council.
7. Apprentice Wage Rates are the applicable wage rates that are to be paid for an apprentice registered in a training program, separate from Journey Level rates, as set by the Washington State Apprenticeship Training Council and Washington State Department of Labor and Industries (L&I).

Electronic Reporting

The Contractor shall use the PWIA System to submit the "Apprentice Utilization Plan". Reporting instructions are available in the application.

Apprentice Utilization Plan

The Contractor shall submit an "Apprentice Utilization Plan" by filling out the Apprentice Utilization Plan Form (WSDOT Form 424-004) within 30 calendar days of execution, however no later than the preconstruction meeting, demonstrating how and when they intend to achieve the Apprentice Utilization Requirement. The Plan shall be in sufficient detail for the Engineer to track the Contractor's progress in meeting the utilization requirements. An Apprentice Utilization Plan shall be updated and resubmitted as the Work progresses or when requested by the Engineer.

If the Contractor is unable to demonstrate the ability to meet the Apprentice Utilization Requirement with their initial Apprentice Utilization Plan submission, an effort must be made to find additional registered apprentices to perform on the contract. If after attempts have been made at every tier and every scope, the Contractor must submit GFE documentation to the Contracting Agency. The Contractor shall actively seek out opportunities to meet the Apprentice Utilization Requirement during the construction Work.

Contacts

The Contractor may obtain information on State-approved Apprenticeship Training Programs by using the Apprentice Registration and Tracking System (ARTS) <https://secure.lni.wa.gov/arts-public/#/program-search> or contacting the Department of Labor and Industries directly at:

Specialty Compliance and Services Division, Apprenticeship Section, P.O. Box 44530, Olympia, WA 98504-4530 or by phone at (360) 902-5320.

Compliance

The Contractor is expected to make attempts to employ Apprentices and shall include the requirement in any subcontracts at any tier. In the event that the Contractor is unable to achieve the Apprentice Utilization Requirement, the Contractor shall submit GFE documentation demonstrating the efforts and attempts they made. Final GFE documentation shall be submitted to the Contracting Agency after Substantial Completion but no later than 30 days after Physical Completion.

If the Contractor fails to actively attempt to employ Apprentices, submit GFE documentation, or if the Engineer does not approve the GFE, the Contractor will be assessed a penalty. The Engineer will provide the Contractor with a written notice at Final Acceptance of the project informing the Contractor of the failure to comply with this specification which will include a calculation of the penalty to be assessed as provided for in the Payment section in this special provision.

If the Contractor achieves the required Apprentice Utilization an incentive will be assessed with Final Payment.

Good Faith Efforts

The GFE shall document the attempts (efforts) the Contractor (and any subcontractor at any tier) made to meet the Apprentice Utilization Requirement. Emails, letters, or other written communications with letterhead, titles, and contact information are required.

Documentation must include one or more of the following accepted GFEs:

1. Demonstrated Lack of Availability of Apprentices. Correspondence from State-approved Apprenticeship Training Program(s), with project specific responses confirming there is a lack of availability of Apprentices for this project.
2. Demonstrated Disproportionate Ratio of Material/Equipment/Products to Labor Hours. Documentation explaining the bid includes a disproportionate high cost of material/equipment/products to Labor Hours. (E.g., a \$2 M estimated contract includes \$1 M or more in procurement costs of equipment to be installed.)
3. Demonstrated Lack of Necessary Labor Hours. Correspondence from a State-approved Apprentice Training Programs confirming there is not enough time in the project to meet required journey level to apprentice training ratios.
4. Demonstrated Lack of Available Approved Programs. Correspondence from State-approved Apprentice Training Programs, confirming there are no programs that train for the scopes included/anticipated on the project. Contractor and state programs to submit training program detail needs and details that could be used for future program creation.
5. Funding Precedent. Documentation that shows conflicting, more restrictive, or precedent requirements for other training on the Project. Examples include, but are not limited to, Tribal Employment Rights (TERO), Federal Training Hours, or Special Training that affect the ability to use state-registered apprentices.
6. Warranty Work. Documentation from Original Equipment Manufacturers, or similar, confirming that work performed must only be completed by certified journey-level installers or risk voiding warranty, or similar.
7. Other Effort. The Contractor may submit other evidence, documentation, or rationale for not being able to achieve the required Apprentice Utilization that are not covered in the other efforts named. Other efforts will still need to be corroborated by an independent, knowledgeable third-party.

Contractors may receive a GFE credit for graduated Apprentice hours through the end of the calendar year for all projects worked on as long as the Apprentice remains continuously employed with the same Contractor/subcontractor they were working for when they graduated. If an Apprentice graduates during employment on a project of significant duration, they may be counted towards a GFE credit for up to one year after their graduation or until the end of the project (whichever comes first). Determination of whether Contract requirements were met in good faith will be made by subtracting the hours from the journeyman total reported hours for the project and adding them to the apprentice hour total. If the new utilization percentage meets the Contract requirement, the Contractor will be reported as meeting the requirement in good faith.

Approving Good Faith Efforts

The Contracting Agency will review submitted Good Faith Efforts and issue a determination. The Engineer may request additional information, documentation, evidence or similar in order to approve such efforts. A determination by the Engineer is final. The approved Good Faith Efforts will be loaded into the PWIA system by the Contracting Agency.

Payment

Payment will be made for the following Bid Items:

“Apprenticeship Incentive”, by calculation

An incentive of \$2,000.00 will be assessed with the Final Payment for Contractors who meet the Apprentice Utilization Requirement without a reduction by Good Faith Effort. For the purpose of providing a common proposal for all bidders, the Contracting Agency has entered an amount in the proposal to become a part of the total bid by the Contractor.

“Apprenticeship Penalty”, by calculation.

Apprenticeship Hours will be measured for each hour of work performed by an apprentice as shown on the Monthly Apprentice Utilization Report, based on certified payrolls or the affidavits of wages paid, whichever is least. The percentage is not rounded up. For the purpose of providing a common proposal for all bidders, the Contracting Agency has entered an amount in the proposal to become a part of the total bid by the Contractor.

When the Contractor fails to meet the Apprenticeship goal of 15%, a penalty will be assessed for each hour that is not achieved, unless a Good Faith Effort is approved by the Contracting Agency.

Apprenticeship Utilization Penalty will be calculated as described below:

Percent of goal met	Penalty per hour of unmet goal
100%	\$0.00
90% to 99%	\$2.00
75% to 89%	\$4.00
50% to 74%	\$6.00
1% to 49%	\$8.00
0%	\$10.00

The Contractor shall include all related costs in the unit Bid prices of the Contract, included but not limited to implementing, developing, documenting, and administering an apprenticeship utilization program, recording and reporting hours and all other costs to comply with this provision.

1-07.9(5)A Required Documents

(July 8, 2024 APWA GSP)

This section is revised to read as follows:

All Statements of Intent to Pay Prevailing Wages, Affidavits of Wages Paid and Certified Payrolls, including a signed Statement of Compliance for Federal-aid projects, shall be submitted to the Engineer and to the State L&I online Prevailing Wage Intent & Affidavit (PWIA) system. When apprenticeship is a requirement of the contract, include in PWIA all apprentices.

1-07.16 Protection and Restoration of Property

1-07.16(2) Vegetation Protection and Restoration

(August 2, 2010 WSDOT GSP)

Section 1-07.16(2) is supplemented with the following:

Vegetation and soil protection zones for trees shall extend out from the trunk to a distance of 1 foot radius for each inch of trunk diameter at breast height.

Vegetation and soil protection zones for shrubs shall extend out from the stems at ground level to twice the radius of the shrub.

Vegetation and soil protection zones for herbaceous vegetation shall extend to encompass the diameter of the plant as measured from the outer edge of the plant.

1-07.17 Utilities and Similar Facilities
(April 2, 2007 WSDOT GSP, OPTION 1)

Section 1-07.17 is supplemented with the following:

Locations and dimensions shown in the Plans for existing facilities are in accordance with available information obtained without uncovering, measuring, or other verification.

The following addresses and telephone numbers of utility companies known or suspected of having facilities within the project limits are supplied for the Contractor's convenience.

UTILITY CONTACTS

PUGET SOUND ENERGY (POWER & GAS)

Katie Dierick - Katie.Dierick@pse.com

Cell: (253) 268-6331

LAKEHAVEN WATER & SEWER DISTRICT

Dennis Hopper, Field Operations Supervisor - dhopper@lakehaven.org

Cell: (253) 261-1770

3203 SW Dash Point Rd; Federal Way, WA 98023

ZAYO

Zayo.Relo.Washington@zayo.com

LUMEN

Nathan Macleod – Nathan.macleod@Lumen.com

Tele: (253) 583-6283

7850 S Trafton S, Bldg B; Tacoma, WA 98409

COMCAST

Kyle Kinney – Kyle_Kinney@comcast.com

Tele: (253) 293-3838

410 Valley Ave NW; Puyallup, WA 98371

AT&T

Steve Duppenhaler

Tele: (425) 286-3822

11241 Willows Rd NE, #130; Redmond, WA 98052

KING COUNTY TRAFFIC (SIGNALS & STREET LIGHTS)

Mark Parrett

Tele: (206) 296-8153

155 Monroe Ave NE; Renton, WA 98056

CITY OF FEDERAL WAY IT DEPARTMENT (CITY FIBER)

Thomas Fichtner

Tele: (253) 835-2547
33325 8th Ave S
Federal Way, WA 98003

ADDITIONAL CONTACTS

CITY OF FEDERAL WAY POLICE

Tele: (253) 835-6701 (for officer traffic control scheduling)
Tele: (253) 835-6767 (for traffic / road closure issues)
33325 8th Ave S; Federal Way, WA 98003

SOUTH KING FIRE & RESCUE

Tele: 253) 946-7253
31617 1st Ave S; Federal Way, WA 98003

KING COUNTY METRO TRANSIT

Tele: (206) 684-2785
81270 6th Ave S, Bldg 2; Seattle, WA 98134

FEDERAL WAY SCHOOL DISTRICT

Please notify this entire group

Rob Bryant, Chief Finance & Operations Officer - rbryant@fwps.org
Michael Swartz, Exec. Director of Capital Projects - mswartz@fwps.org
Michelle Turner, Exec. Director of Transportation - mturner@fwps.org
Renee Swayze - rswayze@fwps.org
Mike Benzien, Exec. Director of Maint. & Operations - mbenzien@fwps.org
Brian Humphreys, Maintenance Manager - bhumphre@fwps.org
Paula Benz - pbenz@fwps.org

WASTE MANAGEMENT

Steve Frisbie (Route Manager, FW Residential) – sfrisbie@wm.com
Tele: (971) 990-9638
David Cruz (Route Manager, FW Commercial) – dcruz8@wm.com
Tele: (206) 580-6316

(October 3, 2022 WSDOT GSP, OPTION 2)

Section 1-07.17 is supplemented with the following:

Locations and dimensions shown in the Plans for existing facilities are in accordance with available information obtained without uncovering, measuring, or other verification.

Public and private utilities, or their Contractors, will furnish all work necessary to adjust, relocate, replace, or construct their facilities unless otherwise provided for in the Plans or these Special Provisions. Such adjustment, relocation, replacement, or construction will be done during the prosecution of the work for this project. It is anticipated that utility adjustment, relocation, replacement or construction within the project limits will be completed as follows:

- **LIST SPECIFIC UTILITY WORK TO TAKE PLACE DURING CONSTRUCTION. INCLUDE DESCRIPTION, LOCATION, AND DURATION.**
- Any other relocations, replacements, or adjustments as necessary

The Contractor shall attend a mandatory utility preconstruction meeting with the Engineer, all affected subcontractors, and all utility owners and their Contractors prior to beginning onsite work.

The following addresses and telephone numbers of utility companies or their Contractors that will be adjusting, relocating, replacing or constructing utilities within the project limits are supplied for the Contractor's use:

- See contact info listed in Section 1-07.17, Option 1

The Contractor shall:

- Provide franchise utilities with a minimum two-week advance notice to facilitate scheduling for their crews. Work will be completed by utilities after the area has been prepared by the City's contractor, including excavation and staking of appurtenant facilities such as right-of-way & back of sidewalk (line & grade).
- The Contractor shall coordinate scheduling of utility work with the utility companies involved and incorporate that work into the project schedule.
- **INCLUDE DETAILS OF ANY ADDITIONAL REQUIREMENTS (ADVANCE NOTIFICATIONS, COORDINATION DETAILS, ETC.)**

1-07.18 Public Liability and Property Damage Insurance ***(January 4, 2024 APWA GSP)***

Delete this section in its entirety, and replace it with the following:

1-07.18 Insurance

1-07.18(1) General Requirements

- A. The Contractor shall procure and maintain the insurance described in all subsections of section 1-07.18 of these Special Provisions, from insurers with a current A. M. Best rating of not less than A-: VII and licensed to do business in the State of Washington. The Contracting Agency reserves the right to approve or reject the insurance provided, based on the insurer's financial condition.
- B. The Contractor shall keep this insurance in force without interruption from the commencement of the Contractor's Work through the term of the Contract and for thirty (30) days after the Physical Completion date, unless otherwise indicated below.
- C. If any insurance policy is written on a claims-made form, its retroactive date, and that of all subsequent renewals, shall be no later than the effective date of this Contract. The policy shall state that coverage is claims made, and state the retroactive date. Claims-made form coverage shall be maintained by the Contractor for a minimum of 36 months following the Completion Date or earlier termination of this Contract, and the Contractor shall annually provide the Contracting Agency with proof of renewal. If renewal of the claims made form of coverage becomes unavailable, or economically prohibitive, the Contractor shall purchase an extended reporting period ("tail") or execute another form of guarantee acceptable to the Contracting Agency to assure financial responsibility for liability for services performed.
- D. The Contractor's Automobile Liability, Commercial General Liability and Excess or Umbrella Liability insurance policies shall be primary and non-contributory insurance as respects the Contracting Agency's insurance, self-insurance, or self-insured pool coverage. Any insurance, self-insurance, or self-insured pool coverage maintained by the

Contracting Agency shall be excess of the Contractor's insurance and shall not contribute with it.

- E. The Contractor shall provide the Contracting Agency and all additional insureds with written notice of any policy cancellation, within two business days of their receipt of such notice.
- F. The Contractor shall not begin work under the Contract until the required insurance has been obtained and approved by the Contracting Agency.
- G. Failure on the part of the Contractor to maintain the insurance as required shall constitute a material breach of contract, upon which the Contracting Agency may, after giving five business days' notice to the Contractor to correct the breach, immediately terminate the Contract or, at its discretion, procure or renew such insurance and pay any and all premiums in connection therewith, with any sums so expended to be repaid to the Contracting Agency on demand, or at the sole discretion of the Contracting Agency, offset against funds due the Contractor from the Contracting Agency.
- H. All costs for insurance shall be incidental to and included in the unit or lump sum prices of the Contract and no additional payment will be made.

1-07.18(2) Additional Insured

All insurance policies, with the exception of Workers Compensation, and of Professional Liability and Builder's Risk (if required by this Contract) shall name the following listed entities as additional insured(s) using the forms or endorsements required herein:

- The Contracting Agency and its officers, elected officials, employees, agents, and volunteers.
- Consultants hired by the Contracting Agency for construction support or materials testing.

The above-listed entities shall be additional insured(s) for the full available limits of liability maintained by the Contractor, irrespective of whether such limits maintained by the Contractor are greater than those required by this Contract, and irrespective of whether the Certificate of Insurance provided by the Contractor pursuant to 1-07.18(4) describes limits lower than those maintained by the Contractor.

For Commercial General Liability insurance coverage, the required additional insured endorsements shall be at least as broad as ISO forms CG 20 10 10 01 for ongoing operations and CG 20 37 10 01 for completed operations.

1-07.18(3) Subcontractors

The Contractor shall cause each subcontractor of every tier to provide insurance coverage that complies with all applicable requirements of the Contractor-provided insurance as set forth herein, except the Contractor shall have sole responsibility for determining the limits of coverage required to be obtained by subcontractors.

The Contractor shall ensure that all subcontractors of every tier add all entities listed in 1-07.18(2) as additional insureds, and provide proof of such on the policies as required by that section as detailed in 1-07.18(2) using an endorsement as least as broad as ISO CG 20 10 10 01 for ongoing operations and CG 20 37 10 01 for completed operations.

Upon request by the Contracting Agency, the Contractor shall forward to the Contracting Agency evidence of insurance and copies of the additional insured endorsements of each subcontractor of every tier as required in 1-07.18(4) Verification of Coverage.

1-07.18(4) Verification of Coverage

The Contractor shall deliver to the Contracting Agency a Certificate(s) of Insurance and endorsements for each policy of insurance meeting the requirements set forth herein when the Contractor delivers the signed Contract for the work. Failure of Contracting Agency to demand such verification of coverage with these insurance requirements or failure of Contracting Agency to identify a deficiency from the insurance documentation provided shall not be construed as a waiver of Contractor's obligation to maintain such insurance.

Verification of coverage shall include:

1. An ACORD certificate or a form determined by the Contracting Agency to be equivalent.
2. Copies of all endorsements naming Contracting Agency and all other entities listed in 1-07.18(2) as additional insured(s), showing the policy number. The Contractor may submit a copy of any blanket additional insured clause from its policies instead of a separate endorsement.
3. Any other amendatory endorsements to show the coverage required herein.
4. A notation of coverage enhancements on the Certificate of Insurance shall not satisfy these requirements – actual endorsements must be submitted.

Upon request by the Contracting Agency, the Contractor shall forward to the Contracting Agency a full and certified copy of the insurance policy(s). If Builders Risk insurance is required on this Project, a full and certified copy of that policy is required when the Contractor delivers the signed Contract for the work.

1-07.18(5) Coverages and Limits

The insurance shall provide the minimum coverages and limits set forth below. Contractor's maintenance of insurance, its scope of coverage, and limits as required herein shall not be construed to limit the liability of the Contractor to the coverage provided by such insurance, or otherwise limit the Contracting Agency's recourse to any remedy available at law or in equity.

All deductibles and self-insured retentions must be disclosed and are subject to approval by the Contracting Agency. The cost of any claim payments falling within the deductible or self-insured retention shall be the responsibility of the Contractor. In the event an additional insured incurs a liability subject to any policy's deductibles or self-insured retention, said deductibles or self-insured retention shall be the responsibility of the Contractor.

1-07.18(5)A Commercial General Liability

Commercial General Liability insurance shall be written on coverage forms at least as broad as ISO occurrence form CG 00 01, including but not limited to liability arising from premises, operations, stop gap liability, independent contractors, products-completed operations, personal and advertising injury, and liability assumed under an insured contract. There shall be no exclusion for liability arising from explosion, collapse or underground property damage.

The Commercial General Liability insurance shall be endorsed to provide a per project general aggregate limit, using ISO form CG 25 03 05 09 or an equivalent endorsement.

Contractor shall maintain Commercial General Liability Insurance arising out of the Contractor's completed operations for at least three years following Substantial Completion of the Work.

Such policy must provide the following minimum limits:

\$2,000,000	Each Occurrence
\$3,000,000	General Aggregate
\$3,000,000	Products & Completed Operations Aggregate
\$2,000,000	Personal & Advertising Injury each offense
\$2,000,000	Stop Gap / Employers' Liability each Accident

1-07.18(5)B Automobile Liability

Automobile Liability shall cover owned, non-owned, hired, and leased vehicles; and shall be written on a coverage form at least as broad as ISO form CA 00 01. If the work involves the transport of pollutants, the automobile liability policy shall include MCS 90 and CA 99 48 endorsements.

Such policy must provide the following minimum limit:

\$1,000,000	Combined single limit each accident
-------------	-------------------------------------

1-07.18(5)C Workers' Compensation

The Contractor shall comply with Workers' Compensation coverage as required by the Industrial Insurance laws of the State of Washington.

1-07.18(5)D Excess or Umbrella Liability

(January 4, 2016 APWA GSP)

The Contractor shall provide Excess or Umbrella Liability insurance with limits of not less than \$3,000,000 each occurrence and annual aggregate. This excess or umbrella liability coverage shall be excess over and as least as broad in coverage as the Contractor's Commercial General and Auto Liability insurance.

All entities listed under 1-07.18(2) of these Special Provisions shall be named as additional insureds on the Contractor's Excess or Umbrella Liability insurance policy.

This requirement may be satisfied instead through the Contractor's primary Commercial General and Automobile Liability coverages, or any combination thereof that achieves the overall required limits of insurance.

1-07.18(5)J Pollution Liability

(January 4, 2016 APWA GSP)

This is a new section as follows:

The Contractor shall provide a Contractors Pollution Liability policy, providing coverage for claims involving bodily injury, property damage (including loss of use of tangible property that has not been physically injured), cleanup costs, remediation, disposal or other handling of pollutants, including costs and expenses incurred in the investigation, defense, or settlement of claims, arising out of any one or more of the following:

1. Contractor's operations related to this project.

2. Remediation, abatement, repair, maintenance or other work with lead-based paint or materials containing asbestos.
3. Transportation of hazardous materials away from any site related to this project.

All entities listed under 1-07.18(2) of these Special Provisions shall be named by endorsement as additional insureds on the Contractors Pollution Liability insurance policy.

Such Pollution Liability policy shall provide the following minimum limits:
\$2,000,000 each loss and annual aggregate

1-07.23 Public Convenience and Safety

1.07.23(1) Construction Under Traffic ***(February 6, 2023 WSDOT GSP, OPTION 5)***

Section 1-07.23(1) is supplemented with the following:

Lane, ramp, shoulder, and roadway closures are subject to the following restrictions:

- The Contractor shall, at all times throughout the project, conduct the work in such a manner as will obstruct and inconvenience vehicular and pedestrian traffic as little as possible. The streets, sidewalks and private driveways shall be kept open by the Contractor except for the brief periods when actual work is being done. The Contractor shall conduct his operations so as to have under construction no greater length or amount of work than he can prosecute vigorously and he shall not open up sections of the work and leave them in an unfinished condition.
- The Contractor shall provide flaggers, signs, and other traffic control devices. The Contractor shall erect and maintain all construction signs, warning signs, detour signs, and other traffic control devices necessary to warn and protect the public at all times from injury or damage as a result of the Contractor's operations which may occur on highways, roads, streets, sidewalks, or paths. No work shall be done on or adjacent to any traveled way until all necessary signs and traffic control devices are in place.
- All signs and traffic control devices for the permitted closures shall only be installed during the specified hours. Construction signs, if placed earlier than the specified hours of closure, shall be turned or covered so as not to be visible to motorists.
- The Contractor shall keep all pedestrian routes & access points (including, but not limited to, sidewalks, and crosswalks when located within the project limits) open and clear at all times unless permitted otherwise by the Engineer in an approved traffic control plan. An ADA accessible route must be provided through the project site at all times.
- Pedestrians must have access to pedestrian push buttons at all times.
- Lane closures shall not impact business access. All businesses shall remain accessible by vehicles and pedestrian during business hours.
- Lane closures shall not restrict vehicular access for buses through the project site. Bus stops shall remain ADA accessible to pedestrians at all times throughout the project.

- The Contractor shall be responsible for notifying all affected property owners and tenants prior to commencing the barricading of streets, alleys, sidewalks and driveways. Notifications should be at least 48 hours in advance of closures, if possible.
- No paving or planing (milling) shall occur in residential areas during refuse, recycle, and yard waste collection days. Collection schedules are available at www.federalwaywa.gov/publicworks/recycling.
- For approved night work, it shall be the Contractor's responsibility to obtain any required noise variance or exemption for such work.
- For approved night work, the Contractor shall, at no additional cost to the City, make all arrangements for operations during hours of darkness. Flagger stations shall be illuminated using a minimum 150-watt floodlight. Lighting used for nighttime work shall, whenever possible, be directed away from or shielded from residences and oncoming traffic. Signs and barricades shall be supplemented by Type C steady burn lights to delineate edge of roadway during the hours of darkness.
- The Contractor may, if shown on a traffic control plan approved by the Engineer, momentarily interrupt continuous two-way traffic to allow one-way traffic (alternating directions / flagger controlled). Such interruptions shall utilize qualified flaggers placed in strategic locations to insure the public safety and minimize driver confusion.
- For projects with bid schedules located in multiple locations throughout the City, the Contractor shall not have personnel or subcontractors working on-site at more than two schedules at any given time.
- When school is in session at Sherwood Forest Elementary no lane closures may occur during student drop-off and pick-up times. Additionally, driveway ingress and egress shall be unobstructed during these times. Daily bell schedules, as well as calendars which reflect no-school days, early release days, and half-days are also available on fwps.org.
 - Student Drop-Off (typically in morning): No lane closures beginning 20 minutes prior to school start time until 10 minutes after school start time.
 - Student Pick-Up (typically in afternoon): No lane closures beginning 20 minutes prior to school end time until 20 minutes after school end time.

If the Engineer determines the permitted closure hours adversely affect traffic, the Engineer may adjust the hours accordingly. The Engineer will notify the Contractor in writing of any change in the closure hours. Exceptions to these restrictions are listed below and when applicable take precedence over closures listed above. The Engineer may also consider on a case-by-case basis additional exceptions following a written request by the Contractor.

Lane, ramp, shoulder, and roadway closures are not allowed on any of the following:

1. A holiday,
2. A holiday weekend; holidays that occur on Friday, Saturday, Sunday or Monday are considered a holiday weekend. A holiday weekend includes Saturday, Sunday, and the holiday.
3. After 12:00 PM (noon) on the day prior to a holiday or holiday weekend, and
4. Before 7:00 AM on the day after the holiday or holiday weekend.
5. Within the City Center zone from the Friday after Thanksgiving Day (“Black Friday”) until the first City recognized business day of the following year without written approval by the Engineer. The boundaries of the City Center zone are identified in the City of Federal Way Comprehensive Plan. In general, it is the area located within the following boundaries:
 - Northern boundary: S 312th Street
 - Southern boundary: S 324th Street
 - Eastern boundary: Interstate 5
 - Western boundary: 14th Ave S (future extension) / Federal Way 320th Library / 11th Pl S

Traffic Delays

When Automated Flagger Assistance Devices (AFADs) or flaggers are used to control traffic, traffic shall not be stopped for more than two minutes at any time. All traffic congestion shall be allowed to clear before traffic is delayed again.

If the delay becomes greater than two minutes, the Contractor shall immediately begin to take action to cease the operations that are causing the delays. If the two minute delay limit has been exceeded, as determined by the Engineer, the Contractor shall provide to the Engineer, a written proposal to revise his work operations to meet the two minute limit. This proposal shall be accepted by the Engineer prior to resuming any work requiring traffic control.

There shall be no delay to medical, fire, or other emergency vehicles. The Contractor shall alert all flaggers and personnel of this requirement.

General Restrictions

Construction vehicles using a closed traffic lane shall travel only in the normal direction of traffic flow unless expressly allowed in an accepted traffic control plan. Construction vehicles shall be equipped with flashing or rotating amber lights.

No two consecutive on-ramps, off-ramps, or intersections shall be closed at the same time and only one ramp at an interchange shall be closed, unless specifically shown in the Plans.

Roads or ramps that are designated as part of a detour shall not be closed or restricted during the implementation of that detour, unless specifically shown in the Plans.

Controlled Access

No special access or egress shall be allowed by the Contractor other than normal legal movements or as shown in the Plans.

Contractor's vehicles of 10,000 GVW or greater shall not exit or enter a lane open to public traffic except as follows:

Egress and ingress shall only occur during the hours of allowable lane closures, and:

1. For exiting an open lane of traffic, by decelerating in a lane that is closed during the allowable hours for lane closures.
2. For entering an open lane of traffic, by accelerating in a closed lane during the allowable hours for lane closures.

Traffic control vehicles are excluded from the gross vehicle weight requirement. If placing construction signs will restrict traveled lanes, then the work will be permitted during the hours of allowable lane closures.

Advance Notification

The Contractor shall notify the Engineer in writing of any traffic impacts related to lane closure, shoulder closure, sidewalk closure, or any combination for the week by 12:00 p.m. (noon) Wednesday the week prior to the stated impacts.

The Contractor shall notify the Engineer in writing ten working days in advance of any traffic impacts related to full roadway closure, ramp closure, or both.

The Contractor shall notify the Engineer in writing of any changes to the stated traffic impacts a minimum of 48 hours prior to the traffic impacts.

1-07.24 Rights of Way ***(July 23, 2015 APWA GSP)***

Delete this section and replace it with the following:

Street Right of Way lines, limits of easements, and limits of construction permits are indicated in the Plans. The Contractor's construction activities shall be confined within these limits, unless arrangements for use of private property are made.

Generally, the Contracting Agency will have obtained, prior to bid opening, all rights of way and easements, both permanent and temporary, necessary for carrying out the work. Exceptions to this are noted in the Bid Documents or will be brought to the Contractor's attention by a duly issued Addendum.

Whenever any of the work is accomplished on or through property other than public Right of Way, the Contractor shall meet and fulfill all covenants and stipulations of any easement agreement obtained by the Contracting Agency from the owner of the private property. Copies of the easement agreements may be included in the Contract Provisions or made available to the Contractor as soon as practical after they have been obtained by the Engineer.

Whenever easements or rights of entry have not been acquired prior to advertising, these areas are so noted in the Plans. The Contractor shall not proceed with any portion of the work in areas where right of way, easements or rights of entry have not been acquired

until the Engineer certifies to the Contractor that the right of way or easement is available or that the right of entry has been received. If the Contractor is delayed due to acts of omission on the part of the Contracting Agency in obtaining easements, rights of entry or right of way, the Contractor will be entitled to an extension of time. The Contractor agrees that such delay shall not be a breach of contract.

Each property owner shall be given 48 hours notice prior to entry by the Contractor. This includes entry onto easements and private property where private improvements must be adjusted.

The Contractor shall be responsible for providing, without expense or liability to the Contracting Agency, any additional land and access thereto that the Contractor may desire for temporary construction facilities, storage of materials, or other Contractor needs. However, before using any private property, whether adjoining the work or not, the Contractor shall file with the Engineer a written permission of the private property owner, and, upon vacating the premises, a written release from the property owner of each property disturbed or otherwise interfered with by reasons of construction pursued under this contract. The statement shall be signed by the private property owner, or proper authority acting for the owner of the private property affected, stating that permission has been granted to use the property and all necessary permits have been obtained or, in the case of a release, that the restoration of the property has been satisfactorily accomplished. The statement shall include the parcel number, address, and date of signature. Written releases must be filed with the Engineer before the Completion Date will be established.

(April 12, 2018 CFW GSP)

Section 1-07.24 is supplemented with the following:

The Contractor shall be responsible to abide by the right-of-entry agreements with adjacent property owners that have been obtained (if any) by the City for this project. Please note these agreements may be included as an appendix or will be made available upon request of the Contractor.

Right-of-entries on adjacent private property have been secured for purposes such as: construction of driveways, slope restoration, drainage, utilities, irrigation, and/or property restoration. The Contractor is expressly forbidden from using right-of-entry areas for vehicle or equipment storage or material stockpiling without first receiving written approval from the property owner. A copy of the written approval shall be provided to the Engineer before the Contractor stores any equipment or materials. Written permission from property owners does not relieve the Contractor of their obligation to receive permission from the City Community Development Department for the use of sites as staging areas, if required.

Right-of-entry agreements may include responsibilities for the Contractor, such as: listing property owners as additional insured; providing advance notice to certain representatives; or daily site cleanup requirements. These responsibilities are listed as examples only and the right-of-entry documents should be reviewed by the Contractor to determine all necessary requirements.

1-07.28 Communication with Businesses and Property Owners

(April 12, 2018 CFW GSP)

Section 1-07.28 is added:

The Contractor will be responsible for communicating all work activities with the property owners / tenants that are located adjacent to the project. The Contractor, along with the City's inspector & project engineer, shall have one formal meeting (door-to-door project walk-through) with the property owners/tenants prior to the start of construction. It will be the Contractor's responsibility to initiate and set up the meeting.

Thereafter, the Contractor shall keep the property owners / tenants informed of their general work locations and upcoming activities by distributing a monthly status/schedule memo to the businesses. The memo shall be approved by the City's Project Engineer prior to distribution.

1-07.29 Coordination with Transit Agencies
(December 1, 2021 CFW GSP)

Section 1-07.29 is added:

The Contractor is required to coordinate with impacted transit agencies. King County Metro and/or Pierce Transit personnel will remove and reinstall all existing bus stop signs and supports within the project limits. A copy of all communications between the contractor and transit agencies shall be forwarded to the City of Federal Way.

King County Metro: King County should be notified in writing at construction.coord@kingcounty.gov a minimum of five business days prior to starting any work impacting bus stops, a temporary lane or road closure. Work requiring removing a bus shelter or sign requires notification in writing a minimum of 30 business days.

Pierce Transit: Pierce Transit should be notified at (253)581-8130 to coordinate.

1-08 PROSECUTION AND PROGRESS

1-08.0 Preliminary Matters
(May 25, 2006 APWA GSP)

Add this new section.

1-08.0(1) Preconstruction Conference
(July 8, 2024 APWA GSP)

Add the following new section:

Prior to the Contractor beginning the work, a preconstruction conference will be held between the Contractor, the Engineer, and such other interested parties as may be invited. The purpose of the preconstruction conference will be:

1. To review the initial progress schedule;
2. To establish a working understanding among the various parties associated or affected by the work;
3. To establish and review procedures for progress payment, notifications, approvals, submittals, etc.;
4. To review DBE Requirements, Training Plans, and Apprenticeship Plans, when applicable.
5. To establish normal working hours for the work;
6. To review safety standards and traffic control; and

7. To discuss such other related items as may be pertinent to the work.

The Contractor shall prepare and submit at the preconstruction meeting the following:

1. A breakdown of all lump sum items;
2. A preliminary schedule of working drawing submittals; and
3. A list of material sources for approval if applicable.

1-08.0(2) Hours of Work
(December 8, 2014 APWA GSP)

Add the following new section:

Except in the case of emergency or unless otherwise approved by the Engineer, the normal working hours for the Contract shall be any consecutive 8-hour period between 7:00 a.m. and 6:00 p.m. Monday through Friday, exclusive of a lunch break. If the Contractor desires different than the normal working hours stated above, the request must be submitted in writing prior to the preconstruction conference, subject to the provisions below. The working hours for the Contract shall be established at or prior to the preconstruction conference.

All working hours and days are also subject to local permit and ordinance conditions (such as noise ordinances).

If the Contractor wishes to deviate from the established working hours, the Contractor shall submit a written request to the Engineer for consideration. This request shall state what hours are being requested, and why. Requests shall be submitted for review no later than noon two working days prior to the day(s) the Contractor is requesting to change the hours.

If the Contracting Agency approves such a deviation, such approval may be subject to certain other conditions, which will be detailed in writing. For example:

1. On non-Federal aid projects, requiring the Contractor to reimburse the Contracting Agency for the costs in excess of straight-time costs for Contracting Agency representatives who worked during such times. (The Engineer may require designated representatives to be present during the work. Representatives who may be deemed necessary by the Engineer include, but are not limited to: survey crews; personnel from the Contracting Agency's material testing lab; inspectors; and other Contracting Agency employees or third party consultants when, in the opinion of the Engineer, such work necessitates their presence.)
2. Considering the work performed on Saturdays, Sundays, and holidays as working days with regard to the contract time.
3. Considering multiple work shifts as multiple working days with respect to contract time even though the multiple shifts occur in a single 24-hour period.
4. If a 4-10 work schedule is requested and approved the non-working day for the week will be charged as a working day.
5. If Davis Bacon wage rates apply to this Contract, all requirements must be met and recorded properly on certified payroll.

(December 1, 2021 CFW GSP)

Add the following new section:

The Contractor may request extended work hours on days when paving operations are occurring. Work hours may be modified to 7:00 a.m. to 5:30 p.m. on paving days if the Engineer determines that the benefits of extended working hours will minimize the overall impacts to traffic. Extended work hours for paving will require PCMS boards to be placed a minimum of 2 business days prior to the paving day. Payment for PCMS boards shall be considered incidental to the Contractor's operations, unless there is a specific bid item for PCMS boards.

1-08.1 Subcontracting

1-08.1(7) Payments to Subcontractors and Lower-Tier Subcontractors

1-08.3 Progress Schedule

1-08.3(1) General Requirements

(October 3, 2022 WSDOT GSP, OPTION 2)

Section 1-08.3(1) is supplemented with the following:

In addition to information required in Items 1 through 6, the Progress Schedule shall include the following milestones and/or activities:

7. Materials requiring long procurement or fabrication periods, such as signal or light poles, structural elements, or mechanical items.

1-08.3(2)A Type A Progress Schedule

(December 30, 2022 APWA GSP)

Revise this section to read:

The Contractor shall submit 2 copies of a Type A Progress Schedule no later than at the preconstruction conference, or some other mutually agreed upon submittal time. The schedule may be a critical path method (CPM) schedule, bar chart, or other standard schedule format. Regardless of which format used, the schedule shall identify the critical path. The Engineer will evaluate the Type A Progress Schedule and approve or return the schedule for corrections within 15 calendar days of receiving the submittal.

1-08.4 Prosecution of Work

Delete this section and replace it with the following:

1-08.4 Notice to Proceed and Prosecution of Work

(July 23, 2015 APWA GSP)

Notice to Proceed will be given after the contract has been executed and the contract bond and evidence of insurance have been approved and filed by the Contracting Agency. The Contractor shall not commence with the work until the Notice to Proceed has been given by the Engineer. The Contractor shall commence construction activities on the project site within ten days of the Notice to Proceed Date, unless otherwise approved in writing. The Contractor shall diligently pursue the work to the physical completion date within the time specified in the contract. Voluntary shutdown or slowing of operations by the Contractor shall not relieve the Contractor of the responsibility to complete the work within the time(s) specified in the contract.

When shown in the Plans, the first order of work shall be the installation of high visibility fencing to delineate all areas for protection or restoration, as described in the Contract. Installation of high visibility fencing adjacent to the roadway shall occur after the placement of all necessary signs and traffic control devices in accordance with 1-10.1(2). Upon construction of the fencing, the Contractor shall request the Engineer to inspect the fence. No other work shall be performed on the site until the Contracting Agency has accepted the installation of high visibility fencing, as described in the Contract.

(December 1, 2021 CFW GSP)

Section 1-08.4 is supplemented with the following.

The Contractor shall provide adequate equipment and forces to carry out the construction schedule to completion of the contract by the date specified.

1-08.5 Time for Completion

(December 30, 2022 APWA GSP, OPTION A)

Revise the third and fourth paragraphs to read:

Contract time shall begin on the first working day following the Notice to Proceed Date.

Each working day shall be charged to the contract as it occurs, until the contract work is physically complete. If substantial completion has been granted and all the authorized working days have been used, charging of working days will cease. Each week the Engineer will provide the Contractor a statement that shows the number of working days: (1) charged to the contract the week before; (2) specified for the physical completion of the contract; and (3) remaining for the physical completion of the contract. The statement will also show the nonworking days and any partial or whole day the Engineer declares as unworkable. The statement will be identified as a Written Determination by the Engineer. If the Contractor does not agree with the Written Determination of working days, the Contractor shall pursue the protest procedures in accordance with Section 1-04.5. By failing to follow the procedures of Section 1-04.5, the Contractor shall be deemed as having accepted the statement as correct. If the Contractor is approved to work 10 hours a day and 4 days a week (a 4-10 schedule) and the fifth day of the week in which a 4-10 shift is worked would ordinarily be charged as a working day then the fifth day of that week will be charged as a working day whether or not the Contractor works on that day.

Revise the sixth paragraph to read:

The Engineer will give the Contractor written notice of the completion date of the contract after all the Contractor's obligations under the contract have been performed by the Contractor. The following events must occur before the Completion Date can be established:

1. The physical work on the project must be complete; and
2. The Contractor must furnish all documentation required by the contract and required by law, to allow the Contracting Agency to process final acceptance of the contract. The following documents must be received by the Project Engineer prior to establishing a completion date:
 - a. Certified Payrolls (per Section 1-07.9(5)).
 - b. Material Acceptance Certification Documents.
 - c. Monthly Reports of Amounts Credited as DBE Participation, as required by the Contract Provisions.

- d. Final Contract Voucher Certification.
- e. Copies of the approved “Affidavit of Prevailing Wages Paid” for the Contractor and all Subcontractors.
- f. A copy of the Notice of Termination sent to the Washington State Department of Ecology (Ecology); the elapse of 30 calendar days from the date of receipt of the Notice of Termination by Ecology; and no rejection of the Notice of Termination by Ecology. This requirement will not apply if the Construction Stormwater General Permit is transferred back to the Contracting Agency in accordance with Section 8-01.3(16).
- g. Property owner releases per Section 1-07.24.

(March 13, 1995 WSDOT GSP, OPTION 7)

Section 1-08.5 is supplemented with the following:

This project shall be physically complete within 120 working days.

1-08.6 Suspension of Work

(February 6, 2023 WSDOT GSP, OPTION 2)

Section 1-08.6 is supplemented with the following:

Contract time may be suspended for procurement of critical materials (Procurement Suspension). In order to receive a Procurement Suspension, the Contractor shall within 21 calendar days after execution by the Contracting Agency, place purchase orders for all materials deemed critical by the Contracting Agency for physical completion of the contract. The Contractor shall provide copies of purchase orders for the critical materials. Such purchase orders shall disclose the purchase order date and estimated delivery dates for such critical material.

The Contractor shall show procurement of the materials listed below as activities in the Progress Schedule. If the approved Progress Schedule indicates the materials procurement are critical activities, and if the Contractor has provided documentation that purchase orders are placed for the critical materials within the prescribed 21 calendar days, then contract time shall be suspended upon physical completion of all critical work except that work dependent upon the listed critical materials:

*** Contech Modular Wetlands ***

Charging of contract time will resume upon delivery of the critical materials to the Contractor or 90 calendar days after execution by the Contracting Agency, whichever occurs first.

1-08.9 Liquidated Damages

(March 3, 2021 APWA GSP, OPTION A)

Replace Section 1-08.9 with the following:

Time is of the essence of the Contract. Delays inconvenience the traveling public, obstruct traffic, interfere with and delay commerce, and increase risk to Highway users. Delays also cost tax payers undue sums of money, adding time needed for administration, engineering, inspection, and supervision.

Accordingly, the Contractor agrees:

1. To pay liquidated damages in the amount of *****\$1\$***** for each working day beyond the number of working days established for Physical Completion, and
2. To authorize the Engineer to deduct these liquidated damages from any money due or coming due to the Contractor.

When the Contract Work has progressed to Substantial Completion as defined in the Contract, the Engineer may determine the Contract Work is Substantially Complete. The Engineer will notify the Contractor in writing of the Substantial Completion Date. For overruns in Contract time occurring after the date so established, liquidated damages identified above will not apply. For overruns in Contract time occurring after the Substantial Completion Date, liquidated damages shall be assessed on the basis of direct engineering and related costs assignable to the project until the actual Physical Completion Date of all the Contract Work. The Contractor shall complete the remaining Work as promptly as possible. Upon request by the Project Engineer, the Contractor shall furnish a written schedule for completing the physical Work on the Contract.

Liquidated damages will not be assessed for any days for which an extension of time is granted. No deduction or payment of liquidated damages will, in any degree, release the Contractor from further obligations and liabilities to complete the entire Contract.

1-09 MEASUREMENT AND PAYMENT

1-09.2(1) General Requirements for Weighing Equipment **(January 4, 2024 APWA GSP, OPTION B)**

Revise item 4 of the fifth paragraph to read:

4. Test results and scale weight records for each day's hauling operations are provided to the Engineer daily. Reporting shall utilize WSDOT form 422-027A, Scaleman's Daily Report, unless the printed ticket contains the same information that is on the Scaleman's Daily Report Form. The scale operator must provide AM and/or PM tare weights for each truck on the printed ticket.

1-09.2(5) Measurement **(December 30, 2022 APWA GSP)**

Revise the first paragraph to read:

Scale Verification Checks – At the Engineer's discretion, the Engineer may perform verification checks on the accuracy of each batch, hopper, or platform scale used in weighing contract items of Work.

1-09.6 Force Account **(December 30, 2022 APWA GSP)**

Supplement this section with the following:

The Contracting Agency has estimated and included in the Proposal, dollar amounts for all items to be paid per force account, only to provide a common proposal for Bidders. All such dollar amounts are to become a part of Contractor's total bid. However, the Contracting Agency does not warrant expressly or by implication, that the actual amount of work will correspond with those estimates. Payment will be made on the basis of the amount of work actually authorized by the Engineer.

1-09.7 Mobilization **(March 22, 2023 CFW GSP)**

Supplement Section 1-09.7 with the following:

Obtaining a site for the Contractor's mobilization, field office(s), storage of materials, access and personnel parking spaces, and other general operations shall be the responsibility of the Contractor. The Contractor will be responsible for maintaining these spaces in a safe and orderly condition throughout the duration of the project. The Contractor shall provide the City with a copy of agreement(s) with property owner. All costs associated with securing sites shall be included in the other bid items on the project and no other compensation will be made.

(December 30, 2022 APWA GSP)

Delete this Section and replace it with the following:

Mobilization consists of preconstruction expenses and costs of preparatory Work and operations performed by the Contractor typically occurring before 10 percent of the total original amount of an individual Bid Schedule is earned from other Contract items on that Bid Schedule. Items which are not to be included in the item of Mobilization include but are not limited to:

1. Portions of the Work covered by the specific Contract item or incidental Work which is to be included in a Contract item or items.
2. Profit, interest on borrowed money, overhead, or management costs.
3. Costs incurred for mobilizing equipment for force account Work.

Based on the lump sum Contract price for "Mobilization", partial payments will be made as follows:

1. When 5 percent of the total original Bid Schedule amount is earned from other Contract items on that original Bid Schedule, excluding amounts paid for materials on hand, 50 percent of the Bid Item for mobilization on that original Bid Schedule, 5 percent of the total of that original Bid Schedule, or 5 percent of the total original Contract amount, whichever is the least, will be paid.
2. When 10 percent of the total original Bid Schedule amount is earned from other Contract items on that original Bid Schedule, excluding amounts paid for materials on hand, 100 percent of the Bid Item for mobilization on that original Bid Schedule, 10 percent of the total of that original Bid Schedule, or 10 percent of the total original Contract amount, whichever is the least, will be paid.
3. When the Substantial Completion Date has been established for the project, payment of any remaining amount Bid for mobilization will be paid.

Nothing herein shall be construed to limit or preclude partial payments otherwise provided by the Contract.

1-09.9 Payments

(July 8, 2024 APWA GSP, OPTION B)

Delete the fourth paragraph and replace it with the following:

Progress payments for completed work and material on hand will be based upon progress estimates prepared by the Engineer. A progress estimate cutoff date will be established at the preconstruction conference.

The initial progress estimate will be made not later than 30 days after the Contractor commences the work, and successive progress estimates will be made every month

thereafter until the Completion Date. Progress estimates made during progress of the work are tentative, and made only for the purpose of determining progress payment. The progress estimates are subject to change at any time prior to the calculation of the Final Payment.

The value of the progress estimate will be the sum of the following:

1. Unit Price Items in the Bid Form – the approximate quantity of acceptable units of work completed multiplied by the unit price.
2. Lump Sum Items in the Bid Form – based on the approved Contractor’s lump sum breakdown for that item, or absent such a breakdown, based on the Engineer’s determination.
3. Materials on Hand – 100 percent of invoiced cost of material delivered to Job site or other storage area approved by the Engineer.
4. Change Orders – entitlement for approved extra cost or completed extra work as determined by the Engineer.

Progress payments will be made in accordance with the progress estimate less:

1. Retainage per Section 1-09.9(1), on non FHWA-funded projects;
2. The amount of Progress Payments previously made; and
3. Funds withheld by the Contracting Agency for disbursement in accordance with the Contract Documents.

Progress payments for work performed shall not be evidence of acceptable performance or an admission by the Contracting Agency that any work has been satisfactorily completed. The determination of payments under the contract will be final in accordance with Section 1-05.1.

1-09.11(3) Time Limitation and Jurisdiction
(December 30, 2022 APWA GSP)

Revise this section to read:

For the convenience of the parties to the Contract it is mutually agreed by the parties that all claims or causes of action which the Contractor has against the Contracting Agency arising from the Contract shall be brought within 180 calendar days from the date of final acceptance (Section 1-05.12) of the Contract by the Contracting Agency; and it is further agreed that all such claims or causes of action shall be brought only in the Superior Court of the county where the Contracting Agency headquarters is located, provided that where an action is asserted against a county, RCW 36.01.050 shall control venue and jurisdiction. The parties understand and agree that the Contractor’s failure to bring suit within the time period provided, shall be a complete bar to all such claims or causes of action. It is further mutually agreed by the parties that when claims or causes of action which the Contractor asserts against the Contracting Agency arising from the Contract are filed with the Contracting Agency or initiated in court, the Contractor shall permit the Contracting Agency to have timely access to all records deemed necessary by the Contracting Agency to assist in evaluating the claims or action.

1-09.13 Claim Resolution

1-09.13(1) General
(December 30, 2022 APWA GSP)

Revise this Section to read

Prior to seeking claims resolution through arbitration or litigation, the Contractor shall proceed in accordance with Sections 1-04.5 and 1-09.11. The provisions of Sections 1-04.5 and 1-09.11 must be complied with in full as a condition precedent to the Contractor's right to seek claim resolution through binding arbitration or litigation.

Any claims or causes of action which the Contractor has against the Contracting Agency arising from the Contract shall be resolved, as prescribed herein, through binding arbitration or litigation.

The Contractor and the Contracting Agency mutually agree that those claims or causes of action which total \$1,000,000 or less, which are not resolved by mediation, shall be resolved through litigation unless the parties mutually agree in writing to resolve the claim through binding arbitration.

The Contractor and the Contracting Agency mutually agree that those claims or causes of action in excess of \$1,000,000, which are not resolved by mediation, shall be resolved through litigation unless the parties mutually agree in writing to resolve the claim through binding arbitration.

1-09.13(3)A Arbitration General
(January 19, 2022 APWA GSP)

Revise the third paragraph to read:

The Contracting Agency and the Contractor mutually agree to be bound by the decision of the arbitrator, and judgment upon the award rendered by the arbitrator may be entered in the Superior Court of the county in which the Contracting Agency's headquarters is located, provided that where claims subject to arbitration are asserted against a county, RCW 36.01.050 shall control venue and jurisdiction of the Superior Court. The decision of the arbitrator and the specific basis for the decision shall be in writing. The arbitrator shall use the Contract as a basis for decisions.

1-09.13(4) Venue for Litigation
(December 30, 2022 APWA GSP)

Revise this section to read:

Litigation shall be brought in the Superior Court of the county in which the Contracting Agency's headquarters is located, provided that where claims are asserted against a county, RCW 36.01.050 shall control venue and jurisdiction of the Superior Court. It is mutually agreed by the parties that when litigation occurs, the Contractor shall permit the Contracting Agency to have timely access to all records deemed necessary by the Contracting Agency to assist in evaluating the claims or action.

1-10 Temporary Traffic Control

1-10.1 General

1-10.1(2) Description
(April 12, 2018 CFW GSP)

Section 1-10.1(2) is supplemented with the following:

Business Open During Construction Signs

The Contractor shall provide a "Business Open During Construction" sign at every non-residential driveway approach within the project limits. Business Open During Construction Signs shall be considered Construction Signs Class A.

City of Federal Way Project Signs

City of Federal Way Project signs shall be considered Construction Signs Class A. The Contractor shall provide two (2) project signs (4' x 8') per the detail available from the City.

1-10.2 Traffic Control Management
(November 2, 2022 WSDOT GSP, OPTION 1)

1-10.2(1) General
(October 3, 2022 WSDOT GSP, OPTION 1)

Section 1-10.2(1) is supplemented with the following:

The Traffic Control Supervisor shall be certified by one of the following:

The Northwest Laborers-Employers Training Trust
27055 Ohio Ave.
Kingston, WA 98346
(360) 297-3035
<https://www.nwlett.edu>

Evergreen Safety Council
12545 135th Ave. NE
Kirkland, WA 98034-8709
1-800-521-0778
<https://www.esc.org>

The American Traffic Safety Services Association
15 Riverside Parkway, Suite 100
Fredericksburg, Virginia 22406-1022
Training Dept. Toll Free (877) 642-4637
Phone: (540) 368-1701
<https://altssa.com/training>

Integrity Safety
13912 NE 20th Ave
Vancouver, WA 98686
(360) 574-6071
<https://www.integritysafety.com>

US Safety Alliance
(904)705-5660
<https://www.ussafetyalliance.com>

K&D Services Inc.
2719 Rockefeller Ave.
Everett, WA 98201
(800) 343-4049
<https://www.kndservices.net>

1-10.2(2) Traffic Control Plans
(September 20, 2024 CFW GSP)

Section 1-10.2(2) is supplemented with the following:

The following minimum Traffic Control requirements shall be maintained during the construction of the project:

1. If the Contractor opts to utilize traffic control plans other than those provided in these Contract Documents, the Contractor shall provide traffic control plans to the City of Federal Way for review and approval a minimum of five (5) working days prior to implementation. These plans shall supplement Construction Staging Plans. The plans as provided by the Contractor shall include and not be limited to the following information:
 - Stop line locations with station and offset to verify safety of intersection turning radius for vehicles.
 - Minimum lane widths provided for vehicular travel.
 - Turn pocket length, gap, and tapers in conformance with the City of Federal Way Standard Details.
2. Detours will not be allowed except as noted herein or Section 1-07.23(2) as amended.
3. Temporary paint striping, reflective marking tape, and/or retroreflective tubular markers shall be required for each shift of traffic control. The Contractor shall provide temporary striping, reflective marking tape, and/or reflective tubular markers as required at the direction of the Engineer.
4. The Contractor provided Traffic Control Plans shall lay out traffic control device spacing, tapers, etc., to scale, and shall contain accurate dimensions and legends and shall be signed by the preparer.

1-10.3 Traffic Control Labor, Procedures and Devices

1-10.3(1)C Signalized Intersection Traffic Control ***(September 3, 2021 CFW GSP)***

Section 1-10.3(1)C is a new section:

Signalized Intersection Traffic Control is required when a signal system is in flashing mode, or is not operational. Signalized intersection traffic may not be flagged with an active signal in full operation.

Placing a signalized intersection into flash mode requires an approved traffic control plan. Additionally, the days/times that a signal is placed into flash mode must be pre-approved by the City. The signal should only be switched into flash mode by the City. The type of work that requires signals to be placed into flash mode may include, but is not limited to: installation of signal poles, signal switchover, paving, striping, or excavation in the intersection.

The Contractor shall minimize the limits of the work zone area at intersections whenever possible in order to avoid having the signal be placed into flash mode.

Signalized Intersection Traffic Control Labor shall conform to WAC 468-95-302 and approved traffic control plans.

If flaggers are utilized to provide traffic control of signalized intersections:

- At least two flaggers are required to flag from the center of the intersection, in addition to a flagger controlling each leg of the intersection.

If off-duty Uniformed Police Officers are utilized to provide traffic control of signalized intersections:

- A uniformed police officer (UPO) is a sworn police officer from a local law enforcement agency or a Washington State Patrol officer.
- Off-duty uniformed police officers must have a marked police vehicle with them on the project site. Unmarked police vehicles or personal vehicles are not acceptable.
- There is currently no availability of UPO's from the City of Federal Way Police Department. Many other law enforcement agencies also have little to no availability of off-duty officers. No other agencies or private companies are authorized to perform off-duty work within the City without project-specific approval from the Federal Way Police Chief or his designee. If the Contractor is able to procure a UPO from another law enforcement agency that is acceptable to the Federal Way Chief of Police, a change order will be required to add a bid item for "Contractor Provided Off-Duty Uniformed Police Officer".

END OF DIVISION 1

DIVISION 2 EARTHWORK

2-01 CLEARING, GRUBBING, AND ROADSIDE CLEANUP

2-01.1 Description

(March 13, 1995 WSDOT GSP, OPTION 1)

Section 2-01.1 is supplemented with the following:

Clearing and grubbing on this project shall be performed within the following limits:

Limits for clearing & grubbing shall be as shown on the plans. Clearing shall include removal of trees as noted on the plans or as directed by the Engineer to accommodate the improvements. Tree removal shall include removal of stumps and/or grinding of stumps to a depth at least two feet below finish grade.

2-01.3 Construction Requirements

2-01.3(3) Clearing Limit Fence

(April 12, 2018 CFW GSP)

Section 2-01.3(3) is a new section:

Clearing limit fence shall be 4-feet high, orange, high density polyethylene fencing with mesh openings 1½-inch by 3-inches nominal and weigh at least 7 oz. per linear foot. Either wood or steel posts shall be used. Wood posts shall have minimum dimensions of 1½ inches by 1½ inches by the minimum length of 5 feet, and shall be free of knots, splits, or gouges. Steel posts shall consist of either size No. 6 rebar or larger, ASTM A 120 steel pipe with a minimum diameter of 1 inch, U, T, L or C shape steel posts with a minimum weight of 1.35 lbs./ft. or other steel posts having equivalent strength and bending resistance to the post sizes listed. The spacing of the support posts shall be a maximum of 6½ feet.

2-01.3(4) Roadside Cleanup

(January 5, 1998 WSDOT GSP, OPTION 1)

Section 2-01.3(4) is supplemented with the following:

The Contractor shall restore, repair or correct all portions of the roadside or adjacent landscapes that were unavoidably damaged due to the performance or installation of the specified work. Unavoidable damage shall be determined only by the Engineer. All materials utilized shall be in accordance with Sections 9-14 and 9-15 and other applicable sections of the Standard Specifications or Special Provisions, whichever may apply. All work shall be performed in accordance with Sections 8-02 and 8-03 and other applicable sections of the Standard Specifications. The Contractor shall review the work with the Engineer and receive approval to proceed prior to commencing the work.

2-01.4 Measurement

(April 12, 2018 CFW GSP)

Section 2-01.4 is supplemented with the following:

“Clearing and Grubbing” will be measured on a lump sum basis. Installation, maintenance, and removal of the Clearing Limit Fence shall be included in the Clearing and Grubbing bid item.

“Tree Removal”, will be measured per each and includes root removal.

2-01.5 Payment

(April 12, 2018 CFW GSP)

Section 2-01.5 is supplemented with the following:

“Clearing and Grubbing”, lump sum.

“Tree Removal”, per each.

2-02 REMOVAL OF STRUCTURES AND OBSTRUCTIONS

2-02.3 Construction Requirements

(September 7, 2021 WSDOT GSP, OPTION 1)

Section 2-02.3 is supplemented with the following:

(October 4, 2021 WSDOT GSP, OPTION 5)

Section 2-02.3 is supplemented with the following:

Removal and Disposal of Asbestos Material

In the event suspected Asbestos Containing Material (ACM) is encountered, the Contractor shall immediately notify the Engineer and the provisions of Section 1-04.7 shall apply. Prior to commencing asbestos related work, the Contractor shall obtain all permits from and provide notification to, the Washington State Department of Labor and Industries, the Washington State Department of Ecology, the local clean air agency, and other permitting and regulatory agencies with jurisdiction over the work involving asbestos as the laws, rules, and regulations require.

The ACM shall only be disturbed under the supervision of a Washington State Certified Asbestos Supervisor (CAS). The CAS shall be certified in accordance with WAC 295-65-012.

The CAS shall supervise the asbestos removal and ensure that the handling and removal of asbestos is accomplished by certified asbestos workers and in accordance with Washington State Department of Labor and Industries standards. The Contractor shall ensure that the removal and disposal of asbestos meets the requirements of EPA regulation 40 CFR Part 61, local health department regulations, and all other applicable regulations.

No asbestos is expected to be encountered. However, if the Contractor believes they have encountered asbestos, they shall immediately notify the Engineer in accordance with Section 1-04.7.

2-02.3(3) Removal of Pavement, Sidewalks, Curbs, and Gutters

(April 12, 2018 CFW GSP)

Section 2-02.3(3) is supplemented with the following:

Prior to removal of pavement, the Contractor shall make a full-depth sawcut to delineate the areas of pavement removal from those areas of pavement to remain. The Engineer shall approve the equipment and procedures used to make the full-depth sawcut. No wastewater from the sawcutting operation shall be released directly to any stream or storm sewer system.

(December 1, 2021 CFW GSP)

Section 2-02.3(3) is supplemented with the following:

Removal of pavement, curbs, gutters, and sidewalks within the entire project limits shall be measured and paid as "Roadway Excavation incl. Haul" in accordance with Section 2-03.

2-02.3(4) Removal of Drainage Structures
(April 12, 2018 CFW GSP)

Section 2-02.3(4) is a new section:

Where shown in the Plans or where designated by the Engineer, the Contractor shall remove existing catch basins, manholes, pipes, and other drainage features in accordance with Section 2-02 of the Standard Specifications. Removal shall be conducted in such a manner as to prevent damage to surrounding facilities including any existing storm sewers, sanitary sewers, electrical conduits or other facilities to remain. All remaining facilities including but not limited to storm sewers, sanitary sewers, monuments, valves, vaults, and electrical conduits damaged due to the Contractor's operations shall be replaced by the Contractor to the satisfaction of the Engineer at no additional cost to the Contracting Agency. Catch basins, manholes, and other drainage structures designated for removal, including all debris, shall be completely removed. All removed catch basins, manholes, and other drainage structures shall become the property of the Contractor and shall be disposed of in accordance with Section 2-02 of the Standard Specifications. All undamaged frames, grates, and solid covers in a re-useable condition shall become the property of the City of Federal Way and shall be delivered to a location specified by the Engineer.

Sawcutting (full depth) of existing asphalt concrete pavement and cement concrete curb and gutter surrounding the structure required for removal will be considered incidental to the removal of the catch basin, manhole, or other drainage structures. Sawcuts shall be in accordance with Section 2-02 of these Special Provisions.

Backfilling of catch basins, manholes, pipes and other drainage structures to be removed and replaced shall not be performed until the new structure is installed and shall be in accordance with Section 7-05. Backfilling of a structure to be replaced shall be considered incidental to the construction and installation of the new catch basin, manhole, or other drainage structure. Backfilling of catch basins, manholes, pipes and other drainage structures to be completely removed shall be performed using gravel borrow paid in accordance with the Bid Schedule.

Prior to backfilling any voids, the Contractor shall remove pipe as noted in the plans. Pipe shown to be abandoned or ordered by the Engineer to be abandoned shall be filled with CDF in accordance with Section 2-09.3(1)E of the Standard Specifications. Plugging pipe ends shall be considered incidental and included in the pipe removal and no additional payment will be made.

The Contractor shall maintain existing drainage, where designated by the Engineer, until the new drainage system is completely installed and functioning.

2-02.3(5) Adjust Existing Utility to Grade
(September 20, 2024 CFW GSP)

2-02.3(5) is a new section:

As shown in the Plans, existing utilities such as monuments, manholes, catch basin frames and grates, water valves, and meter boxes shall be adjusted to finished grade. The Contractor shall, prior to the beginning of any work, familiarize himself with the existing

utility locations. The Contractor shall adjust City-owned utilities. Final adjustment shall be smooth and flush with finished grade. The Contractor shall mark the location of all utilities prior to paving the new surface. Unless otherwise provided for in the Special Provisions and Proposal, costs for adjusting utilities to grade, including coordinating the work with other utilities, shall be incidental to the various items of work and no additional compensation will be allowed.

Existing facilities shall be adjusted to the finished grade as shown in the Drawings and as further specified herein. Existing box, ring, grate, and cover shall be reset in a careful and workmanlike manner to conform to the new grade. Special care shall be exercised in all operations. Any damage occurring to the manholes, concrete inlets, monument cases, valve boxes, or water mains, due to the Contractor's operations, shall be repaired at the Contractor's own expense. Adjustments shall be made using bricks, concrete blocks, or cement, and the interior of the manhole adjustment shall be mortared smoothly. All covers and frames shall be thoroughly cleaned. The Contractor shall be responsible for referencing and keeping a record of such references of all manholes, catch basins, monument cases, meter boxes, and valve boxes encountered, and shall submit a copy of these references to the Engineer.

The manholes, catch basins, monument cases, meter boxes, and valve boxes shall be adjusted to grade in accordance with Section 1-05.3(1). Final restoration of finished grade surfaces shall be performed in the following manner:

1. Within a Gravel Surface: Provide a 6-inch-deep and 6-inch-wide concrete collar installed and restored with 3 inches of crushed surfacing top course.
2. Within a Grass Surface: Provide crushed surfacing top course backfill and 3 inches of Topsoil Type A, and seed.
3. Within an Asphalt Cement Concrete Paved Surface: See City of Federal Way Standard Details for Utility Adjustment.

2-02.4 Vacant

(December 1, 2021 CFW GSP)

Section 2-02.4 Vacant shall be deleted and replaced with the following:

2-02.4 Measurement

"Sawcutting" will be measured by the linear foot for pavement removal.

"Remove Existing Catch Basin" will be measured per each.

2-02.5 Payment

(December 1, 2021 CFW GSP)

Section 2-02.5 is supplemented with the following:

Payment will be made in accordance with Section 1-04.1 for the following bid items when included in the proposal:

"Removal of Structure and Obstruction", lump sum. Structure Excavation Class B for the removal of items shall be considered included in this bid item.

"Sawcutting", per linear foot. Sawcutting necessary for utility and stormwater installation are incidental to the measurement and payment of those contract items.

“Remove Existing Catch Basin”, per each.

2-03 ROADWAY EXCAVATION AND EMBANKMENT

2-03.2 Pavement Removal

(April 12, 2018 CFW GSP)

Section 2-03.2 is replaced with the following:

Where shown in the Plans or where designated by the Engineer, the Contractor shall remove asphalt, concrete, Portland cement concrete pavement, sidewalks and curbs.

Prior to removal, the Contractor shall make a full-depth sawcut to delineate the areas of pavement removal from those areas of pavement to remain. The Engineer shall approve the equipment and procedures used to make the full-depth sawcut. No wastewater from the sawcutting operation shall be released directly to any stream or storm sewer system. Alternatively, the Contractor may elect grinding for pavement removal, where appropriate.

The removed pavement shall become the property of the Contractor and shall be removed from the project. Damage caused to portions of the pavement to remain, due to the Contractor's operation, shall be repaired by the Contractor at the Contractor's expense and to the satisfaction of the Engineer.

Removal of pavement, sidewalks, curbs, and gutters throughout the project shall be measured and paid as “Roadway Excavation Incl. Haul” and no additional payment will be made.

2-03.3 Construction Requirements

Section 2-03.3(10) Selected Material

(April 12, 2018 CFW GSP)

Section 2-03.3(10) is supplemented with the following:

Selected Material when specified or required by the Engineer for use on the project shall meet the requirements of specified in Section 9-03.14(3) for Common Borrow.

Section 2-03.3(14)E Unsuitable Foundation Excavation

(August 27, 2021 CFW GSP)

Section 2-03.3(14)E is supplemented with the following:

All embankments shall be founded on dense, non-yielding granular foundation soil as approved by the engineer. Remove all organic materials and debris, trash, or other deleterious material prior to beginning construction of new embankments. Proof roll the foundation.

Section 2-03.3(14)G Backfilling

(February 21, 2024 CFW GSP)

Section 2-03.3(14)G is supplemented with the following:

Remove all water and non-compatible materials from excavations prior to backfilling or attempting to compact embankment soil. Provide import Gravel Borrow as required to complete the work. Backfill all embankments in accordance with 2-03.3(14)C, Compacting Earth Embankments, Method C.

Section 2-03.3(14)N Wet Weather Earthwork

(April 12, 2018 CFW GSP)

Section 2-03.3(14)N is a new section:

Earthwork completed in wet weather or under wet conditions shall be accomplished in small sections to minimize exposure to wet weather. Each section shall be sufficiently small so that the removal of soil and placement of backfill can be accomplished on the same day. No soil shall be left un-compacted and exposed to water. Soil that is too wet for compaction shall be removed and replaced with Gravel Borrow material. Grading and earthwork should not be accomplished during periods of heavy continuous rainfall.

2-03.4 Measurement

(March 13, 1995 WSDOT GSP, OPTION 2)

Section 2-03.4 is supplemented with the following:

Only one determination of the original ground elevation will be made on this project. Measurement for roadway excavation and embankment will be based on the original ground elevations recorded previous to the award of this contract.

If discrepancies are discovered in the ground elevations which will materially affect the quantities of earthwork, the original computations of earthwork quantities will be adjusted accordingly.

Earthwork quantities will be computed, either manually or by means of electronic data processing equipment, by use of the average end area method or by the finite element analysis method utilizing digital terrain modeling techniques.

Electronic Design Files will be available by request for the Bidder's Inspection before the opening of the bids.

(April 12, 2018 CFW GSP)

Section 2-03.4 is supplemented with the following:

If the Contractor excavates outside the neat-line limits designated for "Roadway Excavation, Incl. Haul" or performs extra excavation, it shall be considered for the Contractor's benefit and shall be included in the cost of other Bid Items.

2-03.5 Payment

(March 13, 1995 WSDOT GSP, OPTION 2)

Section 2-03.5 is supplemented with the following:

All costs in connection with the preparation of waste sites and waste deposits shall be included in the Mobilization.

2-09 STRUCTURE EXCAVATION

2-09.3 Construction Requirements

2-09.3(1) General Requirements

(March 22, 2023 CFW GSP)

Section 2-09.3(1) is supplemented with the following:

All shoring, including sheeting and bracing, or equivalent trench stabilization and worker protection system required to perform and protect the excavation, and to safeguard the personnel who may enter the excavation, shall be furnished by the Contractor. If workers enter any trench or other excavation four feet (4') or more in depth that does not meet the open pit requirements as generally set forth in Section 2-09.3(3)B, it shall be shored.

The Contractor alone shall be responsible for worker safety, and the Contracting Agency assumes no responsibility therefore.

Upon completing the Work, the Contractor shall remove all shoring, unless otherwise shown in the Plans or directed by the Engineer.

The Contractor is advised that the Contracting Agency has not so delegated, and the Engineer does not purport to be, a trench excavation system safety expert, is not so engaged in that capacity under this Contract, and has neither the authority nor the responsibility to enforce construction safety laws, rules, regulations, or procedures, or to order the suspension of work for claimed violations of trench excavation safety.

The furnishing by the Contracting Agency of resident project representation and inspection shall not make the Contracting Agency responsible for the enforcement of such laws, rules, regulations, or procedures, nor shall such make the Contracting Agency responsible for construction means, methods, techniques, sequences, procedures, or for the Contractor's failure to properly perform the Work necessary for proper trench excavation.

2-09.3(1)D Disposal of Excavated Material

(March 17, 2020 CFW GSP)

Replace the third paragraph with the following:

If the Contract includes Structure Excavation, Class A or B, including haul; Shoring or Extra Excavation, Class A or B; or Trench Safety System, the unit contract price shall include all costs for loading and hauling excavated materials to a permitted disposal site, or to and from a temporary stockpile. Any such stockpiled materials, either suitable or designated for incorporation into the project, shall be handled in accordance with Section 2-09.3(1)E.

2-09.3(1)E Backfilling

(April 12, 2018 CFW GSP)

The first paragraph of Section 2-09.3(1) is replaced with the following:

The backfilling of openings dug for Structures or for Removal of Structures and Obstructions shall be a necessary part of and incidental to the excavation. Backfill material shall be Gravel Borrow unless the use of native or other material is approved by the engineer.

2-09.3(3) Construction Requirements, Structure Excavation, Class A

2-09.3(3)F Trench Safety Systems

(March 17, 2020 CFW GSP)

Add the following new subsection:

The Contractor shall provide all materials, labor, and equipment necessary to shore trenches to protect the Work, and existing improvements and natural features not designated for removal, and to provide safe working conditions in the trench. The Contractor may elect to use any combination of shoring and overbreak, tunneling, boring, sliding trench shield, or other method of accomplishing the Work consistent with applicable local, State, or Federal safety codes.

If workers enter any trench four (4) feet or more in depth that does not meet the open pit requirements of Section 2-09.3(3)B, the excavation shall be shored as provided in Section

2-09.3(4). The Contractor alone shall be responsible for worker safety, and the Contracting Agency assumes no responsibility.

Upon completing the Work, the Contractor shall remove all shoring unless the Plans or the Engineer direct otherwise.

Shoring to be removed, or moveable trench shields or boxes, shall be located at least two and one-half (2-1/2) pipe diameters away from metal or thermoplastic pipe if the bottom of the shoring, shield, or box extends below the top of the pipe, unless a satisfactory means of reconsolidating the bedding or side support material disturbed by shoring removal can be demonstrated.

Damages resulting from improper shoring or failure to shore shall be the sole responsibility of the Contractor.

The furnishing by the Contracting Agency of resident project representation and inspection shall not make the Contracting Agency responsible for the enforcement of such laws, rules, regulations, or procedures, nor shall such make the Contracting Agency responsible for construction means, methods, techniques, sequences, procedures, or for the Contractor's failure to properly perform the Work necessary for proper trench excavation safety.

2-09.4 Measurement

(March 17, 2020 CFW GSP)

Section 2-09.4 is supplemented with the following:

Shoring or Extra Excavation Class B will be measured for payment only when the excavation is four-feet (4') or deeper.

No unit of measurement shall apply to the lump sum price for "Trench Safety System".

For vaults and handholes the limits shall be as follows:

Horizontal: 18 inches outside the perimeter of the vault or handhole.

Lower: 6 inches below the bottom of the vault

Upper: The top surface of the ground when the structure excavation begins.

2-09.5 Payment

(March 17, 2020 CFW GSP)

Replace the fourteenth paragraph with the following:

The unit contract price per square foot for "Shoring or Extra Excavation Class B" shall be full pay for furnishing, placing, moving, and removing temporary shoring, or equivalent trench stabilization and worker protection system, and for all excavation, backfill, compact, and other work required when extra excavation is used in lieu of such temporary shoring or equivalent trench safety system. If select backfill material is required for backfilling within the limits of the excavation, it shall also be required as backfill material for the extra excavation at the Contractor's expense.

(March 17, 2020 CFW GSP)

Replace the fifteenth paragraph with the following:

"Trench Safety System", lump sum.

If there is no bid item for Shoring or Extra Excavation, Class B on a square foot basis and the nature of the excavation is such that shoring is required then the lump sum contract price for "Trench Safety System" shall be full payment for:

- 1) All temporary shoring or equivalent trench stabilization including all design and engineering fees.
- 2) Furnishing, constructing, and removing all temporary shoring or equivalent trench safety systems.

END OF DIVISION 2

**DIVISION 3
AGGREGATE PRODUCTION AND ACCEPTANCE**

3-01 PRODUCTION FROM QUARRY AND PIT SITES

3-01.4 Contractor Furnished Material Sources

3-01.4(1) Acquisition and Development

(April 12, 2018 CFW GSP)

Section 3-01.4(1) is supplemented with the following:

No source has been provided for any materials necessary for the construction of these improvements.

If the source of material provided by the Contractor necessitates hauling over roads other than City streets, the Contractor shall, at his own cost and expense, make all arrangements for the use of haul routes.

END OF DIVISION 3

DIVISION 4 BASES

4-04 BALLAST AND CRUSHED SURFACING

4-04.3 Construction Requirements

4-04.3(3) Mixing

(April 12, 2018 CFW GSP)

Item 2 of Section 4-04.3(3), is replaced with the following:

2. **Road Mix Method** - The road mix method of mixing surfacing material will not be allowed.

4-04.3(4) Placing and Spreading

(April 12, 2018 CFW GSP)

Item 2 of Section 4-04(4), is replaced with the following:

2. **Road Mix Method** - The road mix method of mixing surfacing material will not be allowed.

4-04.5 Payment

(January 19, 2024 CFW GSP)

Section 4-04.5 is supplemented with the following:

The unit contract price for Crushed Surfacing and Shoulder Finishing shall also include hauling, compacting, spreading, and removing to waste when required by the Engineer.

END OF DIVISION 4

DIVISION 5 SURFACE TREATMENTS AND PAVEMENTS

5-04 Hot Mix Asphalt

(January 31, 2023 APWA GSP)

Delete Section 5-04 and amendments, Hot Mix Asphalt and replace it with the following:

5-04.1 Description

This Work shall consist of providing and placing one or more layers of plant-mixed hot mix asphalt (HMA) on a prepared foundation or base in accordance with these Specifications and the lines, grades, thicknesses, and typical cross-sections shown in the Plans. The manufacture of HMA may include warm mix asphalt (WMA) processes in accordance with these Specifications. WMA processes include organic additives, chemical additives, and foaming.

HMA shall be composed of asphalt binder and mineral materials as may be required, mixed in the proportions specified to provide a homogeneous, stable, and workable mixture.

5-04.2 Materials

Materials shall meet the requirements of the following sections:

Asphalt Binder	9-02.1(4)
Cationic Emulsified Asphalt	9-02.1(6)
Anti-Stripping Additive	9-02.4
HMA Additive	9-02.5
Aggregates	9-03.8
Recycled Asphalt Pavement (RAP)	9-03.8(3)B, 9-03.21
Reclaimed Asphalt Shingles (RAS)	9-03.8(3)B, 9-03.21
Mineral Filler	9-03.8(5)
Recycled Material	9-03.21

The Contract documents may establish that the various mineral materials required for the manufacture of HMA will be furnished in whole or in part by the Contracting Agency. If the documents do not establish the furnishing of any of these mineral materials by the Contracting Agency, the Contractor shall be required to furnish such materials in the amounts required for the designated mix. Mineral materials include coarse and fine aggregates, and mineral filler.

The Contractor may choose to utilize recycled asphalt pavement (RAP) in the production of HMA. The RAP may be from pavements removed under the Contract, if any, or pavement material from an existing stockpile.

The Contractor may use up to 20 percent RAP by total weight of HMA with no additional sampling or testing of the RAP.

If the Contractor wishes to utilize High RAP/Any RAS, the design must be listed on the WSDOT Qualified Products List (QPL).

The grade of asphalt binder shall be as required by the Contract. Blending of asphalt binder from different sources is not permitted.

The Contractor may only use warm mix asphalt (WMA) processes in the production of HMA with 20 percent or less RAP by total weight of HMA. The Contractor shall submit to the Engineer for approval the process that is proposed and how it will be used in the manufacture of HMA.

Production of aggregates shall comply with the requirements of Section 3-01. Preparation of stockpile site, the stockpiling of aggregates, and the removal of aggregates from stockpiles shall comply with the requirements of Section 3-02.

5-04.2(1) How to Get an HMA Mix Design on the QPL

If the contractor wishes to submit a mix design for inclusion in the Qualified Products List (QPL), please follow the WSDOT process outlined in Standard Specification 5-04.2(1).

5-04.2(1)A Vacant

5-04.2(2) Mix Design – Obtaining Project Approval

No paving shall begin prior to the approval of the mix design by the Engineer.

Nonstatistical evaluation will be used for all HMA not designated as Commercial HMA in the contract documents.

Commercial evaluation will be used for Commercial HMA and for other classes of HMA in the following applications: sidewalks, road approaches, ditches, slopes, paths, trails, gores, prelevel, temporary pavement, and pavement repair. Other nonstructural applications of HMA accepted by commercial evaluation shall be as approved by the Project Engineer. Sampling and testing of HMA accepted by commercial evaluation will be at the option of the Project Engineer. The Proposal quantity of HMA that is accepted by commercial evaluation will be excluded from the quantities used in the determination of nonstatistical evaluation.

Nonstatistical Mix Design. Fifteen days prior to the first day of paving the contractor shall provide one of the following mix design verification certifications for Contracting Agency review;

- The WSDOT Mix Design Evaluation Report from the current WSDOT QPL, or one of the mix design verification certifications listed below.
- The proposed HMA mix design on WSDOT Form 350-042 with the seal and certification (stamp & signature) of a valid licensed Washington State Professional Engineer.
- The Mix Design Report for the proposed HMA mix design developed by a qualified City or County laboratory that is within one year of the approval date.

The mix design shall be performed by a lab accredited by a national authority such as Laboratory Accreditation Bureau, L-A-B for Construction Materials Testing, The Construction Materials Engineering Council (CMEC's) ISO 17025 or AASHTO Accreditation Program (AAP) and shall supply evidence of participation in the AASHTO: resource proficiency sample program.

Mix designs for HMA accepted by Nonstatistical evaluation shall;

- Have the aggregate structure and asphalt binder content determined in accordance with WSDOT Standard Operating Procedure 732 and meet the requirements of Sections 9-03.8(2), except that Hamburg testing for ruts and stripping are at the discretion of the Engineer, and 9-03.8(6).
- Have anti-strip requirements, if any, for the proposed mix design determined in accordance with AASHTO T 283 or T 324, or based on historic anti-strip and aggregate source compatibility from previous WSDOT lab testing.

At the discretion of the Engineer, agencies may accept verified mix designs older than 12 months from the original verification date with a certification from the Contractor that the materials and sources are the same as those shown on the original mix design.

Commercial Evaluation Mix Design. Approval of a mix design for “Commercial Evaluation” will be based on a review of the Contractor’s submittal of WSDOT Form 350-042 (For commercial mixes, AASHTO T 324 evaluation is not required) or a Mix Design from the current WSDOT QPL or from one of the processes allowed by this section. Testing of the HMA by the Contracting Agency for mix design approval is not required.

For the Bid Item Commercial HMA, the Contractor shall select a class of HMA and design level of ESALs appropriate for the required use.

5-04.2(2)B Using Warm Mix Asphalt Processes

The Contractor may elect to use additives that reduce the optimum mixing temperature or serve as a compaction aid for producing HMA. Additives include organic additives, chemical additives and foaming processes. The use of Additives is subject to the following:

- Do not use additives that reduce the mixing temperature more than allowed in Section 5-04.3(6) in the production of mixtures.
- Before using additives, obtain the Engineer’s approval using WSDOT Form 350-076 to describe the proposed additive and process.

5-04.3 Construction Requirements

5-04.3(1) Weather Limitations

Do not place HMA for wearing course on any Traveled Way beginning October 1st through March 31st of the following year without written concurrence from the Engineer.

Do not place HMA on any wet surface, or when the average surface temperatures are less than those specified below, or when weather conditions otherwise prevent the proper handling or finishing of the HMA.

Minimum Surface Temperature for Paving

Compacted Thickness (Feet)	Wearing Course	Other Courses
Less than 0.10	55°F	45°F
0.10 to .20	45°F	35°F
More than 0.20	35°F	35°F

5-04.3(2) Paving Under Traffic

When the Roadway being paved is open to traffic, the requirements of this Section shall apply.

The Contractor shall keep intersections open to traffic at all times except when paving the intersection or paving across the intersection. During such time, and provided that there has been an advance warning to the public, the intersection may be closed for the minimum time required to place and compact the mixture. In hot weather, the Engineer may require the application of water to the pavement to accelerate the finish rolling of the pavement and to shorten the time required before reopening to traffic.

Before closing an intersection, advance warning signs shall be placed and signs shall also be placed marking the detour or alternate route.

During paving operations, temporary pavement markings shall be maintained throughout the project. Temporary pavement markings shall be installed on the Roadway prior to opening to traffic. Temporary pavement markings shall be in accordance with Section 8-23.

All costs in connection with performing the Work in accordance with these requirements, except the cost of temporary pavement markings, shall be included in the unit Contract prices for the various Bid items involved in the Contract.

5-04.3(3) Equipment

5-04.3(3)A Mixing Plant

Plants used for the preparation of HMA shall conform to the following requirements:

- 1. Equipment for Preparation of Asphalt Binder** – Tanks for the storage of asphalt binder shall be equipped to heat and hold the material at the required temperatures. The heating shall be accomplished by steam coils, electricity, or other approved means so that no flame shall be in contact with the storage tank. The circulating system for the asphalt binder shall be designed to ensure proper and continuous circulation during the operating period. A valve for the purpose of sampling the asphalt binder shall be placed in either the storage tank or in the supply line to the mixer.
- 2. Thermometric Equipment** – An armored thermometer, capable of detecting temperature ranges expected in the HMA mix, shall be fixed in the asphalt binder feed line at a location near the charging valve at the mixer unit. The thermometer location shall be convenient and safe for access by Inspectors. The plant shall also be equipped with an approved dial-scale thermometer, a mercury actuated thermometer, an electric pyrometer, or another approved thermometric instrument placed at the discharge chute of the drier to automatically register or indicate the temperature of the heated aggregates. This device shall be in full view of the plant operator.
- 3. Heating of Asphalt Binder** – The temperature of the asphalt binder shall not exceed the maximum recommended by the asphalt binder manufacturer nor shall it be below the minimum temperature required to maintain the asphalt binder in a homogeneous state. The asphalt binder shall be heated in a manner that will avoid local variations in heating. The heating method shall provide a continuous supply of asphalt binder to

the mixer at a uniform average temperature with no individual variations exceeding 25°F. Also, when a WMA additive is included in the asphalt binder, the temperature of the asphalt binder shall not exceed the maximum recommended by the manufacturer of the WMA additive.

4. **Sampling and Testing of Mineral Materials** – The HMA plant shall be equipped with a mechanical sampler for the sampling of the mineral materials. The mechanical sampler shall meet the requirements of Section 1-05.6 for the crushing and screening operation. The Contractor shall provide for the setup and operation of the field testing facilities of the Contracting Agency as provided for in Section 3-01.2(2).
5. **Sampling HMA** – The HMA plant shall provide for sampling HMA by one of the following methods:
 - a. A mechanical sampling device attached to the HMA plant.
 - b. Platforms or devices to enable sampling from the hauling vehicle without entering the hauling vehicle.

5-04.3(3)B Hauling Equipment

Trucks used for hauling HMA shall have tight, clean, smooth metal beds and shall have a cover of canvas or other suitable material of sufficient size to protect the mixture from adverse weather. Whenever the weather conditions during the work shift include, or are forecast to include, precipitation or an air temperature less than 45°F or when time from loading to unloading exceeds 30 minutes, the cover shall be securely attached to protect the HMA.

The contractor shall provide an environmentally benign means to prevent the HMA mixture from adhering to the hauling equipment. Excess release agent shall be drained prior to filling hauling equipment with HMA. Petroleum derivatives or other coating material that contaminate or alter the characteristics of the HMA shall not be used. For live bed trucks, the conveyer shall be in operation during the process of applying the release agent.

5-04.3(3)C Pavers

HMA pavers shall be self-contained, power-propelled units, provided with an internally heated vibratory screed and shall be capable of spreading and finishing courses of HMA plant mix material in lane widths required by the paving section shown in the Plans.

The HMA paver shall be in good condition and shall have the most current equipment available from the manufacturer for the prevention of segregation of the HMA mixture installed, in good condition, and in working order. The equipment certification shall list the make, model, and year of the paver and any equipment that has been retrofitted.

The screed shall be operated in accordance with the manufacturer's recommendations and shall effectively produce a finished surface of the required evenness and texture without tearing, shoving, segregating, or gouging the mixture. A copy of the manufacturer's recommendations shall be provided upon request by the Contracting Agency. Extensions will be allowed provided they produce the same results, including ride, density, and surface texture as obtained by the primary screed. Extensions without augers and an internally heated vibratory screed shall not be used in the Traveled Way.

When specified in the Contract, reference lines for vertical control will be required. Lines shall be placed on both outer edges of the Traveled Way of each Roadway. Horizontal control utilizing the reference line will be permitted. The grade and slope for intermediate lanes shall be controlled automatically from reference lines or by means of a mat referencing device and a slope control device. When the finish of the grade prepared for paving is superior to the established tolerances and when, in the opinion of the Engineer, further improvement to the line, grade, cross-section, and smoothness can best be achieved without the use of the reference line, a mat referencing device may be substituted for the reference line. Substitution of the device will be subject to the continued approval of the Engineer. A joint matcher may be used subject to the approval of the Engineer. The reference line may be removed after the completion of the first course of HMA when approved by the Engineer. Whenever the Engineer determines that any of these methods are failing to provide the necessary vertical control, the reference lines will be reinstalled by the Contractor.

The Contractor shall furnish and install all pins, brackets, tensioning devices, wire, and accessories necessary for satisfactory operation of the automatic control equipment.

If the paving machine in use is not providing the required finish, the Engineer may suspend Work as allowed by Section 1-08.6. Any cleaning or solvent type liquids spilled on the pavement shall be thoroughly removed before paving proceeds.

5-04.3(3)D Material Transfer Device or Material Transfer Vehicle

A Material Transfer Device/Vehicle (MTD/V) shall only be used with the Engineer's approval, unless otherwise required by the Contract.

Where an MTD/V is required by the Contract, the Engineer may approve paving without an MTD/V, at the request of the Contractor. The Engineer will determine if an equitable adjustment in cost or time is due.

When used, the MTD/V shall mix the HMA after delivery by the hauling equipment and prior to laydown by the paving machine. Mixing of the HMA shall be sufficient to obtain a uniform temperature throughout the mixture. If a windrow elevator is used, the length of the windrow may be limited in urban areas or through intersections, at the discretion of the Engineer.

To be approved for use, an MTV:

1. Shall be self-propelled vehicle, separate from the hauling vehicle or paver.
2. Shall not be connected to the hauling vehicle or paver.
3. May accept HMA directly from the haul vehicle or pick up HMA from a windrow.
4. Shall mix the HMA after delivery by the hauling equipment and prior to placement into the paving machine.
5. Shall mix the HMA sufficiently to obtain a uniform temperature throughout the mixture.

To be approved for use, an MTD:

1. Shall be positively connected to the paver.
2. May accept HMA directly from the haul vehicle or pick up HMA from a windrow.

3. Shall mix the HMA after delivery by the hauling equipment and prior to placement into the paving machine.
4. Shall mix the HMA sufficiently to obtain a uniform temperature throughout the mixture.

5-04.3(3)E Rollers

Rollers shall be of the steel wheel, vibratory, oscillatory, or pneumatic tire type, in good condition and capable of reversing without backlash. Operation of the roller shall be in accordance with the manufacturer's recommendations. When ordered by the Engineer for any roller planned for use on the project, the Contractor shall provide a copy of the manufacturer's recommendation for the use of that roller for compaction of HMA. The number and weight of rollers shall be sufficient to compact the mixture in compliance with the requirements of Section 5-04.3(10). The use of equipment that results in crushing of the aggregate will not be permitted. Rollers producing pickup, washboard, uneven compaction of the surface, displacement of the mixture or other undesirable results shall not be used.

5-04.3(4) Preparation of Existing Paved Surfaces

When the surface of the existing pavement or old base is irregular, the Contractor shall bring it to a uniform grade and cross-section as shown on the Plans or approved by the Engineer.

Preleveling of uneven or broken surfaces over which HMA is to be placed may be accomplished by using an asphalt paver, a motor patrol grader, or by hand raking, as approved by the Engineer.

Compaction of preleveling HMA shall be to the satisfaction of the Engineer and may require the use of small steel wheel rollers, plate compactors, or pneumatic rollers to avoid bridging across preleveled areas by the compaction equipment. Equipment used for the compaction of preleveling HMA shall be approved by the Engineer.

Before construction of HMA on an existing paved surface, the entire surface of the pavement shall be clean. All fatty asphalt patches, grease drippings, and other objectionable matter shall be entirely removed from the existing pavement. All pavements or bituminous surfaces shall be thoroughly cleaned of dust, soil, pavement grindings, and other foreign matter. All holes and small depressions shall be filled with an appropriate class of HMA. The surface of the patched area shall be leveled and compacted thoroughly. Prior to the application of tack coat, or paving, the condition of the surface shall be approved by the Engineer.

A tack coat of asphalt shall be applied to all paved surfaces on which any course of HMA is to be placed or abutted; except that tack coat may be omitted from clean, newly paved surfaces at the discretion of the Engineer. Tack coat shall be uniformly applied to cover the existing pavement with a thin film of residual asphalt free of streaks and bare spots at a rate between 0.02 and 0.10 gallons per square yard of retained asphalt. The rate of application shall be approved by the Engineer. A heavy application of tack coat shall be applied to all joints. For Roadways open to traffic, the application of tack coat shall be limited to surfaces that will be paved during the same working shift. The spreading equipment shall be equipped with a thermometer to indicate the temperature of the tack coat material.

Equipment shall not operate on tacked surfaces until the tack has broken and cured. If the Contractor's operation damages the tack coat it shall be repaired prior to placement of the HMA.

The tack coat shall be CSS-1, or CSS-1h emulsified asphalt. The CSS-1 and CSS-1h emulsified asphalt may be diluted once with water at a rate not to exceed one-part water to one-part emulsified asphalt. The tack coat shall have sufficient temperature such that it may be applied uniformly at the specified rate of application and shall not exceed the maximum temperature recommended by the emulsified asphalt manufacturer.

5-04.3(4)A Crack Sealing

5-04.3(4)A1 General

When the Proposal includes a pay item for crack sealing, seal cracks in accordance with Section 5-03.

5-04.3(4)B Vacant

5-04.3(4)C Pavement Repair

The Contractor shall excavate pavement repair areas and shall backfill these with HMA in accordance with the details shown in the Plans and as marked in the field. The Contractor shall conduct the excavation operations in a manner that will protect the pavement that is to remain. Pavement not designated to be removed that is damaged as a result of the Contractor's operations shall be repaired by the Contractor to the satisfaction of the Engineer at no cost to the Contracting Agency. The Contractor shall excavate only within one lane at a time unless approved otherwise by the Engineer. The Contractor shall not excavate more area than can be completely finished during the same shift, unless approved by the Engineer.

Unless otherwise shown in the Plans or determined by the Engineer, excavate to a depth of 1.0 feet. The Engineer will make the final determination of the excavation depth required. The minimum width of any pavement repair area shall be 40 inches unless shown otherwise in the Plans. Before any excavation, the existing pavement shall be sawcut or shall be removed by a pavement grinder. Excavated materials will become the property of the Contractor and shall be disposed of in a Contractor-provided site off the Right of Way or used in accordance with Sections 2-02.3(3) or 9-03.21.

Asphalt for tack coat shall be required as specified in Section 5-04.3(4). A heavy application of tack coat shall be applied to all surfaces of existing pavement in the pavement repair area.

Placement of the HMA backfill shall be accomplished in lifts not to exceed 0.35-foot compacted depth. Lifts that exceed 0.35-foot of compacted depth may be accomplished with the approval of the Engineer. Each lift shall be thoroughly compacted by a mechanical tamper or a roller.

5-04.3(5) Producing/Stockpiling Aggregates and RAP

Aggregates and RAP shall be stockpiled according to the requirements of Section 3-02. Sufficient storage space shall be provided for each size of aggregate and RAP. Materials shall be removed from stockpile(s) in a manner to ensure minimal segregation when being

moved to the HMA plant for processing into the final mixture. Different aggregate sizes shall be kept separated until they have been delivered to the HMA plant.

5-04.3(5)A Vacant

5-04.3(6) Mixing

After the required amount of mineral materials, asphalt binder, recycling agent and anti-stripping additives have been introduced into the mixer the HMA shall be mixed until complete and uniform coating of the particles and thorough distribution of the asphalt binder throughout the mineral materials is ensured.

When discharged, the temperature of the HMA shall not exceed the optimum mixing temperature by more than 25°F as shown on the reference mix design report or as approved by the Engineer. Also, when a WMA additive is included in the manufacture of HMA, the discharge temperature of the HMA shall not exceed the maximum recommended by the manufacturer of the WMA additive. A maximum water content of 2 percent in the mix, at discharge, will be allowed providing the water causes no problems with handling, stripping, or flushing. If the water in the HMA causes any of these problems, the moisture content shall be reduced as directed by the Engineer.

Storing or holding of the HMA in approved storage facilities will be permitted with approval of the Engineer, but in no event shall the HMA be held for more than 24 hours. HMA held for more than 24 hours after mixing shall be rejected. Rejected HMA shall be disposed of by the Contractor at no expense to the Contracting Agency. The storage facility shall have an accessible device located at the top of the cone or about the third point. The device shall indicate the amount of material in storage. No HMA shall be accepted from the storage facility when the HMA in storage is below the top of the cone of the storage facility, except as the storage facility is being emptied at the end of the working shift.

Recycled asphalt pavement (RAP) utilized in the production of HMA shall be sized prior to entering the mixer so that a uniform and thoroughly mixed HMA is produced. If there is evidence of the recycled asphalt pavement not breaking down during the heating and mixing of the HMA, the Contractor shall immediately suspend the use of the RAP until changes have been approved by the Engineer. After the required amount of mineral materials, RAP, new asphalt binder and asphalt rejuvenator have been introduced into the mixer the HMA shall be mixed until complete and uniform coating of the particles and thorough distribution of the asphalt binder throughout the mineral materials, and RAP is ensured.

5-04.3(7) Spreading and Finishing

The mixture shall be laid upon an approved surface, spread, and struck off to the grade and elevation established. HMA pavers complying with Section 5-04.3(3) shall be used to distribute the mixture. Unless otherwise directed by the Engineer, the nominal compacted depth of any layer of any course shall not exceed the following:

HMA Class 1"	0.35 feet
HMA Class ¾" and HMA Class ½"	
wearing course	0.30 feet
other courses	0.35 feet
HMA Class ⅜"	0.15 feet

On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the paving may be done with other equipment or by hand.

When more than one JMF is being utilized to produce HMA, the material produced for each JMF shall be placed by separate spreading and compacting equipment. The intermingling of HMA produced from more than one JMF is prohibited. Each strip of HMA placed during a work shift shall conform to a single JMF established for the class of HMA specified unless there is a need to make an adjustment in the JMF.

5-04.3(8) Aggregate Acceptance Prior to Incorporation in HMA

For HMA accepted by nonstatistical evaluation, the aggregate properties of sand equivalent, uncompacted void content, and fracture will be evaluated in accordance with Section 3-04. Sampling and testing of aggregates for HMA accepted by commercial evaluation will be at the option of the Engineer.

5-04.3(9) HMA Mixture Acceptance

Acceptance of HMA shall be as provided under nonstatistical, or commercial evaluation.

Nonstatistical evaluation will be used for the acceptance of HMA unless Commercial Evaluation is specified.

Commercial evaluation will be used for Commercial HMA and for other classes of HMA in the following applications: sidewalks, road approaches, ditches, slopes, paths, trails, gores, prelevel, temporary pavement, and pavement repair. Other nonstructural applications of HMA accepted by commercial evaluation shall be as approved by the Engineer. Sampling and testing of HMA accepted by commercial evaluation will be at the option of the Engineer.

The mix design will be the initial JMF for the class of HMA. The Contractor may request a change in the JMF. Any adjustments to the JMF will require the approval of the Engineer and may be made in accordance with this section.

HMA Tolerances and Adjustments

- 1. **Job Mix Formula Tolerances** – The constituents of the mixture at the time of acceptance shall be within tolerance. The tolerance limits will be established as follows:

For Asphalt Binder and Air Voids (Va), the acceptance limits are determined by adding the tolerances below to the approved JMF values. These values will also be the Upper Specification Limit (USL) and Lower Specification Limit (LSL) required in Section 1-06.2(2)D2

Property	Non-Statistical Evaluation	Commercial Evaluation
Asphalt Binder	+/- 0.5%	+/- 0.7%
Air Voids, Va	2.5% min. and 5.5% max	N/A

For Aggregates in the mixture:

- a. First, determine preliminary upper and lower acceptance limits by applying the following tolerances to the approved JMF.

Aggregate Percent Passing	Non-Statistical Evaluation	Commercial Evaluation
1", ¾", ½", and 3/8" sieves	+/- 6%	+/- 8%
No. 4 sieve	+/-6%	+/- 8%
No. 8 Sieve	+/- 6%	+/-8%
No. 200 sieve	+/- 2.0%	+/- 3.0%

- b. Second, adjust the preliminary upper and lower acceptance limits determined from step (a) the minimum amount necessary so that none of the aggregate properties are outside the control points in Section 9-03.8(6). The resulting values will be the upper and lower acceptance limits for aggregates, as well as the USL and LSL required in Section 1-06.2(2)D2.
2. Job Mix Formula Adjustments – An adjustment to the aggregate gradation or asphalt binder content of the JMF requires approval of the Engineer. Adjustments to the JMF will only be considered if the change produces material of equal or better quality and may require the development of a new mix design if the adjustment exceeds the amounts listed below.
 - a. **Aggregates** – 2 percent for the aggregate passing the 1½", 1", ¾", ½", ⅜", and the No. 4 sieves, 1 percent for aggregate passing the No. 8 sieve, and 0.5 percent for the aggregate passing the No. 200 sieve. The adjusted JMF shall be within the range of the control points in Section 9-03.8(6).
 - b. **Asphalt Binder Content** – The Engineer may order or approve changes to asphalt binder content. The maximum adjustment from the approved mix design for the asphalt binder content shall be 0.3 percent

5-04.3(9)A Vacant

5-04.3(9)B Vacant

5-04.3(9)C Mixture Acceptance – Nonstatistical Evaluation

HMA mixture which is accepted by Nonstatistical Evaluation will be evaluated by the Contracting Agency by dividing the HMA tonnage into lots.

5-04.3(9)C1 Mixture Nonstatistical Evaluation – Lots and Sublots

A lot is represented by randomly selected samples of the same mix design that will be tested for acceptance. A lot is defined as the total quantity of material or work produced for each Job Mix Formula placed. Only one lot per JMF is expected. A subplot shall be equal to one day's production or 800 tons, whichever is less except that the final subplot will be a minimum of 400 tons and may be increased to 1200 tons.

All of the test results obtained from the acceptance samples from a given lot shall be evaluated collectively. If the Contractor requests a change to the JMF that is approved, the material produced after the change will be evaluated on the basis of the new JMF for the remaining sublots in the current lot and for acceptance of subsequent lots. For a lot in progress with a CPF less than 0.75, a new lot will begin at the Contractor's request after the Engineer is satisfied that material conforming to the Specifications can be produced.

Sampling and testing for evaluation shall be performed on the frequency of one sample per subplot.

5-04.3(9)C2 Mixture Nonstatistical Evaluation Sampling

Samples for acceptance testing shall be obtained by the Contractor when ordered by the Engineer. The Contractor shall sample the HMA mixture in the presence of the Engineer and in accordance with AASH-TO T 168. A minimum of three samples should be taken for each class of HMA placed on a project. If used in a structural application, at least one of the three samples shall be tested.

Sampling and testing HMA in a structural application where quantities are less than 400 tons is at the discretion of the Engineer.

For HMA used in a structural application and with a total project quantity less than 800 tons but more than 400 tons, a minimum of one acceptance test shall be performed. In all cases, a minimum of 3 samples will be obtained at the point of acceptance, a minimum of one of the three samples will be tested for conformance to the JMF:

- If the test results are found to be within specification requirements, additional testing will be at the Engineer’s discretion.
- If test results are found not to be within specification requirements, additional testing of the remaining samples to determine a CPF shall be performed.

5-04.3(9)C3 Mixture Nonstatistical Evaluation – Acceptance Testing

Testing of HMA for compliance of V_a will at the option of the Contracting Agency. If tested, compliance of V_a will use WSDOT SOP 731.

Testing for compliance of asphalt binder content will be by WSDOT FOP for AASHTO T 308.

Testing for compliance of gradation will be by FOP for WAQTC T 27/T 11.

5-04.3(9)C4 Mixture Nonstatistical Evaluation – Pay Factors

For each lot of material falling outside the tolerance limits in 5-04.3(9), the Contracting Agency will determine a CPF using the following price adjustment factors:

Table of Price Adjustment Factors	
Constituent	Factor “f”
All aggregate passing: 1½", 1", ¾", ½", ⅜" and No.4 sieves	2
All aggregate passing No. 8 sieve	15
All aggregate passing No. 200 sieve	20
Asphalt binder	40
Air Voids (V_a) (where applicable)	20

Each lot of HMA produced under Nonstatistical Evaluation and having all constituents falling within the tolerance limits of the job mix formula shall be accepted at the unit Contract price with no further evaluation. When one or more constituents fall outside the nonstatistical tolerance limits in the Job Mix Formula shown in Table of Price Adjustment

Factors, the lot shall be evaluated in accordance with Section 1-06.2 to determine the appropriate CPF. The nonstatistical tolerance limits will be used in the calculation of the CPF and the maximum CPF shall be 1.00. When less than three sublots exist, backup samples of the existing sublots or samples from the Roadway shall be tested to provide a minimum of three sets of results for evaluation.

5-04.3(9)C5 Vacant

5-04.3(9)C6 Mixture Nonstatistical Evaluation – Price Adjustments

For each lot of HMA mix produced under Nonstatistical Evaluation when the calculated CPF is less than 1.00, a Nonconforming Mix Factor (NCMF) will be determined. The NCMF equals the algebraic difference of CPF minus 1.00 multiplied by 60 percent. The total job mix compliance price adjustment will be calculated as the product of the NCMF, the quantity of HMA in the lot in tons, and the unit Contract price per ton of mix.

If a constituent is not measured in accordance with these Specifications, its individual pay factor will be considered 1.00 in calculating the CPF.

5-04.3(9)C7 Mixture Nonstatistical Evaluation - Retests

The Contractor may request a subplot be retested. To request a retest, the Contractor shall submit a written request within 7 calendar days after the specific test results have been received. A split of the original acceptance sample will be retested. The split of the sample will not be tested with the same tester that ran the original acceptance test. The sample will be tested for a complete gradation analysis, asphalt binder content, and, at the option of the agency, V_a . The results of the retest will be used for the acceptance of the HMA in place of the original subplot sample test results. The cost of testing will be deducted from any monies due or that may come due the Contractor under the Contract at the rate of \$500 per sample.

5-04.3 (9)D Mixture Acceptance – Commercial Evaluation

If sampled and tested, HMA produced under Commercial Evaluation and having all constituents falling within the tolerance limits of the job mix formula shall be accepted at the unit Contract price with no further evaluation. When one or more constituents fall outside the commercial tolerance limits in the Job Mix Formula shown in 5-04.3(9), the lot shall be evaluated in accordance with Section 1-06.2 to determine the appropriate CPF. The commercial tolerance limits will be used in the calculation of the CPF and the maximum CPF shall be 1.00. When less than three sublots exist, backup samples of the existing sublots or samples from the street shall be tested to provide a minimum of three sets of results for evaluation.

For each lot of HMA mix produced and tested under Commercial Evaluation when the calculated CPF is less than 1.00, a Nonconforming Mix Factor (NCMF) will be determined. The NCMF equals the algebraic difference of CPF minus 1.00 multiplied by 60 percent. The Job Mix Compliance Price Adjustment will be calculated as the product of the NCMF, the quantity of HMA in the lot in tons, and the unit Contract price per ton of mix.

If a constituent is not measured in accordance with these Specifications, its individual pay factor will be considered 1.00 in calculating the CPF.

5-04.3(10) HMA Compaction Acceptance

HMA mixture accepted by nonstatistical evaluation that is used in traffic lanes, including lanes for intersections, ramps, truck climbing, weaving, and speed change, and having a specified compacted course thickness greater than 0.10-foot, shall be compacted to a specified level of relative density. The specified level of relative density shall be a CPF of not less than 0.75 when evaluated in accordance with Section 1-06.2, using a LSL of 92.0 (minimum of 92 percent of the maximum density). The maximum density shall be determined by WSDOT FOP for AASHTO T 729. The specified level of density attained will be determined by the evaluation of the density of the pavement. The density of the pavement shall be determined in accordance with WSDOT FOP for WAQTC TM 8, except that gauge correlation will be at the discretion of the Engineer, when using the nuclear density gauge and WSDOT SOP 736 when using cores to determine density.

Tests for the determination of the pavement density will be taken in accordance with the required procedures for measurement by a nuclear density gauge or Roadway cores after completion of the finish rolling.

If the Contracting Agency uses a nuclear density gauge to determine density the test procedures FOP for WAQTC TM 8 and WSDOT SOP T 729 will be used on the day the mix is placed and prior to opening to traffic.

Roadway cores for density may be obtained by either the Contracting Agency or the Contractor in accordance with WSDOT SOP 734. The core diameter shall be 4-inches minimum, unless otherwise approved by the Engineer. Roadway cores will be tested by the Contracting Agency in accordance with WSDOT FOP for AASHTO T 166.

If the Contract includes the Bid item "Roadway Core", the cores shall be obtained by the Contractor in the presence of the Engineer on the same day the mix is placed and at locations designated by the Engineer. If the Contract does not include the Bid item "Roadway Core", the Contracting Agency will obtain the cores.

For a lot in progress with a CPF less than 0.75, a new lot will begin at the Contractor's request after the Engineer is satisfied that material conforming to the Specifications can be produced.

HMA mixture accepted by commercial evaluation and HMA constructed under conditions other than those listed above shall be compacted on the basis of a test point evaluation of the compaction train. The test point evaluation shall be performed in accordance with instructions from the Engineer. The number of passes with an approved compaction train, required to attain the maximum test point density, shall be used on all subsequent paving.

HMA for preleveling shall be thoroughly compacted. HMA that is used for preleveling wheel rutting shall be compacted with a pneumatic tire roller unless otherwise approved by the Engineer.

Test Results

For a subplot that has been tested with a nuclear density gauge that did not meet the minimum of 92 percent of the reference maximum density in a compaction lot with a CPF below 1.00 and thus subject to a price reduction or rejection, the Contractor may request that a core be used for determination of the relative density of the subplot. The relative density of the core will replace the relative density determined by the nuclear density

gauge for the subplot and will be used for calculation of the CPF and acceptance of HMA compaction lot.

When cores are taken by the Contracting Agency at the request of the Contractor, they shall be requested by noon of the next workday after the test results for the subplot have been provided or made available to the Contractor. Core locations shall be outside of wheel paths and as determined by the Engineer. Traffic control shall be provided by the Contractor as requested by the Engineer. Failure by the Contractor to provide the requested traffic control will result in forfeiture of the request for cores. When the CPF for the lot based on the results of the HMA cores is less than 1.00, the cost for the coring will be deducted from any monies due or that may become due the Contractor under the Contract at the rate of \$200 per core and the Contractor shall pay for the cost of the traffic control.

5-04.3(10)A HMA Compaction – General Compaction Requirements

Compaction shall take place when the mixture is in the proper condition so that no undue displacement, cracking, or shoving occurs. Areas inaccessible to large compaction equipment shall be compacted by other mechanical means. Any HMA that becomes loose, broken, contaminated, shows an excess or deficiency of asphalt, or is in any way defective, shall be removed and replaced with new hot mix that shall be immediately compacted to conform to the surrounding area.

The type of rollers to be used and their relative position in the compaction sequence shall generally be the Contractor's option, provided the specified densities are attained. Unless the Engineer has approved otherwise, rollers shall only be operated in the static mode when the internal temperature of the mix is less than 175°F. Regardless of mix temperature, a roller shall not be operated in a mode that results in checking or cracking of the mat. Rollers shall only be operated in static mode on bridge decks.

5-04.3(10)B HMA Compaction – Cyclic Density

Low cyclic density areas are defined as spots or streaks in the pavement that are less than 90 percent of the theoretical maximum density. At the Engineer's discretion, the Engineer may evaluate the HMA pavement for low cyclic density, and when doing so will follow WSDOT SOP 733. A \$500 Cyclic Density Price Adjustment will be assessed for any 500-foot section with two or more density readings below 90 percent of the theoretical maximum density.

5-04.3(10)C Vacant

5-04.3(10)D HMA Nonstatistical Compaction

5-04.3(10)D1 HMA Nonstatistical Compaction – Lots and Sublots

HMA compaction which is accepted by nonstatistical evaluation will be based on acceptance testing performed by the Contracting Agency dividing the project into compaction lots.

A lot is represented by randomly selected samples of the same mix design that will be tested for acceptance. A lot is defined as the total quantity of material or work produced for each Job Mix Formula placed. Only one lot per JMF is expected. A subplot shall be equal to one day's production or 400 tons, whichever is less except that the final subplot

will be a minimum of 200 tons and may be increased to 800 tons. Testing for compaction will be at the rate of 5 tests per subplot per WSDOT T 738.

The subplot locations within each density lot will be determined by the Engineer. For a lot in progress with a CPF less than 0.75, a new lot will begin at the Contractor's request after the Engineer is satisfied that material conforming to the Specifications can be produced.

HMA mixture accepted by commercial evaluation and HMA constructed under conditions other than those listed above shall be compacted on the basis of a test point evaluation of the compaction train. The test point evaluation shall be performed in accordance with instructions from the Engineer. The number of passes with an approved compaction train, required to attain the maximum test point density, shall be used on all subsequent paving.

HMA for preleveling shall be thoroughly compacted. HMA that is used to prelevel wheel ruts shall be compacted with a pneumatic tire roller unless otherwise approved by the Engineer.

5-04.3(10)D2 HMA Compaction Nonstatistical Evaluation – Acceptance Testing

The location of the HMA compaction acceptance tests will be randomly selected by the Engineer from within each subplot, with one test per subplot.

5-04.3(10)D3 HMA Nonstatistical Compaction – Price Adjustments

For each compaction lot with one or two sublots, having all sublots attain a relative density that is 92 percent of the reference maximum density the HMA shall be accepted at the unit Contract price with no further evaluation. When a subplot does not attain a relative density that is 92 percent of the reference maximum density, the lot shall be evaluated in accordance with Section 1-06.2 to determine the appropriate CPF. The maximum CPF shall be 1.00, however, lots with a calculated CPF in excess of 1.00 will be used to offset lots with CPF values below 1.00 but greater than 0.90. Lots with CPF lower than 0.90 will be evaluated for compliance per 5-04.3(11). Additional testing by either a nuclear moisture-density gauge or cores will be completed as required to provide a minimum of three tests for evaluation.

For compaction below the required 92%, a Non-Conforming Compaction Factor (NCCF) will be determined. The NCCF equals the algebraic difference of CPF minus 1.00 multiplied by 40 percent. The Compaction Price Adjustment will be calculated as the product of CPF, the quantity of HMA in the compaction control lot in tons, and the unit Contract price per ton of mix.

5-04.3(11) Reject Work

5-04.3(11)A Reject Work General

Work that is defective or does not conform to Contract requirements shall be rejected. The Contractor may propose, in writing, alternatives to removal and replacement of rejected material. Acceptability of such alternative proposals will be determined at the sole discretion of the Engineer. HMA that has been rejected is subject to the requirements in Section 1-06.2(2) and this specification, and the Contractor shall submit a corrective action proposal to the Engineer for approval.

5-04.3(11)B Rejection by Contractor

The Contractor may, prior to sampling, elect to remove any defective material and replace it with new material. Any such new material will be sampled, tested, and evaluated for acceptance.

5-04.3(11)C Rejection Without Testing (Mixture or Compaction)

The Engineer may, without sampling, reject any batch, load, or section of Roadway that appears defective. Material rejected before placement shall not be incorporated into the pavement. Any rejected section of Roadway shall be removed.

No payment will be made for the rejected materials or the removal of the materials unless the Contractor requests that the rejected material be tested. If the Contractor elects to have the rejected material tested, a minimum of three representative samples will be obtained and tested. Acceptance of rejected material will be based on conformance with the nonstatistical acceptance Specification. If the CPF for the rejected material is less than 0.75, no payment will be made for the rejected material; in addition, the cost of sampling and testing shall be borne by the Contractor. If the CPF is greater than or equal to 0.75, the cost of sampling and testing will be borne by the Contracting Agency. If the material is rejected before placement and the CPF is greater than or equal to 0.75, compensation for the rejected material will be at a CPF of 0.75. If rejection occurs after placement and the CPF is greater than or equal to 0.75, compensation for the rejected material will be at the calculated CPF with an addition of 25 percent of the unit Contract price added for the cost of removal and disposal.

5-04.3(11)D Rejection - A Partial Sublot

In addition to the random acceptance sampling and testing, the Engineer may also isolate from a normal sublot any material that is suspected of being defective in relative density, gradation or asphalt binder content. Such isolated material will not include an original sample location. A minimum of three random samples of the suspect material will be obtained and tested. The material will then be statistically evaluated as an independent lot in accordance with Section 1-06.2(2).

5-04.3(11)E Rejection - An Entire Sublot

An entire sublot that is suspected of being defective may be rejected. When a sublot is rejected a minimum of two additional random samples from this sublot will be obtained. These additional samples and the original sublot will be evaluated as an independent lot in accordance with Section 1-06.2(2).

5-04.3(11)F Rejection - A Lot in Progress

The Contractor shall shut down operations and shall not resume HMA placement until such time as the Engineer is satisfied that material conforming to the Specifications can be produced:

1. When the CPF of a lot in progress drops below 1.00 and the Contractor is taking no corrective action, or
2. When the Pay Factor (PF) for any constituent of a lot in progress drops below 0.95 and the Contractor is taking no corrective action, or
3. When either the PF for any constituent or the CPF of a lot in progress is less than 0.75.

5-04.3(11)G Rejection - An Entire Lot (Mixture or Compaction)

An entire lot with a CPF of less than 0.75 will be rejected.

5-04.3(12) Joints

5-04.3(12)A HMA Joints

5-04.3(12)A1 Transverse Joints

The Contractor shall conduct operations such that the placing of the top or wearing course is a continuous operation or as close to continuous as possible. Unscheduled transverse joints will be allowed, and the roller may pass over the unprotected end of the freshly laid mixture only when the placement of the course must be discontinued for such a length of time that the mixture will cool below compaction temperature. When the Work is resumed, the previously compacted mixture shall be cut back to produce a slightly beveled edge for the full thickness of the course.

A temporary wedge of HMA constructed on a 20H:1V shall be constructed where a transverse joint as a result of paving or planing is open to traffic. The HMA in the temporary wedge shall be separated from the permanent HMA by strips of heavy wrapping paper or other methods approved by the Engineer. The wrapping paper shall be removed and the joint trimmed to a slightly beveled edge for the full thickness of the course prior to resumption of paving.

The material that is cut away shall be wasted and new mix shall be laid against the cut. Rollers or tamping irons shall be used to seal the joint.

5-04.3(12)A2 Longitudinal Joints

The longitudinal joint in any one course shall be offset from the course immediately below by not more than 6 inches nor less than 2 inches. All longitudinal joints constructed in the wearing course shall be located at a lane line or an edge line of the Traveled Way. A notched wedge joint shall be constructed along all longitudinal joints in the wearing surface of new HMA unless otherwise approved by the Engineer. The notched wedge joint shall have a vertical edge of not less than the maximum aggregate size or more than $\frac{1}{2}$ of the compacted lift thickness and then taper down on a slope not steeper than 4H:1V. The sloped portion of the HMA notched wedge joint shall be uniformly compacted.

5-04.3(12)B Bridge Paving Joint Seals

Bridge Paving Joint Seals shall be in accordance with Section 5-03.

5-04.3(13) Surface Smoothness

The completed surface of all courses shall be of uniform texture, smooth, uniform as to crown and grade, and free from defects of all kinds. The completed surface of the wearing course shall not vary more than $\frac{1}{8}$ inch from the lower edge of a 10-foot straightedge placed on the surface parallel to the centerline. The transverse slope of the completed surface of the wearing course shall vary not more than $\frac{1}{4}$ inch in 10 feet from the rate of transverse slope shown in the Plans.

When deviations in excess of the above tolerances are found that result from a high place in the HMA, the pavement surface shall be corrected by one of the following methods:

1. Removal of material from high places by grinding with an approved grinding machine, or
2. Removal and replacement of the wearing course of HMA, or

3. By other method approved by the Engineer.

Correction of defects shall be carried out until there are no deviations anywhere greater than the allowable tolerances.

Deviations in excess of the above tolerances that result from a low place in the HMA and deviations resulting from a high place where corrective action, in the opinion of the Engineer, will not produce satisfactory results will be accepted with a price adjustment. The Engineer shall deduct from monies due or that may become due to the Contractor the sum of \$500.00 for each and every section of single traffic lane 100 feet in length in which any excessive deviations described above are found.

When utility appurtenances such as manhole covers and valve boxes are located in the traveled way, the utility appurtenances shall be adjusted to the finished grade prior to paving. This requirement may be waived when requested by the Contractor, at the discretion of the Engineer or when the adjustment details provided in the project plan or specifications call for utility appurtenance adjustments after the completion of paving.

Utility appurtenance adjustment discussions will be included in the Pre-Paving and Pre-Planing Briefing (5-04.3(14)B3). Submit a written request to waive this requirement to the Engineer prior to the start of paving.

5-04.3(14) Planing Bituminous Pavement

The planing plan must be approved by the Engineer and a pre-planing meeting must be held prior to the start of any planing. See Section 5-04.3(14)B2 for information on planing submittals.

Where planing an existing pavement is specified in the Contract, the Contractor must remove existing surfacing material and to reshape the surface to remove irregularities. The finished product must be a prepared surface acceptable for receiving an HMA overlay.

Use the cold milling method for planing unless otherwise specified in the Contract. Do not use the planer on the final wearing course of new HMA.

Conduct planing operations in a manner that does not tear, break, burn, or otherwise damage the surface which is to remain. The finished planed surface must be slightly grooved or roughened and must be free from gouges, deep grooves, ridges, or other imperfections. The Contractor must repair any damage to the surface by the Contractor's planing equipment, using an Engineer approved method.

Repair or replace any metal castings and other surface improvements damaged by planing, as determined by the Engineer.

A tapered wedge cut must be planed longitudinally along curb lines sufficient to provide a minimum of 4 inches of curb reveal after placement and compaction of the final wearing course. The dimensions of the wedge must be as shown on the Drawings or as specified by the Engineer.

A tapered wedge cut must also be made at transitions to adjoining pavement surfaces (meet lines) where butt joints are shown on the Drawings. Cut butt joints in a straight line

with vertical faces 2 inches or more in height, producing a smooth transition to the existing adjoining pavement.

After planing is complete, planed surfaces must be swept, cleaned, and if required by the Contract, patched and preleveled.

The Engineer may direct additional depth planing. Before performing this additional depth planing, the Contractor must conduct a hidden metal in pavement detection survey as specified in Section 5-04.3(14)A.

(June 13, 2023 CFW GSP)

Section 5-04.3(14) is supplemented with the following:

Existing paving fabric encountered during planing shall be removed incidental to planing bituminous pavement. Additional street sweeping and disposal associated with paving fabric removal shall be incidental to planing bituminous pavement.

5-04.3(14)A Pre-Planing Metal Detection Check

Before starting planing of pavements, and before any additional depth planing required by the Engineer, the Contractor must conduct a physical survey of existing pavement to be planed with equipment that can identify hidden metal objects.

Should such metal be identified, promptly notify the Engineer.

See Section 1-07.16(1) regarding the protection of survey monumentation that may be hidden in pavement.

The Contractor is solely responsible for any damage to equipment resulting from the Contractor's failure to conduct a pre-planing metal detection survey, or from the Contractor's failure to notify the Engineer of any hidden metal that is detected.

5-04.3(14)B Paving and Planing Under Traffic

5-04.3(14)B1 General

In addition, the requirements of Section 1-07.23 and the traffic controls required in Section 1-10, and unless the Contract specifies otherwise or the Engineer approves, the Contractor must comply with the following:

1. Intersections:
 - a. Keep intersections open to traffic at all times, except when paving or planing operations through an intersection requires closure. Such closure must be kept to the minimum time required to place and compact the HMA mixture, or plane as appropriate. For paving, schedule such closure to individual lanes or portions thereof that allows the traffic volumes and schedule of traffic volumes required in the approved traffic control plan. Schedule work so that adjacent intersections are not impacted at the same time and comply with the traffic control restrictions required by the Traffic Engineer. Each individual intersection closure or partial closure must be addressed in the traffic control plan, which must be submitted to and accepted by the Engineer, see Section 1-10.2(2).

- b. When planing or paving and related construction must occur in an intersection, consider scheduling and sequencing such work into quarters of the intersection, or half or more of an intersection with side street detours. Be prepared to sequence the work to individual lanes or portions thereof.
 - c. Should closure of the intersection in its entirety be necessary, and no trolley service is impacted, keep such closure to the minimum time required to place and compact the HMA mixture, plane, remove asphalt, tack coat, and as needed.
 - d. Any work in an intersection requires advance warning in both signage and a number of Working Days advance notice as determined by the Engineer, to alert traffic and emergency services of the intersection closure or partial closure.
 - e. Allow new compacted HMA asphalt to cool to ambient temperature before any traffic is allowed on it. Traffic is not allowed on newly placed asphalt until approval has been obtained from the Engineer.
2. Temporary centerline marking, post-paving temporary marking, temporary stop bars, and maintaining temporary pavement marking must comply with Section 8-23.
 3. Permanent pavement marking must comply with Section 8-22.

5-04.3(14)B2 Submittals – Planing Plan and HMA Paving Plan

The Contractor must submit a separate planing plan and a separate paving plan to the Engineer at least 5 Working Days in advance of each operation's activity start date. These plans must show how the moving operation and traffic control are coordinated, as they will be discussed at the pre-planing briefing and pre-paving briefing. When requested by the Engineer, the Contractor must provide each operation's traffic control plan on 24 x 36 inch or larger size Shop Drawings with a scale showing both the area of operation and sufficient detail of traffic beyond the area of operation where detour traffic may be required. The scale on the Shop Drawings is 1 inch = 20 feet, which may be changed if the Engineer agrees sufficient detail is shown.

The planing operation and the paving operation include, but are not limited to, metal detection, removal of asphalt and temporary asphalt of any kind, tack coat and drying, staging of supply trucks, paving trains, rolling, scheduling, and as may be discussed at the briefing.

When intersections will be partially or totally blocked, provide adequately sized and noticeable signage alerting traffic of closures to come, a minimum 2 Working Days in advance. The traffic control plan must show where police officers will be stationed when signalization is or may be, countermanded, and show areas where flaggers are proposed.

At a minimum, the planing and the paving plan must include:

1. A copy of the accepted traffic control plan, see Section 1-10.2(2), detailing each day's traffic control as it relates to the specific requirements of that day's planing and paving. Briefly describe the sequencing of traffic control consistent with the proposed planing and paving sequence, and scheduling of placement of temporary pavement markings and channelizing devices after each day's planing, and paving.

2. A copy of each intersection's traffic control plan.
3. Haul routes from supplier facilities, and locations of temporary parking and staging areas, including return routes. Describe the complete round trip as it relates to the sequencing of paving operations.
4. Names and locations of HMA supplier facilities to be used.
5. List of all equipment to be used for paving.
6. List of personnel and associated job classification assigned to each piece of paving equipment.
7. Description (geometric or narrative) of the scheduled sequence of planing and of paving and intended area of planing and of paving for each day's work, must include the directions of proposed planing and of proposed paving, sequence of adjacent lane paving, sequence of skipped lane paving, intersection planing and paving scheduling and sequencing, and proposed notifications and coordinations to be timely made. The plan must show HMA joints relative to the final pavement marking lane lines.
8. Names, job titles, and contact information for field, office, and plant supervisory personnel.
9. A copy of the approved Mix Designs.
10. Tonnage of HMA to be placed each day.
11. Approximate times and days for starting and ending daily operations.

5-04.3(14)B3 Pre-Paving and Pre-Planing Briefing

At least 2 Working Days before the first paving operation and the first planing operation, or as scheduled by the Engineer for future paving and planing operations to ensure the Contractor has adequately prepared for notifying and coordinating as required in the Contract, the Contractor must be prepared to discuss that day's operations as they relate to other entities and to public safety and convenience, including driveway and business access, garbage truck operations, transit operations and working around energized overhead wires, school and nursing home and hospital and other accesses, other Contractors who may be operating in the area, pedestrian and bicycle traffic, and emergency services. The Contractor, and Subcontractors that may be part of that day's operations, must meet with the Engineer and discuss the proposed operation as it relates to the submitted planing plan and paving plan, approved traffic control plan, and public convenience and safety. Such discussion includes, but is not limited to:

1. General for both the Paving and Planing:
 - a. The actual times of starting and ending daily operations.
 - b. In intersections, how to break up the intersection, and address traffic control and signalization for that operation, including use of peace officers.

- c. The sequencing and scheduling of paving operations and of planing operations, as applicable, as it relates to traffic control, public convenience and safety, and other Contractors who may operate in the Project limits.
 - d. Notifications required of Contractor activities and coordinating with other entities and the public as necessary.
 - e. Description of the sequencing of installation and types of temporary pavement markings as it relates to planning and paving.
 - f. Description of the sequencing of installation of, and the removal of, temporary pavement patch material around exposed castings and as may be needed.
 - g. Description of procedures and equipment to identify hidden metal in the pavement, such as survey monumentation, monitoring wells, streetcar rail, and castings, before planing as per Section 5-04.3(14)B2.
 - h. Description of how flaggers will be coordinated with the planing, paving, and related operations.
 - i. Description of sequencing of traffic controls for the process of rigid pavement base repairs.
 - j. Other items the Engineer deems necessary to address.
2. Paving – additional topics:
- a. When to start applying tack and coordinating with paving.
 - b. Types of equipment and numbers of each type of equipment to be used. If more pieces of equipment than personnel are proposed, describe the sequencing of the personnel operating the types of equipment. Discuss the continuance of operator personnel for each type of equipment as it relates to meeting Specification requirements.
 - c. Number of JMFs to be placed, and if more than one JMF is used, how the Contractor will ensure different JMFs are distinguished, how pavers and how MTVs are distinguished, and how pavers and MTVs are cleaned so that one JMF does not adversely influence the other JMF.
 - d. Description of contingency plans for that day's operations such as equipment breakdown, rain out, and supplier shutdown of operations.
 - e. Number of sublots to be placed, sequencing of density testing, and other sampling and testing.

5-04.3(15) Sealing Pavement Surfaces

Apply a fog seal where shown in the plans. Construct the fog seal in accordance with Section 5-02.3. Unless otherwise approved by the Engineer, apply the fog seal prior to opening to traffic.

5-04.3(16) HMA Road Approaches

HMA approaches shall be constructed at the locations shown in the Plans or where staked by the Engineer. The Work shall be performed in accordance with Section 5-04.

5-04.3(17) Temporary Asphalt Pavement ***(December 1, 2021 CFW GSP)***

Section 5-04.3(17) is a new section:

Temporary asphalt pavement shall be placed by the Contractor immediately upon the request of the Engineer for the maintenance of traffic during construction. These areas include: voids created by the removal of existing improvements (i.e. Traffic islands, curbs), providing paved access to private properties, and ramps for property access during cement concrete driveway approach construction. All temporary paving shall be approved by the Engineer before placement. Any areas of temporary pavement to be removed and replaced shall be approved by the Engineer beforehand. This work shall also include the removal of temporary asphalt concrete pavement in its entirety prior to final paving.

Hot Mix Asphalt Temporary Pavement: Hot mix asphalt will be used for any trench or pavement restoration within the traveled way. Whether temporary or permanent, saw cut and treat edges with CSS-1 asphalt emulsion and apply a minimum 3-inch pavement depth or match existing, whichever is greater. Also, fill voids created by the removal of existing traffic islands and curbing, paving over excavated roadway to temporary access to adjacent properties, and ramps for property access during concrete approach construction.

Cold Mix Asphalt Temporary Pavement: Cold mix asphalt is allowed for temporary paving outside the traveled way. The cold mix shall be approved by the Engineer and placed in a 2-inch minimum thickness. Placement of temporary pavement without prior approval of the Engineer shall be considered as a benefit of the Contractor and no cost to the owner. Any areas of temporary pavement to be removed and replaced require prior approval by the Engineer. This work shall include the removal of the temporary pavement prior to paving of final asphalt concrete pavement.

5-04.4 Measurement

HMA Cl. ___ PG ___, HMA for ___ Cl. ___ PG ___, and Commercial HMA will be measured by the ton in accordance with Section 1-09.2, with no deduction being made for the weight of asphalt binder, mineral filler, or any other component of the mixture. If the Contractor elects to remove and replace mix as allowed by Section 5-04.3(11), the material removed will not be measured.

Roadway cores will be measured per each for the number of cores taken.

Pavement repair excavation will be measured by the square yard of surface marked prior to excavation.

Planing bituminous pavement will be measured by the square yard.

(April 12, 2018 CFW GSP)

Section 5-04.4 is supplemented with the following:

Hot Mix Asphalt Temporary Pavement shall be measured by the ton of material actually placed, with no deduction being made for the weight of liquid asphalt, blending sand, mineral filler, or any other component of the mixture. Hot Mix Asphalt Temporary

Pavement shall be paid under the "Temporary Pavement" bid item and shall include placement and compaction of hot mix asphalt, removal and disposal of temporary pavement.

Cold Mix Asphalt Temporary Pavement will not be measured and shall be considered incidental to other bid items.

(December 1, 2021 CFW GSP)

Section 5-04.4 is supplemented with the following:

"Remove and Replace HMA Speed Hump, Complete", per each.

(*****)

Section 5-04.4 is supplemented with the following:

"Remove and Replace Raised Crosswalk, Complete", per each

5-04.5 Payment

Payment will be made for each of the following Bid items that are included in the Proposal:

"HMA Cl. ___ PG ___", per ton.

"HMA for Approach Cl. ___ PG ___", per ton.

"HMA for Preleveling Cl. ___ PG ___", per ton.

"HMA for Pavement Repair Cl. ___ PG ___", per ton.

"Commercial HMA", per ton.

The unit Contract price per ton for "HMA Cl. ___ PG ___", "HMA for Approach Cl. ___ PG ___", "HMA for Preleveling Cl. ___ PG ___", "HMA for Pavement Repair Cl. ___ PG ___", and "Commercial HMA" shall be full compensation for all costs, including anti-stripping additive, incurred to carry out the requirements of Section 5-04 except for those costs included in other items which are included in this Subsection and which are included in the Proposal.

"Pavement Repair Excavation Incl. Haul", per cubic yard.

The unit Contract price per cubic yard for "Pavement Repair Excavation Incl. Haul" shall be full payment for all costs incurred to perform the Work described in Section 5-04.3(4) with the exception, however, that all costs involved in the placement of HMA shall be included in the unit Contract price per ton for "HMA for Pavement Repair Cl. ___ PG ___", per ton.

"Asphalt for Prime Coat", per ton.

The unit Contract price per ton for "Asphalt for Prime Coat" shall be full payment for all costs incurred to obtain, provide and install the material in accordance with Section 5-04.3(4).

"Prime Coat Agg.", per cubic yard, or per ton.

The unit Contract price per cubic yard or per ton for “Prime Coat Agg.” shall be full pay for furnishing, loading, and hauling aggregate to the place of deposit and spreading the aggregate in the quantities required by the Engineer.

“Planing Bituminous Pavement”, per square yard.

The unit Contract price per square yard for “Planing Bituminous Pavement” shall be full payment for all costs incurred to perform the Work described in Section 5-04.3(14).

“Job Mix Compliance Price Adjustment”, by calculation.

“Job Mix Compliance Price Adjustment” will be calculated and paid for as described in Section 5-04.3(9)C6.

“Compaction Price Adjustment”, by calculation.

“Compaction Price Adjustment” will be calculated and paid for as described in Section 5-04.3(10)D3.

“Roadway Core”, per each.

The Contractor’s costs for all other Work associated with the coring (e.g., traffic control) shall be incidental and included within the unit Bid price per each.

“Cyclic Density Price Adjustment”, by calculation.

“Cyclic Density Price Adjustment” will be calculated and paid for as described in Section 5-04.3(10)B.

(*****)

Section 5-04.5 is supplemented with the following:

“Remove and Replace Raised Crosswalk, Complete”, per each. The unit contract price for each for Remove and Replace Raised Crosswalk, Complete shall be full compensation for all tools, labor, equipment, and materials necessary to remove and reinstall the Raised Crosswalk and pavement markings, including, but not limited to: grinding, pavement removal, excavation, asphalt placement, plastic pavement markings, paint pavement markings, and raised pavement markers.”

(April 12, 2018 CFW GSP)

Section 5-04.5 is supplemented with the following:

“Temporary Pavement”, per ton.

(December 1, 2021 CFW GSP)

Section 5-04.5 is supplemented with the following:

“Remove and Replace HMA Speed Hump, Complete”, per each. The unit contract price per each for Remove and Replace HMA Speed Hump, Complete shall be full compensation for all tools, labor, equipment, and materials necessary to remove and reinstall the HMA Speed Hump and pavement markings, including, but not limited to:

grinding, pavement removal, excavation, asphalt placement, plastic pavement markings, and raised pavement markers.

END OF DIVISION 5

DIVISION 6 STRUCTURES

6-02 CONCRETE STRUCTURES

6-02.3 Construction Requirements

6-02.3(2)A Contractor Mix Design *(December 16, 2022 CFW GSP)*

The first sentence of the first paragraph of Section 6-02.3(2)A is deleted and replaced with the following:

The Contractor shall provide a mix design in writing to the Engineer for all classes of concrete.

6-02.3(2)B Commercial Concrete *(December 16, 2022 CFW GSP)*

The last sentence of the first paragraph of Section 6-02.3(2)B is deleted and replaced with the following:

Commercial concrete requires mix design and source approvals for cement, aggregate, and other admixtures.

Section 6-02.3(2)B is supplemented with the following:

The concrete class requirements in paragraph one and two are applicable for Type I/II Portland cement. See Section 9.01.2(1)B for requirements for Type 1L cement.

6-10 CONCRETE BARRIER

6-10.3 Construction Requirements

6-10.3(1) Precast Concrete Barrier *(December 16, 2022 CFW GSP)*

Section 6-10.3(1) is supplemented with the following:

The concrete class requirements are applicable for Type I/II Portland cement. See Section 9-01.2(1)B for requirements for Type 1L cement.

6-10.3(2) Cast-In-Place Concrete Barrier *(December 16, 2022 CFW GSP)*

Section 6-10.3(2) is supplemented with the following:

The concrete class requirements are applicable for Type I/II Portland cement. See Section 9-01.2(1)B for requirements for Type 1L cement.

END OF DIVISION 6

**DIVISION 7
DRAINAGE STRUCTURES, STORM SEWERS,
SANITARY SEWERS, WATER MAINS, AND CONDUITS**

7-01 DRAINS

7-01.1 Description

(April 12, 2018 CFW GSP)

Section 7-01.1 is supplemented with the following:

This work consists of replacing a existing catch basin with a new 6'x8' Contech Modular Wetlands. The Modular Wetlands

7-01.3 Construction Requirements

7-01.3(3) Cleanouts and Fittings for Drain and Underdrain Pipe

(April 12, 2018 CFW GSP)

Section 7-01.3(3) is a new section:

The Contractor shall install cleanouts at the terminal end of any drain or underdrain pipe not entering into a drainage structure. Cleanouts shall be installed at 150' maximum spacing with a maximum of two (2) cleanouts per section of drain or underdrain pipe.

7-01.5 Payment

(December 16, 2022 CFW GSP)

Section 7-01.5 is supplemented with the following:

Excavation, laying pipe, fittings, cleanouts, pipe bedding, imported backfill material, construction geotextile, connections to new or existing storm drainage structures, haul and disposal of trench material to be wasted including unsuitable material, cleaning, and testing will not be measured as these items are incidental to the drain pipe and/or underdrain pipe pay item(s).

7-04 Storm Sewers

7-04.2 Materials

(October 11, 2024 CFW GSP)

Section 7-04.5 is deleted and replaced with the following:

Materials shall meet the requirements of the following sections:

Solid Wall PVC Storm Sewer Pipe	9-05.12(1)
Reinforced Concrete Storm Sewer Pipe	9-05.7(2)
Polyvinyl Chloride (PVC) Pressure Pipe (4 inches and over)	9-30.1(5)A
Dual Wall HDPE Storm Sewer Pipe	9-05.12(3)
Ductile Iron Storm Sewer Pipe	9-05.13

7-04.3 Construction Requirements

7-04.3(1) Cleaning and Testing

(April 12, 2018 CFW GSP)

Section 7-04.3(1) is supplemented with the following:

Cleaning and testing of storm sewer pipe shall be in accordance with Section 7-04.3(1) of the Standard Specifications, except as modified herein:

Any departures from the best construction practices by the Contractor, such as pipe line misalignment, presence of foreign matter in the pipes or catch basins, poor catch basin construction, etc., shall be corrected by the Contractor at the Contractor's own expense. Testing will not be authorized until such corrections have been made to the satisfaction of the Engineer.

7-04.5 Payment

(December 16, 2022 CFW GSP)

Section 7-04.5 is supplemented with the following:

"Polyvinyl Chloride (PVC) Pressure Pipe ____ In. Diam.", per linear foot.

"Ductile Iron Storm Sewer Pipe ____ In. Diam.", per linear foot.

Section 7-04.5 is modified as follows:

The unit contract price per linear foot of storm sewer pipe of the type and size specified shall be full pay for furnishing all tools, labor, and equipment, and materials necessary for its complete installation, including, but not limited to: sawcutting for trench, sawcutting for "T-Cut" for trench restoration, pavement removal, trench excavation, dewatering (if required), temporary flow bypass, laying pipe, pipe bedding, imported backfill, compaction, connection to new or existing storm sewers or drainage structures, haul and disposal of trench material to be wasted including unsuitable material, cleaning and testing, and costs related to maintaining existing drainage system during construction or to provide temporary drainage systems.

90% of payment will be made once the storm sewer pipe is installed. The remaining 10% will be paid once pipe testing has been completed with satisfactory results. The engineer will have the discretion to adjust these payment percentages as may be appropriate. Payment percentages may be adjusted for any reason the engineer deems necessary, including but not limited to, a high number of unsatisfactory test results.

7-05 MANHOLES, INLETS, CATCH BASINS, AND DRYWELLS

7-05.3 Construction Requirements

(March 22, 2023 CFW GSP)

Section 7-05.3 is supplemented with the following:

Storm drain cleanouts shall be provided for retaining wall drainage and connected to the storm drainage system at the locations specified in the plans or as directed by the Engineer.

All lids located within sidewalk areas, along an ADA pedestrian route, or in other accessible surfaces within the public right-of-way or on publicly owned properties, must meet ADA requirements and be slip-resistant. Acceptable slip-resistant products shall be non-slip methyl methacrylate (MMA) coating. Placement of the non-slip MMA coating shall be in accordance with the manufacturer's recommendations. Vertical edges of the utility shall be flush with the adjoining surface to the extent possible after installation.

The following requirements shall be applicable to both existing and proposed structures, as shown in the plans, or as designated by the Engineer:

Vaned Grate vs Solid Lid

A vaned grate and associated frame shall be installed on manholes and catch basins located where they will accept runoff. Bi-directional vaned grates shall be installed at all roadway sag locations and at low points along curb returns.

All structures not receiving surface runoff shall include solid lids, unless otherwise indicated in the plans or directed by the Engineer.

Locking vs Non-Locking Lid

All lids and frames shall be locking unless shown as non-locking on plans or directed otherwise by the Engineer. The Contractor shall place anti-seize compound on all locking lid bolts prior to the final project punch list inspection.

Round vs Square Lid

All structures, new or existing, shall utilize round lids, except for those that accept surface runoff (i.e. those located along a gutter flow line). Catch basins shall include conversion risers to accommodate round lids where indicated in the plans or directed by the Engineer.

Heavy-Duty Hinged Frames and Covers

Heavy-duty hinged frames and covers shall be installed whenever round, solid lids are required as outlined above.

7-05.3(1) Adjusting Manholes, Valve Boxes and Catch Basins to Grade
(January 19, 2024 CFW GSP)

Section 7-05.3 is supplemented with the following:

Manholes, valve boxes, catch basins, and other structures shall not be adjusted to final grade until the adjacent pavement is completed, at which time the center of each structure shall be carefully relocated from references previously established by the Contractor. The asphalt concrete pavement shall be removed to a neat circular shape for circular grates and covers and a neat rectangular shape for rectangular grates and covers. The edge of the cut shall be 1.5 feet from the outside edge of the cast iron frame of the structure. The base materials and crushed rock shall be removed to the full depth of adjustment plus 2 inches. The manhole and catch basin frames shall be lifted and reset to the final grade, plumb to the roadway, and shall remain operational and accessible in accordance with City of Federal Way Standard Drawings.

Shims and adjustment materials may not be made of wood or other degradable materials.

The Contractor shall adjust manholes and catch basins with pre-cast grade rings, and mortar and high impact adjustment risers with a maximum 2-inch thickness where required for heavy-duty frames and covers within the travelled roadway. Metal adjustment rings shall not be used. If more than three grade rings are required to adjust a manhole or Type 2 catch basin to final grade, including existing grade rings, the Contractor shall remove the existing cone section or top slab, install a pre-cast manhole section of sufficient height to limit the number of grade rings to a maximum of three, and reinstall the cone section or top slab prior to paving operations. Grade adjustment rings and high impact riser installation shall be inspected by the Engineer prior to frame installation. Cover and grate frames shall be securely grouted to the structure.

Where existing structures are located within the wheel path of a proposed travel lane, catch basins adjusted to grade shall also include conversion risers and heavy duty locking frames and covers and high-impact risers.

Following frame installation, the edges of the removed asphalt pavement and the outer edge of the reset frame shall be painted with asphalt for tack coat. The entire void around the adjustment shall then be filled with Commercial HMA, placed and compacted in maximum 3-inch lifts, to match the adjacent pavement surface. The joint between the patch and existing pavement shall then be painted with asphalt for tack coat and immediately covered with dry paving sand before the asphalt for tack coat solidifies.

7-05.3(3) Connections to Existing Manholes

(April 12, 2018 CFW GSP)

Section 7-05.3(3) is supplemented with the following:

The requirements of this section shall also apply to connections to existing catch basins.

7-05.3(5) Connections to Existing Pipe

(April 12, 2018 CFW GSP)

Section 7-05.3(5) is a new section:

The contractor shall connect (or reconnect) existing pipes to new manholes or catch basins without obstructing flow from upstream locations.

7-05.3(6) Cleaning

(April 12, 2019 CFW GSP)

Section 7-05.3(6) is a new section:

Prior to final project acceptance by the City, the Contractor shall be responsible to ensure the sumps of all manholes, inlets, catch basins, and drywells are clean of sediment and debris.

7-05.4 Measurement

(January 19, 2024 CFW GSP)

Section 7-05.4 is supplemented with the following:

7-05.5 Payment

(January 19, 2024 CFW GSP)

Section 7-05.5 is supplemented with the following:

The unit contract price for catch basins and/or manholes shall be full pay for furnishing all labor, tools, equipment, and materials necessary to complete each unit according to the Plans and Specifications. This includes all sawcutting, pavement removal and disposal, excavation, dewatering (if required), temporary flow bypass, connections to existing and new pipe, foundation material, bedding, imported backfill, compaction, surface restoration, testing, cleaning, and furnishing and placing of all accessories and conversion risers, temporary patching hot mix to allow for the passage of traffic, and other items as applicable. Frames and grates or rings and covers, grade rings and adjustment risers including conversion risers, and non-slip MMA coating for new lids in accessible surfaces shall be considered incidental to this bid item and will not be measured for separate payment. 50% of payment will be made once the catch basin or manhole is installed and the pipe inlets and outlets are grouted. The remaining 50% will be paid once risers/rings are grouted to the satisfaction of the City, the frame/grate is installed, and non-slip MMA coating is applied.

The unit contract price for “Adjust Manhole” and/or “Adjust Catch Basin” and/or “Adjust Inlet” applies to existing storm drainage catch basins, inlets, and manholes that require adjustment to grade by addition or removal of adjustment risers. The unit contract price includes all labor, tools, equipment, and materials necessary to adjust to finished grade,

sawcutting, temporary patching hot mix to allow for the passage of traffic, restoration of the area around the adjusted structure, and providing new rings and covers or frames and grates. Conversion of catch basin/manhole/inlet lids (i.e. convert to heavy duty, solid, round locking lid) shall be included in this bid item. Grade rings and adjustment risers (concrete or high-impact) shall be considered incidental to this bid item and will not be measured for separate payment. Non-slip MMA coating for lids in accessible surfaces shall be considered incidental to this bid item and will not be measured for separate payment. Payment will be made once the adjustment is fully complete and grouted. Partial payment will not be made if risers have been added, but the grouting has not been completed to the satisfaction of the City.

The unit contract price for “Connection to Drainage Structure” applies to connecting new storm drain pipe to existing storm drainage catch basins and manholes and includes all labor, tools, equipment, and materials necessary to core drill the existing drainage structure and provide the necessary pipe connection. Any associated sawcutting, pavement removal and disposal, excavation, imported backfill, compaction, and pavement restoration are incidental to this bid item.

“Non-slip MMA Coating for Lids”, per lump sum.

7-07 CLEANING EXISTING DRAINAGE STRUCTURES

7-07.5 Payment

(April 12, 2018 CFW GSP)

Section 7-07.5 is replaced with the following:

All costs associated with cleaning existing drainage structures shall be considered incidental to and included in the various bid items and no additional payment shall be made.

7-08 GENERAL PIPE INSTALLATION REQUIREMENTS

7-08.3(1)A Trenches

(March 22, 2023 CFW GSP)

Section 7-08.3(1)A is supplemented with the following:

Where water is encountered in the trench, it shall be removed during pipe-laying operations and the trench so maintained until the ends of the pipe are sealed and provisions are made to prevent floating of the pipe. Trench water or other deleterious materials shall not be allowed to enter the pipe at any time.

Trenching may disturb existing pavement markings that are not shown to be replaced in the plans. All such pavement markings damaged by trenching shall be repaired after trenching is backfilled and restored. The new pavement markings shall match the damaged pavement marking. All pavement marking repair cost shall be incidental to the pipe installation, including all necessary labor and materials.

7-08.3(3) Backfilling

(December 16, 20228 CFW GSP)

Section 7-08.3(3) is supplemented with the following:

Initial backfilling shall be performed only after inspection and approval of the installed pipe. Backfill shall be accomplished in such a manner that the pipe is not damaged by impact or overloading. Water settling will not be permitted.

If there is an excess of acceptable backfill material obtained from trench excavation at one location on the project, the Contractor may request approval from the City to use it at other locations on the project. Native backfill stockpiles shall be protected to prevent excessive wetting. The cost of transporting the excess backfill material shall be considered incidental to the pipe or structure backfilled.

7-12 VALVES FOR WATER MAINS

7-12.4 Measurement

(December 1, 2021 CFW GSP)

Section 7-12.4 is supplemented with the following:

“Adjust Water Valve to Grade” will be measured per each.

7-12.5 Payment

(December 1, 2021 CFW GSP)

Section 7-12.5 is replaced with the following:

The unit contract price for “Adjust Water Valve to Grade” applies to existing water valves that require adjustment to grade. The unit contract price includes all labor, tools, equipment, and materials necessary to adjust valves to finished grade, sawcutting, temporary patching hot mix to allow for the passage of traffic, restoration of the area around the adjusted structure. Non-slip MMA coating for lids in accessible surfaces shall be considered incidental to this bid item and will not be measured for separate payment. Payment will be made once the adjustment is fully complete.

7-17 SANITARY SEWERS

7-17.4 Measurement

(September 20, 2024 CFW GSP)

Section 7-17.4 is supplemented with the following:

“Adjust Sanitary Sewer Manhole” will be measured per each.

7-17.5 Payment

(September 20, 2024 CFW GSP)

Section 7-17.5 is supplemented with the following:

The unit contract price for “Adjust Sanitary Sewer Manhole” applies to existing manholes that require adjustment to grade by addition or removal of adjustment risers. The unit contract price includes all labor, tools, equipment, and materials necessary to adjust to finished grade, sawcutting, temporary patching hot mix to allow for the passage of traffic, restoration of the area around the adjusted structure, and providing new rings and covers or frames and grates. Grade rings and adjustment risers (concrete or high-impact) shall be considered incidental to this bid item and will not be measured for separate payment. Non-slip MMA coating for lids in accessible surfaces shall be considered incidental to this bid item and will not be measured for separate payment. Payment will be made once the adjustment is fully complete and grouted. Partial payment will not be made if risers have been added, but the grouting has not been completed to the satisfaction of the City.

7-20 STORMWATER MEDIA FILTERS

(March 22, 2023 CFW GSP)

Section 7-20 and its subsections are new sections.

7-20.1 Description

This work shall consist of installing Contech Filterra® and/or MWS (Modular Wetland Systems) Linear Modular Wetland Units for water quality treatment as shown in the Plans.

7-20.2 Materials

7-20.2(1) Material Submittals

Submittals for the stormwater filters shall include the following items:

1. Shop Drawings for each stormwater media filter system installation including size, location, inlet and outlet inverts, appurtenant piping; bedding, backfill, concrete top slab, lid details, and anchorage tiedown system details. The concrete top slab design shall provide H-20 loading for each system.
2. Complete materials list.
3. Manufacturer's recommended installation and maintenance procedures.
4. Manufacturer's certificate of satisfactory installation and warranty.

7-20.2(2) Filterra Units

Filterra stormwater media filter units shall consist of Precast Filterra® units, as manufactured by Contech Engineered Solutions, 9025 Centre Pointe Dr. Suite 400, West Chester, Ohio 45069 (800) 338-1122.

Filterra® units shall have a General Use Level Designation (GULD) for Enhanced treatment from the State of Washington Department of Ecology through the TAPE program.

Each Filterra® unit consists of a precast concrete vault; underdrain system consisting of underdrain stone, perforated pipe, and cleanout; filter media; top slab with integrally-cast tree frame and grate, cleanout cover, and galvanized angle nosing; mulch; and plant material. Conduits shall be precast into the vault walls as detailed in the Plans to accommodate irrigation supply lines.

Filterra® Top Slab: Standard Flat Top

7-20.2(3) Modular Wetland Units

Modular Wetland stormwater media filter units shall consist of MWS Linear Modular Subsurface Flow Wetland Systems, as manufactured by Bio Clean Environmental Services, Inc., 2972 San Luis Rey Road, Oceanside, CA 92058, (760) 433-7640, or Modular Wetland Systems, Inc., P.O. Box 869, Oceanside, CA 92049, (760) 433-7650.

Modular Wetland units shall have a General Use Level Designation (GULD) for Enhanced treatment from the State of Washington Department of Ecology through the TAPE program.

Each Modular Wetland unit consists of a precast concrete vault containing a pretreatment chamber, bioriltration chamber, and discharge chamber. The pretreatment chamber houses perforated cartridge media filters, and is used for pretreating stormwater before it enters the bioriltration chamber. The pretreatment chamber has a pervious floor connected to the underdrain system, to function as a drain down system. The biofiltration chamber has a periphial void area around the filtration media cells and a centralized and vertically extending underdrain to collect filtered water from each cell. Treatment media

within the biofiltration chamber consists of a sorptive media mix which does not contain any organic material and a layer of plant establishment media. Pretreated stormwater flows horizontally through the biofiltration material from the exterior void to the underdrain at the center. Treated water collected by the underdrain flows horizontally to the discharge chamber, which houses a flow control orifice plat that restricts flows greater than the treatment flow rate. The discharge chamber also contains a drain down filter to treat drain down flows that are not treated by the biofiltration chamber.

7-20.2(4) Stormwater Treatment System Bedding and Backfill

Bedding and backfill materials for stormwater media filter unit installation shall be in accordance with Section 7-05.3.

7-20.3 Construction Requirements

7-20.3(1) Filterra Unit Installation

Filterra® units shall be constructed as detailed in the Plans and in accordance with these Special Provisions and the manufacturer's installation instructions. Each unit shall be constructed at the locations and elevations according to the sizes shown on the approved Plans. Any modifications to the elevation or location shall be at the direction of and approved by the Engineer.

If the Filterra® unit is stored before installation, the top slab shall be placed on the box using the 2x4 wood provided, to prevent any contamination from the site. All internal fittings supplied (if any), must be left in place as per the delivery.

The unit shall be placed on a compacted sub-grade with a minimum 6-inch gravel base. The unit shall be placed such that the unit and top slab match the grade of the curb in the area of the unit. Compact undisturbed sub-grade materials to 95% of maximum density at +1- 2% of optimum moisture. Unsuitable material below sub-grade shall be replaced to the site Engineer's approval.

The 4-inch outlet pipe from each unit shall be connected to an adjacent catch basin as shown in the Plans, using 8-inch diameter corrugated polyethylene storm drain pipe, with a maximum of two 45-degree bend fittings.

Once the unit is set, the internal wooden forms and protective mesh cover shall be left intact. Remove only the temporary wooden shipping blocks between the box and top slab. The top lid shall be sealed onto the box section before backfilling, using a non-shrink grout, butyl rubber or similar waterproof seal. The boards on top of the lid and boards sealed in the unit's throat must NOT be removed. The Supplier (Contech or its authorized dealer) will remove these sections at the time of activation. Backfilling shall be performed in a careful manner, bringing the appropriate fill material up in 6-inch lifts on all sides. Precast sections shall be set in a manner that will result in a watertight joint. Installation of Filterra® unit shall conform to ASTM specification C891 "Standard Practice for Installation of Underground Precast Utility Structures".

The contractor is responsible for inlet protection/sediment control and cleaning around each Filterra unit.

The curb and gutter adjacent to each Filterra unit shall be cast in place following installation of the Filterra unit, providing a depressed gutter section as detailed in the

Plans. Dowel bars from the pre-cast Filterra unit shall be bent to extend into the cast-in-place depressed gutter as detailed in the Plans. Throat protection device provided with Filterra unit shall remain in place until the site is stabilized and the Filterra unit is activated by Filterra supplier.

The contractor shall verify that the elevation of the next downstream catch basin is lower than the gutter elevation adjacent to the Filterra unit.

Supplied Filterra® units shall include inspection and maintenance by the supplier, or a supplier-approved contractor, for a minimum period of one year, consisting of two scheduled visits. The maintenance visits shall include the following tasks:

1. Filterra® unit inspection.
2. Foreign debris, silt, mulch & trash removal.
3. Filter media evaluation and recharge as necessary.
4. Plant health evaluation and pruning or replacement as necessary.
5. Replacement of mulch.
6. Disposal of all maintenance refuse items.
7. Maintenance records updated, stored, and submitted to the City of Federal Way Surface Water Management Division.

Prior to each maintenance visit, the Federal Way Surface Water Utility shall be notified and allowed to inspect the facility and observe the maintenance of the Filterra® Bioretention System by the supplier or supplier-approved contractor (contact Surface Water Management Division at 253-835-2750).

7-20.3(2) Modular Wetland Unit Installation

Modular Wetland units shall be constructed as detailed in the Plans and in accordance with these Special Provisions and the manufacturer's installation instructions. Each unit shall be constructed at the locations and elevations according to the sizes shown on the approved Plans. Any modifications to the elevation or location shall be at the direction of and approved by the Engineer.

The contractor shall exercise care in the storage and handling of the Modular Wetland unit and all components prior to and during installation. Any repair or replacement costs associated with events occurring after delivery is accepted and unloading has commenced shall be the responsibility of the contractor.

The unit shall be placed on a compacted sub-grade with a minimum 6-inch gravel base. The unit shall be placed such that the unit and top slab match the grade of the curb in the area of the unit. Compact undisturbed sub-grade materials to 95% of maximum density at +1- 2% of optimum moisture. Unsuitable material below sub-grade shall be replaced to the site Engineer's approval.

Once the unit is set, the internal wooden forms and protective silt fabric cover must be left intact (if Wetland Media pre-installed). The top lid(s) shall be sealed onto the box section before backfilling, using a non-shrink grout, butyl rubber or similar waterproof seal. The boards on the top of the lid and boards sealed in the unit's throat must not be removed. The supplier will remove these sections at the time of activation. Outlet connections shall be aligned and sealed in accordance with the Plans and approved shop drawings. The correct outlet will be marked on the Modular Wetland unit. Backfilling shall be performed in a careful manner, bringing the appropriate fill material up in 6-inch lifts on all sides.

Precast sections shall be set in a manner that will result in a watertight joint. Installation of the Modular Wetland unit shall conform to ASTM specification C891 "Standard Practice for Installation of Underground Precast Utility Structures".

If not pre-installed, the contractor shall install Wetland Media in accordance with the manufacturer's installation instructions. Plants for Modular Wetland units (where specified) shall be supplied and installed by the Contractor.

The curb and gutter adjacent to each Modular Wetland unit shall be cast in place following installation of the Modular Wetland unit, constructing a depressed gutter section and fabricated steel curb hood as detailed in the Plans. It is the responsibility of the Contractor to provide curb and gutter transition to the Modular Wetland unit for positive stormwater flow into the system through the throat, pipe or grate opening.

Supplied Modular Wetland units shall include inspection and maintenance by the supplier, or a supplier-approved contractor, for a minimum period of one year, consisting of two scheduled visits. The maintenance visits shall include the following tasks:

1. Modular Wetland® unit inspection.
2. Cleaning pretreatment chamber.
3. Pretreatment media evaluation and replacement as necessary.
4. Disposal of all maintenance refuse items.
5. Maintenance records updated, stored, and submitted to the City of Federal Way Surface Water Management Division.

Prior to each maintenance visit, the Federal Way Surface Water Utility shall be notified and allowed to inspect the facility and observe the maintenance of the Modular Wetland unit by the supplier or supplier-approved contractor (contact Surface Water Management Division at 253-835-2750).

7-20.3(3) Installation Verification

Manufacturer's representative shall observe installation of the stormwater filters and shall provide a certificate of satisfactory installation to Owner prior to operation.

7-20.3(4) Operational Testing

The manufacturer's representative shall participate in and observe operational testing of the stormwater treatment systems for design performance. All observed problems shall be rectified prior to Owner acceptance.

7-20.4 Measurement

Filtterra Units will be measured per each.
Modular Wetland Units will be measured per each.

7-20.5 Payment

Payment will be made for the following bid items when included in the proposal:

"Modular Wetland Unit", per each.

The unit contract price per each for Stormwater Media Filter (Filtterra or Modular Wetland Unit) shall be full pay for furnishing all labor, tools, equipment, and materials necessary to install a Filtterra or Modular Wetland unit of the size and at the location indicated in the Plans. The unit contract price per each for Stormwater Media Filter shall also include

excavation, plant material (where applicable), gravel base, grates and lids, imported backfill, compaction, adjustment to finished grade, depressed gutter, curb hood (for Modular Wetland), facility activation, and one year of inspection and maintenance by supplier. Storm media material (where applicable) shall be installed and facility activation complete before payment shall be made for Stormwater Media Filters.

Gravel borrow used for backfill when the engineer has determined that native material is not satisfactory for backfill shall be paid in accordance with 2-03.5.

END OF DIVISION 7

DIVISION 8 MISCELLANEOUS CONSTRUCTION

8-01 EROSION CONTROL AND WATER POLLUTION CONTROL

8-01.3 Construction Requirements

8.01.3(1) General

(April 12, 2018 CFW GSP)

The first paragraph of 8-01.3(1) is deleted and replaced with the following:

The Contractor shall install a high visibility fence along the right-of-way lines shown in the Plans or as instructed by the Engineer.

8-01.3(1)A Submittals

(April 12, 2018 CFW GSP)

Section 8-01.3(1)A is revised to read:

A Stormwater Pollution Prevention Plan (SWPPP) shall be prepared by the Contractor and submitted for approval to the Engineer. The plan shall consist of the Contractor's complete strategy to meet the requirements of the Department of Ecology's NPDES and State Waste Discharge General Permit for Stormwater Discharges Associated With Construction Activity (General Permit). The SWPPP shall include and modify as necessary the Site Preparation and Erosion Control Plan drawings provided as part of the Contract Plans. The Contractor shall prepare review and modify the SWPPP as necessary to be consistent with the actual work schedule, sequencing, and construction methods that will be used on the project. The Contractor's SWPPP shall meet the requirements of the general permit. The Contractor's modifications to the SWPPP shall also incorporate the content and requirements for the Spill Prevention, Control and Countermeasures (SPCC) Plan in accordance with Section 1-07.15(1).

The SWPPP shall document all the erosion and sediment control Best Management Practices (BMPs) proposed, whether permanent or temporary. The plan shall document installation procedures, materials, scheduling, and maintenance procedures for each erosion and sediment control BMP. The Contractor shall submit the SWPPP for the Engineer's approval before any work begins. The Contractor shall allow at least five working days for the Engineer's review of the initial SWPPP or any revisions to the modified SWPPP. Failure to approve all or part of any such plan shall not make the Contracting Agency liable to the Contractor for any work delays. The Contractor may not begin work without an approved Contractor's SWPPP.

The Contractor shall complete and modify the SWPPP to meet the Contractor's schedule and method of construction. All TESC Plans shall meet the requirements of the current edition of the WSDOT Temporary Erosion and Sediment Control Manual M 3109 and be adapted as needed throughout construction based on site inspections and discharge samples to maintain compliance with the CSWGP. The Contractor shall develop a schedule for implementation of the SWPPP work and incorporate it into the Contractor's progress schedule.

In addition, the SWPPP shall outline the procedures to be used to prevent high pH stormwater or dewatering water from entering surface waters. The plan shall include how the pH of the water will be maintained between pH 6.5 and pH 8.5 prior to being discharged

from the project or entering surface waters. Prior to beginning any concrete or grinding work, the Contractor shall submit the plan, for the Engineer's review and approval.

As a minimum, the SWPPP shall include all the SWPPP requirements identified in the General Permit, including:

Narrative discussing and justifying erosion control decisions (12 elements)

Drawings illustrating BMPs types and locations

Engineering calculations for ponds and vaults used for erosion control

A schedule for phased installation and removal of the proposed BMPs, including:

- A. BMPs that will be installed at the beginning of project startup.
- B. BMPs that will be installed at the beginning of each construction season.
- C. BMPs that will be installed at the end of each construction season.
- D. BMPs that will be removed at the end of each construction season.
- E. BMPs that will be removed upon completion of the project.

An Ecology template is available to the Contractor for producing the SWPPP, using project-specific information added by the Contractor. The template and instructions are available at:

<http://www.ecy.wa.gov/programs/wq/stormwater/construction/>

Turbidity and pH Exceedances

Following any exceedances of the turbidity or pH benchmarks, the Contractor shall provide the following at no additional cost to the Contracting agency:

1. The necessary SWPPP revisions and on-site measures/revisions including additional source control, BMP maintenance, and/or additional stormwater treatment BMPs that are necessary to prevent continued exceedance of turbidity and/or pH benchmarks.
2. The regulatory notification to the Dept. of Ecology and to the Engineer of any monitoring results requiring regulatory notification.
3. The additional daily sampling and reporting measures described in the General Permit to verify when project site runoff is in compliance.

8-01.3(1)B Erosion and Sediment Control (ESC) Lead ***(October 3, 2022 WSDOT GSP, OPTION 1)***

Item number 3 and 4 in the second paragraph of Section 8-01.3(1)B are revised to read:

3. Submit to the Engineer no later than the end of the next working day following the inspection a TESC Inspection Report that includes:
 - a. When, where, and how BMPs were installed, maintained, modified, and removed.
 - b. Observations of BMP effectiveness and proper placement.

- c. Recommendations for improving future BMP performance with upgraded or replacement BMPs when inspections reveal TESC BMP deficiencies.
- d. Identify for each discharge point location whether there is compliance with state water quality standards in WAC 173-201A for turbidity and pH.

8-01.3(2) Seeding, Fertilizing, and Mulching

8-01.3(2)B Seeding and Fertilizing ***(September 3, 2019 WSDOT GSP, OPTION 3)***

Section 8-01.3(2)B is supplemented with the following:

Grass seed shall be a commercially prepared mix, made up of low growing species which will grow without irrigation at the project location, and approved by the Engineer. The application rate shall be two pounds per 1000 square feet. Fertilizer shall be a commercially prepared mix of 10-20-20 and shall be applied at the rate of 10 pounds per 1000 square feet.

8-02 ROADSIDE RESTORATION

8-02.3 Construction Requirements

8-02.3(1) Responsibility During Construction

(April 12, 2018 CFW GSP)

Section 8-02.3(1) is supplemented with the following:

Landscape construction is anticipated to begin after all curbs, sidewalks, walls, and associated roadside work is completed. Landscape materials shall not be installed until weather permits and installation has been authorized by the Engineer. If water restrictions are anticipated or in force, planting of landscape materials may be delayed.

Throughout planting operations, the Contractor shall keep the premises clean, free of excess soils, plants, and other materials, including refuse and debris, resulting from the Contractor's work. At the end of each work day, and as each planting area is completed, it shall be neatly dressed, and all surrounding walks and paved areas shall be cleaned to the satisfaction of the Engineer. No flushing will be allowed. At the conclusion of work, the Contractor shall remove surplus soils, materials, and debris from the construction site and shall leave the project in a condition acceptable to the Engineer.

8-02.3(5) Planting Area Preparation

(April 12, 2018 CFW GSP)

Section 8-02.3(5) is supplemented with the following:

Thoroughly scarify subgrade in tree, and seeded lawn areas to a minimum depth of six-inches (6") except within critical root zones of existing trees to remain, as noted on plans. Scarified subgrade shall be inspected and approved by the Engineer prior to the placement of topsoil. Remove all construction debris and rocks over two-inches (2") in diameter prior to placing topsoil.

Scarified subgrade shall be inspected and approved by the Engineer prior to placement of topsoil. Upon approval of the subgrade, Topsoil A shall be installed to a minimum depth of 4 inches lightly compacted depth in all seeded areas, unless otherwise noted on plans.

Lightly compact soil and establish a smooth and uniform finished grade to allow to surface drainage and prevents ponding.

The areas shall be brought to a uniform grade, 1 inch, or the specified depth of mulch, below walks, curbs, junction and valve boxes, and driveways, unless otherwise specified.

The costs of removing all excess material and debris shall be considered incidental to and included in the unit contract prices of other items in this contract.

8-02.3(6)B Fertilizers

(September 3, 2019 WSDOT GSP, OPTION 3)

Section 8-02.3(6)B is supplemented with the following:

Fertilizer shall be a commercially prepared mix of 10-20-20 and shall be applied at the rate of 10 pounds per 1000 square feet.

8-02.3(8) Planting

(September 20, 2024 CFW GSP)

Section 8-02.3(8) is supplemented with the following:

All Topsoil Type A required to plant trees and bark mulch for topdressing, as specified in the plans, shall be considered incidental to and included in the unit contract price of the trees.

Use loosened and replaced compacted mineral native soil without organics under tree rootball. Use topsoil on sides of tree rootball only. Use full depth topsoil for shrubs.

Trees shall be handled by the rootball, not by the trunk. Burlap and wire shall remain intact until trees are set in their final positions within each planting pit.

Plant trees and shrubs upright and rotate in order to give the best appearance or relationship to adjacent plants, topography, and structures. Hold plant rigidly in position until topsoil has been backfilled and water settled free of voids and air pockets and tamped firmly around the ball or roots.

When the pit is backfilled halfway, place the specified quantity of fertilizer plant tablets and stakes as shown in the Plans. Evenly space the fertilizer tablets around the perimeter of, and immediately adjacent to the root system. Carefully place water and compact planting topsoil, filling all voids. Tree root crowns to be 1" higher than finished grade to allow for settlement.

When the planting pit is three quarters backfilled, fill with water and allow water to soak away. Fill the pits with additional topsoil to finish grade and continue backfilling as detailed in the Plans. Water trees immediately after planting.

The contractor shall place pea gravel flush with bottom of tree grates in tree wells in accordance with City Standard Details.

8-02.3(9)B Seeding and Fertilizing

(September 3, 2019 WSDOT GSP, OPTION 2)

Section 8-02.3(9)B is supplemented with the following:

Grass seed shall be a commercially prepared mix, made up of low growing species which will grow without irrigation at the project location, and accepted by the Engineer. The application rate shall be two pounds per 1000 square feet.

8-02.3(10) Fertilizer

(April 12, 2018 CFW GSP)

Section 8-02.3(10) is supplemented with the following:

All fertilizers shall be furnished in standard unopened containers with weight, name of plant nutrients and manufacturer's guaranteed statement of analysis clearly marked, in accordance with State and Federal law.

Seeded areas, trees, and shrubs shall be fertilized at a rate according to fertilizer manufacturer's recommendations.

8-02.3(11) Bark or Wood Chip Mulch

(March 22, 2023 CFW GSP)

Section 8-02.3(11) is supplemented with the following:

Bark Mulch shall be placed over all tree planting pits to a depth no less than two (2) inches, or as detailed in the Plans. Thoroughly water and hose down plants with a fine spray to wash the leaves of the plants immediately after application.

8-02.3(17) Protection of Private Property and Property Restoration

(March 22, 2023 CFW GSP)

Section 8-02.3(17) is a new section:

Property Restoration shall consist of fine grading and restoration of adjacent landscaped areas; adjustment and/or replacement of private irrigation systems; slope restoration behind sidewalks; timber edgings; installing and replacing private wood and chain link fencing; and other work not currently identified in the plans, as directed by the Engineer.

The Contractor is specifically reminded that any unnecessary damage caused by construction activities will be repaired at the Contractor's expense.

Restore all disturbed areas to original condition or better. Grass areas shall be restored with hydroseed where directed.

Removal of tree roots outside the limits of construction, as directed by the Engineer and under the supervision of a certified arborist, shall be paid for under "Property Restoration".

Topsoil shall be Type A and mulch shall be Bark or Wood Chip Mulch, per these Special Provisions.

All materials shall conform to Sections 9-14 Erosion Control and Roadside Planting and 9-15 Irrigation System of the Standard Specifications.

The force account provided for property restoration also includes any adjustments and/or replacements of existing irrigation systems not covered under Section 8-03 Irrigation Systems of the Special Provisions. This work shall also consist of modifying existing landscape lighting systems as may become necessary by these improvements.

The Contractor is advised that protecting existing private irrigation and lighting systems from damage does not constitute a basis for claim or extra work.

8-02.4 Measurement

(April 12, 2018 CFW GSP)

Section 8-02.4 is supplemented with the following:

Topsoil, bark mulch, compost, and/or soil amendments will be measured by the cubic yard in the haul conveyance at the point of delivery.

“Seeded Lawn” will be measured in square yards of actual lawn completed, established, and accepted.

“Property Restoration” will be paid by force account and must be approved by the engineer prior to completing the work.

Fertilizer shall be incidental to other bid items unless specifically listed as a bid item.

8-02.5 Payment

(April 12, 2018 CFW GSP)

Section 8-02.5 is supplemented with the following:

“Seeded Lawn” per square yard. The unit contract price will include all preparation, fertilizer, establishment, and mowing as called for in the specifications.

“Property Restoration” per force account.

8-04 CURBS, GUTTERS, AND SPILLWAYS

8-04.3 Construction Requirements

(September 20, 2024 CFW GSP)

Section 8-04.3 is supplemented with the following:

The sub-base for curb and gutter sections shall be compacted to 95 percent density at or below optimum moisture content, as per Section 2-03.3(14)D revised, before placing the curb and gutter.

White-pigmented curing compounds will not be allowed.

The top of the finished concrete shall not deviate more than one-eighth (1/8”) in ten feet (10’) or the alignment one-fourth (1/4”) in ten feet (10’).

Where shown in the Plans, the concrete curb will be ramped for wheel chairs as shown in the City of Federal Way Standard Details and WSDOT Standard Plans.

Where shown in the Plans, the Contractor shall paint the curbs with 2-coats of yellow paint. Paint and application shall conform to the Standard Specifications for traffic paint striping.

8-04.3(1) Cement Concrete Curbs, Gutters, and Spillways

(December 16, 2022 CFW GSP)

Section 8-04.3(1) is supplemented with the following:

The concrete class requirements in paragraph one are applicable for Type I/II Portland cement. See Section 9.01.2(1)B for requirements for Type 1L cement.

8-04.4 Measurement

(April 12, 2018 CFW GSP)

Section 8-04.4 is supplemented with the following:

Painting of curbs, where required, will not be measured and is considered incidental to the unit price of the type of curb.

8-06 CEMENT CONCRETE DRIVEWAY ENTRANCES

8-06.3 Construction Requirements

(December 16, 2022 CFW GSP)

Section 8-06.3 is supplemented with the following:

The concrete class requirements in paragraph one are applicable for Type I/II Portland cement. See Section 9.01.2(1)B for requirements for Type 1L cement.

All driveways shall remain open except as necessary to permit curing of construction materials or for short periods of time as required for excavations. However, at least one (1) driveway per parcel shall remain open to vehicular traffic at all times unless otherwise approved by the Engineer and affected property owner in writing. If a parcel has only one driveway, then that driveway must be constructed one-half at a time to allow the passage of vehicles. The amount of time that a driveway can be closed will be limited. To meet these requirements, the Contractor may use a quick setting concrete. The Engineer shall approve the quick-setting mix prior to use.

Property owners shall be notified in writing at least 48 hours in advance of any planned driveway closures

Crushed rock may be used, with Engineer approval, to maintain a driving surface.

8-06.5 Payment

(April 12, 2018 CFW GSP)

Section 8-06.5 is supplemented with the following:

If the Contractor chooses to use a quick-setting concrete mix for driveway construction, any additional costs to use such mix shall be incidental to the bid item for "Cement Conc. Driveway" and no additional payment will be made.

If the Contractor chooses to use crushed rock to maintain a driveway surface, it shall be incidental to the bid item for "Cement Conc. Driveway" and no additional payment shall be made.

8-07 PRECAST TRAFFIC CURB

8-07.3 Construction Requirements

8-07.3(16) Installing Curbs

(September 20, 2024 CFW GSP)

Section 8-07.3(16) is supplemented with the following:

Nosing pieces will be required at the exposed ends of curbs.

8-09 RAISED PAVEMENT MARKERS

8-09.1 Description

(September 20, 2024 CFW GSP)

Section 8-09.1 is supplemented with the following:

RPMs shall be installed in accordance with City of Federal Way Standard Details. Type 2BB RPMs (blue, bi-directional) shall be installed at all hydrant locations, near the center line of the street, offset to the side of the street containing the hydrant.

8-13 MONUMENT CASES

8-13.2 Materials

(March 13, 1995 WSDOT GSP, OPTION 1)

Section 8-13.2 is supplemented with the following:

The pipe shall be Schedule 40 galvanized pipe.

8-13.3(1) Monument Case and Cover

(March 22, 2023 CFW GSP)

The last paragraph of Section 8-13.3(1) is revised to read:

The monument will be furnished and set by the Contractor.

8-13.3(2)A Removing and Lowering Monument Case and Cover

(January 28, 2024 CFW GSP)

Section 8-13.3(2)A is supplemented with the following:

When existing monument cases are lowered prior to planing and/or paving, it is the Contractor's responsibility to notify the City of any damaged or missing monuments and/or monument cases that are not able to be opened, lowered, and/or raised. If the Contractor does not notify the City of existing damage/issues with monuments & monument cases prior to planing and/or paving, any such damages/issues shall be the responsibility of the Contractor to repair and/or replace.

8-13.3(2)B Reinstalling Monument Case and Cover

(December 16, 2022 CFW GSP)

Section 8-13.3(2)B is supplemented with the following:

The concrete class requirements listed are applicable for Type I/II Portland cement. See Section 9.01.2(1)B for requirements for Type 1L cement.

8-13.3(3)A Pre-Construction Monument Survey

(January 28, 2024 CFW GSP)

Section 8-13.3(3)A is a new Section.

Prior to any planing, paving, or other work that may disturb survey monuments, Contractor shall have a Professional Surveyor survey all monuments shown on the plans or discovered within the project limits. A pre-planing metal detection check shall be completed per Section 5-04.3(14)A. Contractor shall provide results of pre-construction monument survey to the Project Engineer. Results shall be in a spreadsheet that includes the following:

Monument location

Monument, Case, and Cover Condition

Location (vertical accuracy within +/- 0.001 foot and horizontal accuracy within +/- 0.001 foot).

8-13.3(3)B Post-Construction Monument Survey

(January 19, 2024 CFW GSP)

Section 8-13.3(3)B is a new Section.

After completion of construction, Contractor shall survey all monuments shown on the plans or discovered within the project limits. A City of Federal Way Monument Record form shall be completed and stamped by a Professional Land Surveyor and submitted to the Project Engineer for each monument.

8-13.3(3)C Permit to Remove or Destroy Survey Monuments

(January 19, 2024 CFW GSP)

Section 8-13.3(3)C is a new Section.

In accordance with RCW 58.24.040(8), no cadastral or geodetic survey monument may be disturbed without a valid permit to remove or destroy a survey monument, issued by the Washington State Department of Natural Resources. Permit applications can be obtained on the DNR Public Land Survey Office website. The permit application must be stamped by a registered Washington State Land Surveyor. The Contractor shall obtain the permit to Remove or Destroy a survey monument as necessary. All costs to obtain and comply with the permit shall be considered incidental other bid items and no additional payment will be made.

8-13.4 Measurement

(January 19, 2024 CFW GSP)

The first paragraph of Section 8-13.4 is revised to read:

Measurement of monument case and cover will be by the unit for each monument case and cover furnished and set. Incidental to this bid item is the installation of survey monuments (brass discs, copper pug, or tack, etc.) when required.

Section 8-13.4 is supplemented with the following:

Pre-construction monument survey and post-construction monument survey are incidental to these bid items.

8-13.5 Payment

(January 19, 2024 CFW GSP)

The first paragraph of Section 8-13.4 is revised to read:

Payment for "Monument Case and Cover" and "Adjust Monument Case and Cover" will be paid as follows:

- 25% of bid item – Upon acceptance by the City of pre-construction monument survey.
- 50% of bid item – Upon completion of installation/adjustment of monument case and cover.
- 100% of bid item – Upon acceptance by the City of post-construction monument survey.

8-14 CEMENT CONCRETE SIDEWALKS.

8-14.2 Materials

(December 16, 2022 CFW GSP)

Section 8-14.2 is supplemented with the following:

The Cement Concrete Sidewalk and curb ramps shall be constructed of Class 4000 concrete or greater if Type I/II Portland cement is used. If Type 1L Blended hydraulic cement is used, see 9-01.2(1)B.

8-14.3 Construction Requirements

(December 16, 2022 CFW GSP)

Section 8-14.3 is supplemented with the following :

The concrete class requirements in paragraph one are applicable for Type I/II Portland cement. See Section 9.01.2(1)B for requirements for Type 1L cement.

(April 3, 2017 WSDOT GSP, OPTION 1)

Section 8-14.3 is supplemented with the following :

The Contractor shall request a pre-meeting with the Engineer to be held 2 to 5 working days before any work can start on cement concrete sidewalks, curb ramps or other pedestrian access routes to discuss construction requirements. Those attending shall include:

1. The Contractor and Subcontractor in charge of constructing forms, and placing, and finishing the cement concrete.
2. Engineer (or representative) and Project Inspectors for the cement concrete sidewalk, curb ramp or pedestrian access route Work.

Items to be discussed in this meeting shall include, at a minimum, the following:

1. Slopes shown on the Plans
2. Inspection
3. Traffic control
4. Pedestrian control, access routes and delineation
5. Accommodating utilities
6. Form work
7. Installation of detectable warning surfaces
8. Contractor ADA survey and ADA Feature as-built requirements
9. Cold Weather Protection

(January 7, 2019 WSDOT GSP, OPTION 2)

Section 8-14.3 is supplemented with the following:

Timing Restrictions

Curb ramps shall be constructed on one leg of the intersection at a time. The curb ramps shall be completed and open to traffic within five calendar days before construction can begin on another leg of the intersection unless otherwise allowed by the Engineer.

Unless otherwise allowed by the Engineer, the five calendar day time restriction begins when an existing curb ramp for the quadrant or traffic island/median is closed to pedestrian use and ends when the quadrant or traffic island/median is fully functional and open for pedestrian access.

(January 7, 2019 WSDOT GSP, OPTION 3)

Section 8-14.3 is supplemented with the following:

Layout and Conformance to Grades

Using the information provided in the Contract documents, the Contractor shall layout, grade, and form each new curb ramp, sidewalk, and curb and gutter.

(March 22, 2023 CFW GSP)

Section 8-14.3 is supplemented with the following:

Cement concrete sidewalk thickness shall be as shown in the Plans. Score joints shall be constructed at a maximum distance of 5 feet from each full depth expansion joint, except where specific dimensions are detailed in the Plans. Asphalt mastic joint fillers in the sidewalk shall be 3/8" x 4" and of the same material as that used in the curb, and shall be placed in the same location as that in the curb.

No concrete for sidewalk shall be poured against dry forms or dry subgrade.

The Contractor may provide suitable vibrating finishers for use in finishing concrete sidewalks. The type of vibrator and its method of use shall be subject to the approval of the City.

All completed work shall be so barricaded as to prevent damage. Any damaged sections shall be removed and replaced at the Contractor's expense. Landscaped areas disturbed during construction shall be restored to original condition at the Contractor's expense.

Scored Cement Concrete Sidewalk shall be broom finished and scored as detailed in the Plans.

8-14.3(5)C Surface Applied Detectable Warning Surface
(December 16, 2022 CFW GSP)

Section 8-14.3(5)C is replaced with the following:

Glued or stick down Detectable Warning Surfaces are allowed on asphalt surfaces only for temporary work zone applications.

MMA-Style Truncated Dome Detectable Warning Surfaces applied to asphalt surfaces for permanent installations shall be liquid-applied Vanguard ADA Systems, or approved equal.

8-14.4 Measurement
(April 12, 2018 CFW GSP)

Section 8-14.4 is supplemented with the following:

8-14.5 Payment
(September 20, 2024 CFW GSP)

Section 8-14.5 is supplemented with the following:

Payment for "Cement Conc. Curb Ramp Type ____" will not be made until the City has verified that the ramp(s) meet ADA requirements.

8-21 PERMANENT SIGNING

8-21.1 Description
(September 20, 2024 CFW GSP)

Section 8-21.1 is deleted and replaced with the following:

This work shall consist of furnishing and installing permanent signing, sign removal, and sign relocation at the locations shown in the Plans or where designated by the Engineer. Signs to be removed as shown in the Plans, shall be returned to the King County Sign Shop in Renton.

Utility locates for sign locations must be completed prior to the installation or relocation of any signs.

8-21.2 Materials

(September 20, 2024 CFW GSP)

Section 8-21.2 is supplemented with the following:

Contractor-provided signal system-mounted overhead signs shall be single-sided and as detailed in the Plans, City of Federal Way Standard Details, and as approved by the City of Federal Way. Shop drawing submittals shall be required for all overhead signal system-mount signing in accordance with Section 8-20.2(1), prior to fabrication.

All signal system-mounted signs shall require installation as part of the signal work. Attach signal system-mounted signs in accordance with Standard Plans, unless otherwise noted.

Colors of all permanent signs shall be submitted to the City for approval prior to installation in the field. All new signs that do not have color approved by the City may be required to be removed and replaced in an acceptable color at the Contractor's expense.

8-21.3 Construction Requirements

8-21.3(1) Location of Signs

(September 20, 2024 CFW GSP)

Section 8-21.3(1) is supplemented with the following:

Post lengths shall be determined by the Contractor. Signs shall be installed in accordance with the MUTCD and City of Federal Way Standard Details. Posts shall not extend beyond the top of the installed sign, unless specifically called for in the Plans.

Sign installation and maintenance shall include maintaining proper visibility of all signs, including those part of an RRFB or signal, at all times. If vegetation trimming is required, it shall be completed by the Contractor and considered incidental to the bid item.

8-21.3(2) Placement of Signs

(September 20, 2024 CFW GSP)

Section 8-21.3(2) is supplemented with the following:

The Contractor shall be required to furnish the signs, sign posts, and mounting hardware. Unless otherwise noted in the Plans, the Contractor shall install all signs on metal posts.

Catalog cuts indicating fabrication material, layout, sign size, mounting type, mounting hardware, and specifications for the overhead sign type shall be submitted for approval prior to sign fabrication.

8-21.3(4) Sign Removal

(September 20, 2024 CFW GSP)

Section 8-21.3(4) is supplemented with the following:

This work shall consist of removing existing signs and guide posts within the construction project limits and delivering the signs and guide posts in a timely manner and in good condition to the King County Sign Shop.

The Contractor shall remove and dispose of sign posts, sign anchors, and associated concrete.

The existing signs and guide posts to be removed during this project are listed in the Plans.

No existing sign shall be removed until designated by the Engineer; all signs identified for removal are to be maintained in good condition until removed.

8-21.3(5) Sign Relocation

(September 20, 2024 CFW GSP)

Section 8-21.3(5) is supplemented with the following:

The sign relocation work shall consist of relocating an existing sign to the new designated location. New posts are to be furnished by the Contractor unless reuse of existing post is approved by the Engineer. The Contractor shall remove and dispose of sign posts, sign anchors, and associated concrete.

No existing sign shall be relocated until designated by the Engineer. All signs identified for relocation are to be maintained in good condition.

The Contractor shall coordinate with King County Metro or Pierce Transit personnel as necessary for removal and reinstallation of all existing bus stop signs and supports within the project limits.

8-21.3(12) Steel Sign Posts

(September 20, 2024 CFW GSP)

Section 8-21.3(12) is supplemented with the following:

All City of Federal Way signs mounted on roadside structures shall use steel posts, in accordance with City of Federal Way Standard Details.

8-21.5 Payment

(September 20, 2024 CFW GSP)

Section 8-21.5 is deleted and replaced with the following:

“Permanent Signing”, lump sum.

The lump sum price for “Permanent Signing” shall include all labor, materials, tools, and equipment necessary to furnish and install permanent signing, sign posts, sign removal, and sign relocation. Sign covering shall be incidental and shall not be measured.

All costs for furnishing and installing signs on traffic signal mast arms poles shall be included in the lump sum price for “Traffic Signal System – Complete”.

8-22 PAVEMENT MARKING

8-22.1 Description

(September 20, 2024 CFW GSP)

Section 8-22.1 is supplemented with the following:

Pavement markings shall conform to City of Federal Way Standard Details. Longitudinal striping patterns shall be as shown on Standard Plan M-20.20.

The Contractor shall perform all spotting and layout for all permanent pavement markings.

8-22.2 Materials

(September 20, 2024 CFW GSP)

Section 8-22.2 Sentence #3 is deleted and replaced with the following:

Glass beads for Type A plastic shall be as recommended by the manufacturer.

Section 8-22.2 is supplemented with the following:

Glass beads and Reflective Elements for Type D plastic shall be in accordance with Section 9-34.4. Both glass beads and reflective elements are required to be installed with Type D pavement markings.

8-22.3 Construction Requirements

(March 22, 2023 CFW GSP)

Section 8-22.3 is supplemented with the following:

Permanent pavement markings shall be installed within 30 calendar days after paving. If a project contains paving on multiple streets (i.e., schedules of work), this requirement applies to the paving date for each street / schedule individually.

8-22.3(3) Marking Application

8-22.3(3)E Installation

(September 20, 2024 CFW GSP)

Section 8-22.3(3)E is supplemented with the following:

Profiled Type D lines shall be installed in accordance with Standard Plan M-20.20.

All parallel double lines (narrow pattern and wide pattern) shall be placed in one pass.

All longitudinal pavement markings shall be applied, in cycle, in the direction of traffic, unless specifically approved by the City of Federal Way. The City of Federal Way shall designate in which direction to apply center line striping, as applicable.

For paint, the use of a pushcart or motorized cart is prohibited. A striping truck is required, unless otherwise approved by the Engineer for specific locations.

If Type B plastic markings are allowed, the material shall not overlap and there shall not be gaps between individual segments of the material.

For Type D, liquid cold applied methyl methacrylate, longitudinal line markings, Type D-3 or Type D-4 shall be used. Type D-3 or Type D-4 application method shall be defined as machine extrusion. Application by walk-behind carts is not allowed. Application of double center line by means that requires a separate pass for each line is not allowed.

8-22.3(3)G Glass Beads

(March 13, 2012, CFW GSP)

Section 8-22.3(3)G is supplemented with the following:

Glass beads shall be applied to Type D markings at a rate of 8 to 10 pounds per one hundred square feet.

Reflective elements shall be applied to Type D markings at a rate of 10 grams per 4-inch wide by 1 linear foot of marking.

8-22.3(6) Removal of Pavement Markings

(September 20, 2024 CFW GSP)

Section 8-22.3(6) is supplemented with the following:

As indicated in the Plans, the Contractor shall remove existing pavement markings that may consist of paint, plastic, and raised pavement markings.

All existing, plastic pavement markings that are to be paved over, shall be removed prior to paving.

If, in the opinion of the Engineer, the pavement is materially damaged by pavement marking removal or raised pavement marker removal, such damage shall be repaired by the Contractor in accordance with Section 1-07.13(1).

If pavement markings are removed as a part of pavement grinding or removal, that removal will be considered incidental to that bid item and no additional payment will be made under the pavement marking removal bid item.

8-22.4 Measurement

(December 16, 2022 CFW GSP)

Paragraphs 12 and 13 of Section 8-22.4 are replaced with the following:

Measurement for the removal of all pavement markings will be per lump sum.

(March 22, 2023 CFW GSP)

Section 8-22.4 is supplemented with the following:

Raised Pavement Markers are incidental to Pavement Markings. No separate measurement or payment will be made.

8-22.5 Payment

(December 16, 2022 CFW GSP)

Section 8-22.5 is modified as follows:

The following bid items are deleted:

- “Removing Paint Line”, per linear foot.
- “Removing Plastic Line”, per linear foot.
- “Removing Painted Crosswalk Line”, per square foot.
- “Removing Plastic Crosswalk Line”, per square foot.
- “Removing Painted Traffic Marking”, per each.
- “Removing Plastic Traffic Marking”, per each.

The following is a new bid item:

- “Removing Pavement Markings”, lump sum.

8-23 TEMPORARY PAVEMENT MARKINGS

8-23.1 Description

(March 22, 2023 CFW GSP)

Section 8-23.1 is supplemented with the following:

Temporary pavement markings shall be installed and maintained by the Contractor prior to traffic being released onto public streets when the installation of permanent pavement markings is not yet completed. All pavement markings including lines, symbols, and raised pavement markers shown on the plans and details shall be provided as temporary pavement markings until such time that permanent pavement markings are installed. Temporary pavement markings shall generally follow the alignment for the permanent pavement markings.

8-23.2 Materials

(March 22, 2023 CFW GSP)

Section 8-23.2 is supplemented with the following:

The City of Federal Way does not allow Low VOC Waterborne Paint for temporary or permanent pavement markings.

8-23.3 Construction Requirements

8-23.3(1) General

(September 20, 2024 CFW GSP)

Section 8-23.3(1) is deleted and replaced with the following:

All work zone temporary pavement markings shall be paint, except for markings on the new asphalt or concrete wearing course. This includes lane shifts for construction stages.

All temporary pavement markings that are expected to remain in place for two months or more shall be paint, with raised pavement markers. This includes any work zone markings.

All temporary pavement markings that are installed prior to a winter suspension shall be paint with raised pavement markers. This includes any work zone markings.

Temporary pavement markings that are installed on the wearing course of new asphalt or concrete shall be tape.

Tape may be used for other short-term applications, as approved by the Engineer.

8-23.3(4) Pavement Marking Application

8-23.3(4)A Temporary Pavement Markings – Short Duration

(March 22, 2023 CFW GSP)

Paragraph 2 of Section 8-23.3(4)A is modified as follows:

Temporary Center Line (Double Yellow Center Line) – Two SOLID lines used to delineate adjacent lanes of traffic moving in opposite directions. Temporary raised pavement markings should be installed on both sides of the yellow lines at 40-foot intervals.

Temporary Center Line (Skip Center Line) – A BROKEN line used to delineate adjacent lanes of traffic moving in opposite directions. The broken pattern shall be based on a 10-foot unit, consisting of a 1-foot line with a 9-foot gap.

8-23.3(4)A2 Temporary Pavement Marking Tape

(September 20, 2024 CFW GSP)

Section 8-23.3(4)A2 is supplemented with the following:

Black mask pavement marking tape shall not be used, unless specifically requested by the Engineer.

8-23.3(4)E Removal of Pavement Markings

(September 20, 2024 CFW GSP)

Section 8-23.3(4)E is supplemented with the following:

Raised pavement markers shall be removed prior to paving. This work shall be performed by the Contractor.

8-23.4 Measurement

(September 20, 2024 CFW GSP)

Section 8-23.4 is supplemented with the following:

All Temporary Pavement Marking bid items are inclusive of installation, maintenance, and removal.

Temporary Raised Pavement Markers are incidental to Temporary Pavement Markings. No separate measurement or payment will be made.

Traffic control (Flaggers, Traffic Control Supervisor, Other Traffic Control, etc.) for the initial installation of Temporary Pavement Markings shall be measured and paid in accordance with the respective Traffic Control Bid Items. Traffic control associated with the subsequent maintenance and/or removal of Temporary Pavement Markings shall be incidental to the temporary pavement marking bid items and no additional payment will be made.

8-33 POTHOLING AND RESOLUTION OF UTILITY CONFLICTS

(September 20, 2024 CFW GSP)

Section 8-33 and its subsections are new sections as follows:

8-33.1 Description

(September 20, 2024 CFW GSP)

Section 8-33.1 is a new section:

This work involves the identification and resolution of utility conflicts not identified in the plans between proposed improvements and existing utilities. The City will pay these costs by force account if the work proves to be acceptable and the Contractor had performed the work with the authority of and due notice to the Engineer.

8-33.3 Construction Requirements

(September 20, 2024 CFW GSP)

Section 8-33.3 is a new section:

The City may direct the Contractor to pothole existing utilities to verify the field location and depth. Potholing shall include excavation and backfilling of the existing utility, identification of the pipe or line size, material type and condition and the survey work to locate the facility horizontally and vertically. Survey information to be obtained shall include station and offset to center of utility and elevation at top of utility. Stations, offsets and elevations shall be to the nearest 0.1 foot unless greater accuracy is required. Potholes shall be backfilled with CSTC compacted to 95%, or with CDF, as directed by the Engineer. In areas subject to public traffic, the HMA patch shall match the depth of the surrounding pavement.

In the event that a conflict arises between the proposed improvements and an existing utility, the Resolution of Utility Conflicts item will compensate the Contractor for standby time and additional work in the following manner:

1. Standby time resulting from existing utility conflicts. Standby time is defined as time the Contractor is unable to proceed with progression of a specific work item (i.e. storm drainage, underground utility installation etc.) due to conflicts with existing facilities. However, payment for standby time shall be limited to:
 - a. For each agreed upon conflict, a maximum of four (4) hours of standby time will be paid for actual delay of labor and equipment due to a utility conflict. The

Contractor shall be responsible to adjust his work schedule and/or reassign his work forces and equipment to other areas of work to minimize standby time.

- b. If the conflict is resolved within one (1) hour of notification to the Engineer, no standby time will be paid.
2. Additional work required to resolve utility conflicts will be paid for at the bid unit prices for the associated work. Work that can be measured and paid for at the unit contract prices shall not be identified as force account work. This work includes but is not limited to:
- a. Storm drainage manhole, pipe, vault, and conduit realignments of line and/or grade for the storm drain and undergrounding of overhead utilities, to avoid existing utility conflicts.
 - b. Additional storm drainage manholes, pipe, vaults, and conduit required by a change in alignment, and/or grade, not exceeding the limits set in section 1-04.4 of the Standard Specifications.

8-33.4 Measurement

(September 20, 2024 CFW GSP)

Section 8-33.4 is a new section:

"Potholing", will be measured for force account per Section 1-09.6.

"Resolution of Utility Conflicts" will be measured for force account per Section 1-09.6.

8-33.5 Payment

(September 20, 2024 CFW GSP)

Section 8-33.5 is a new section:

"Potholing", will be paid by force account.

"Resolution of Utility Conflicts", will be paid by force account.

To provide a common proposal for all bidders, the City has estimated the amount for "Resolution of Utility Conflicts" and "Potholing" and entered the amounts in the proposal to become a part of the total bid by the Contractor.

Utility conflicts due to the Contractor's actions or operations shall be resolved by the Contractor at no expense to the Contracting Agency.

END OF DIVISION 8

DIVISION 9 MATERIALS

9-01 CONCRETE

9-01.2 Specifications

9-01.2(1)B Blended Hydraulic Cement ***(December 16, 2022 CFW GSP)***

Section 9-01.2(1)B is modified with the following:

Type 1L cement is only allowed for use within the City of Federal Way subject to the conditions listed below:

	Class 3000 Type 1L	Class 4000 Type 1L	Class 4000 Type 1L with crystalline waterproofing and corrosion protection admixture ¹	Class 5000 Type 1L
Pre-cast Foundations (<i>light standards, signals, RRFBs, etc.</i>)	X	X	X	X
Cast-in-Place Foundations (<i>light standards, signals, RRFBs, etc.</i>)		X	X	X
Pre-cast or cast-in-place catch basins and manholes		X	X	X
Roads, curbs, curb & gutters, roundabouts & aprons, sidewalks, ADA ramps, driveway approaches			X	X
Other exposed surfaces (<i>retaining walls, junction box aprons, cabinet bases, barriers, etc.</i>)			X	X

¹ Crystalline Waterproofing admixtures (Penetron or approved equal) shall meet the following specification: ASTM C494, Type S, hydrophilic, crystalline permeability-reducing admixture for hydrostatic conditions (PRAH) shall form insoluble crystals throughout the concrete matrix, self-healing and sealing all pores, capillaries and cracks up to 0.5mm (1/51 inch). The crystalline waterproofing admixture shall include a colored tracer material so that it is visible when included in the concrete mix.

For all Type 1L concrete mixes, the City will not accept any maleated rosin (i.e. MasterAir AE90) as a supplied air entrainment and waterproofing admixture or any wax-based curing compounds.

9-03 AGGREGATES

9-03.12 Gravel Backfill

9-03.12(6) Pit Run Sand ***(April 12, 2018 CFW GSP)***

Section 9-03.12(6) is a new section:

<u>Sieve Size</u>	<u>Percent Passing</u>
3/8" square	100
U.S. No. 4	90
Sand Equivalent	30 minimum

9-03.14(3) Common Borrow

(April 12, 2018 CFW GSP)

Section 9-03.14(3) is modified with the following requirements:

Material from on-site excavations meeting the requirements for Common Borrow shall be used to the extent practicable. Material for common borrow shall consist of granular soil and/or aggregate which is free of trash, wood, debris, and other deleterious material.

Common Borrow material shall be at the proper moisture content for compaction. This material is generally moisture sensitive. The natural moisture content shall range from not more than 1 percent wet of optimum to not more than 3 percent dry of optimum as determined in accordance with Section 2-03.3(14)D. The material shall not pump or yield under the weight of compaction equipment and construction traffic. The Contractor is responsible for protecting the material from excess moisture wherever/whenever possible. To the extent practicable, this material should be handled only during non-rainy periods and should be removed, hauled, placed, and compacted into final embankments without intermediate handling or stockpiling. Surfaces should be graded and sloped to drain and should not be left uncompacted.

Common Borrow shall meet the following gradation limits:

Sieve Size	Percent Passing (by weight)
6" square ¹	100
4" square	90 – 100
2" square	75 - 100
U.S. No. 4	50 - 80
U.S. No. 40	50 max.
U.S. No 200	25 max.

¹ For geosynthetic reinforced walls or slopes, 100 percent passing 1¼-inch square sieve and 90 to 100 percent passing the 1-inch square sieve.

Common Borrow shall contain sufficient fines for compaction and to bind the compacted soil mass together to form a stable surface when heavy construction equipment is operated on its surface.

9-05 DRAINAGE STRUCTURES AND CULVERTS

9-05.13 Ductile Iron Sewer Pipe

(September 20, 2024 CFW GSP)

Section 9-05.13 is supplemented as follows:

All ductile iron pipe shall be epoxy lined.

9-05.23(1) Dual Wall HDPE Storm Sewer Pipe

(October 11, 2024 CFW GSP)

Section 9-05.23(1) is a new section as follows:

Dual wall HDPE storm sewer pipe shall meet the requirements of ASTM F2648.

9-05.15 Metal Castings

9-05.15(4) Heavy Duty Hinged Style Ductile Iron Frame and Cover
(December 2, 2019 CFW GSP)

Section 9-05.15(4) is a new section:

Heavy-Duty Hinged Style Frame & Cover shall be ERGO Assembly: Product Number 00104040L01, Manufactured by EJ Group, Inc., 301 Spring Street, PO Box 439, East Jordan, MI 49727, (800)626-4653, www.ejco.com

9-05.15(5) High Impact Multi-Purpose Rubber Composite Adjustment Risers
(December 2, 2019 CFW GSP)

Section 9-05.15(5) is a new section:

Risers shall be minimum 80% by weight recycled rubber and minimum 10% by volume recycled RFL fiber. Adjustment risers shall be of uniform quality and free from cracks, holes, and any other surface defects. Adjustment risers shall be designed for heavy duty street traffic and shall meet or exceed minimum load capacity requirements of AASHTO. Adjustment risers shall be installed as a single unit and shall not be cut into pieces or used as shims. Manufacturer certification shall be furnished upon request stating that the product meets the requirements of this specification. Risers shall be available in standard thicknesses from 1/2-inch to 3-inches; available flat or tapered; and in round, square, and rectangular shapes.

High Impact Adjustment Riser shall be Infra-Riser Multi-Purpose Rubber Composite Adjustment Riser, EJ Group, Inc., 301 Spring Street, PO Box 439, East Jordan, MI, 49727, (800)626-4653, www.ejco.com

9-14 EROSION CONTROL AND ROADSIDE PLANTING

9-14.1 Materials Submittals and Acceptance
(January 10, 2022, WSDOT GSP, OPT1.2023)

In the table in Section 9-14.1, the row for Compost is revised to read:

9-14.5(8)	Compost	Cert & following information is required to be submitted fourteen days prior to application. a) A copy of the Solid Waste Handling Permit issued to the manufacturer by the Jurisdictional Health Department in accordance with https://apps.leg.wa.gov/WAC/default.aspx?cite=173-350 (Minimum Functions Standards for Solid Waste Handling). b) Compost Test Data submitted on WSDOT Form 220-038 that show the compost complies with the processes, testing, and standards specified in WAC 173-350 and this section. And independent Seal of Testing Assurance (STA) Program certified laboratory shall perform the testing within 90 calendar days of application. c) A copy of the manufacturer's annual Seal of Testing Assurance STA certification as issued by the U.S. Composting Council. d) A sample of the compost approved for use.
-----------	---------	--

		e) A list of feed stocks by volume for each compost type. f) Compliance with the applicable section.
--	--	---

9-14.2 Topsoil

9-14.2(1) Topsoil Type A
(June 12, 2020 CFW GSP)

Section 9-14.2(1) is supplemented with the following:

Topsoil Type A mix shall be 50% pure organic compost and 50% sand or sandy loam. The soil shall be high in organic content and comprised of fully composted and mature organic materials.

No fresh sawdust or other fresh wood by-products shall be added to extend the volume after the composting process.

Chemical and physical characteristics of Topsoil Type A shall comply with the following:

Screen Size	7/16" Maximum
Total Nitrogen	0.25% Minimum
Organic Matter	10% Minimum
pH Range	5.5 to 7.5
Conductivity	5 mmhos/cm Maximum

9-14.3 Seed

(June 12, 2020 CFW GSP)

Section 9-14.3 is supplemented with the following:

The grass seed dealer shall mix the grass seed only. The Contractor shall furnish the Engineer with a dealer's guaranteed statement of the composition, mixture, and the percentage of purity and germination of each variety. Seed shall be applied at manufacturer's recommended rate. Hydroseed shall be composed of the following varieties mixed in the proportions indicated, or approved equal:

SEEDED LAWN MIXTURE			
NAME	BY WEIGHT	% PURITY	% GERMINATION
Tall Fescue / Festuca arundinacea	40%	98%	90%
Creeping Red Fescue / Festuca rubra	25%	98%	90%
Highland Colonial Bentgrass / Agrostis capillaris var. 'Highland'	5%	98%	90%
Perennial Rye / Lolium perenne (blend of two: 'Fiesta II', 'Prelude II', 'Commander')	30%	95%	90%

9-14.4 Fertilizer

(June 12, 2020 CFW GSP)

Section 9-14.4 is supplemented with the following:

Fertilizer for trees shall be biodegradable fertilizer packets, 20-10-5. Apply per manufacturer's recommendations.

9-14.5 Mulch and Amendments

9-14.5(3) Bark or Wood Chips

(June 12, 2020 CFW GSP)

Section 9-14.5(3) is supplemented with the following:

Bark or Wood Chip Mulch shall be medium grade composted ground fir or hemlock bark. The bark shall be uniform in color, free from weed seeds, sawdust and splinters. The moisture content of bagged mulch shall not exceed 22%. The acceptable size range of bark mulch material is ½" to 1" with maximum of 20% passing the ½" screen.

9-14.7 Plant Materials

9-14.7(2) Quality

(June 12, 2020 CFW GSP)

Section 9-14.7(2) is supplemented with the following:

Plant material shall be free from disfiguring knots, swollen grafts, sunscald injuries, bark abrasions, evidence of improper pruning or other objectionable disfigurement.

Potted and container stock shall be well rooted and vigorous enough to ensure survival and healthy growth. Shrubs shall have full foliage (not leggy). Container stock shall be grown in its delivery container for not less than six (6) months, but not for more than two (2) years. Root bound or broken containers will not be accepted. Bare root, liner and root stock with dried or shriveled roots from exposure will not be accepted.

Measurements, caliper, branching, grading, quality, balling and burlapping shall follow the Code of Standards of the American Associate of Nurserymen in the American Standard for Nursery Stock, ANSI 260.1, latest edition. Measurements shall be taken with all branches in their normal growing position. Plants shall not be pruned prior to delivery to site.

9-14.7(3) Handling and Shipping

(June 12, 2020 CFW GSP)

Section 9-14.7(3) is supplemented with the following:

Tie back branches as necessary, and protect bark from chafing with burlap bags. Do not drag Plant materials along ground without proper protection of roots and branches. Protect rootballs from environmental or mechanical damage and water as necessary to keep roots moist. Do not store Plants for more than one week.

9-14.7(4) Sod

(June 12, 2020 CFW GSP)

Section 9-14.7(4) is supplemented with the following:

Sod Lawn shall be three-way Tall Fescue Blend Sod, 33.33% Firecracker LS Tall Fescue, 33.33% Spyder LS Tall Fescue, 33.33% Raptor II Tall Fescue with degradable netting, or approved equal.

9-14.7(5) Tagging

(June 12, 2020 CFW GSP)

Section 9-14.7(5) is a new section:

All Plant material shall be legibly tagged. Tagging may be by species or variety with minimum of one tag per ten trees, shrubs, or vines. Remove all tagging prior to final acceptance.

9-14.7(6) Inspection

(June 12, 2020 CFW GSP)

Section 9-14.7(6) is a new section:

The Contracting Agency shall reserve the option of selecting and inspecting Plant material at the nursery. The contractor shall provide the Contracting Agency with at least one week notice prior to preparing Plants for shipping and delivery. The Contractor shall neither deliver to site nor install Plant materials until authorized by the Contracting Agency.

9-14.7(7) Temporary Storage

(June 12, 2020 CFW GSP)

Section 9-14.7(7) is a new section:

Cold storage of Plants shall not be permitted.

If Planting is delayed more than 24 hours after delivery, set balled and burlapped Plants on the ground, well protected with soil or wet peat. Adequately cover all roots of bare root material with soil or wet peat. Protect rootballs from freezing, sun, drying winds or mechanical damage. Water Plant material as necessary until Planted.

Plants shall not be stored for more than one week. Longer storage period at project site will result in rejection of Plant materials by the Contracting Agency.

9-14.8 Stakes, Guys, and Wrapping

(June 12, 2020 CFW GSP)

Section 9-14.8 is supplemented with the following:

Stakes shall be BVC round tree stakes with Chainlock guying or Engineer accepted product. No wrapping required.

9-14.9 Root Barrier

(June 12, 2020 CFW GSP)

Add the following new section:

Root Barrier shall be 18-inch high, minimum thickness 0.090-inch, interlocking root barrier panels constructed of high-impact polypropylene with 1/2-inch reinforcing ribs.

9-17 FLEXIBLE GUIDE POSTS

9-17.1 General

(September 20, 2024 CFW GSP)

Section 9-17.1 is supplemented with the following:

Flexible guide post curb bases shall be NCHRP 350 and MASH 2009 compliant and shall be designed for use in traffic. Curb bases shall be yellow or white, to match the channelization color, and use a quick-release style base. Curb caps/nosing will be required for both sides of each delineator location, if the curb base is greater than 2 inches high.

The delineators used with the curb base shall be 3 inches in diameter, white with white sheeting, and tubular type.

9-15 IRRIGATION SYSTEM

9-15.1 Pipe, Tubing And Fittings

(June 12, 2020 CFW GSP)

Section 9-15.1 is replaced with the following:

All pipe and tubing shall be PVC or approved equal. All fittings shall be Sch 80 PVC. All pipe for the main, laterals, and sleeving shall be Sch 40 PVC.

9-15.5 Valve Boxes

(June 12, 2020 CFW GSP)

Section 9-15.5 is supplemented with the following:

Valve boxes for control valves shall be grey flared box, HDPE construction with UV inhibitors, heavy duty seat collar, drop in locking, 17”L x 24” D x 12” W with green HDPE drop in locking lid.

Valve boxes for Double Check Valve Assembly shall be grey heavy duty polymer concrete, top dimensions 25”L x 15-16”W and 24” D designed to withstand H-10 and H-20 loading in incidental and non-deliberate traffic areas. Valve box must be compliant with AASHTO H-10 Design Load; ASTM C 857-95 Design Load of A-8, 8,000lbs. Box shall be alkaline, acid and weather resistant, with flush locking polymer concrete cover. Verify size to fit Double Check Valve Assembly.

Valve boxes for quick coupler shall be light duty HDPE with UV inhibitors, 10” diameter flared box with bolt down cover.

9-15.6 Gate Valves

(April 12, 2018 CFW GSP)

Section 9-15.6 is supplemented with the following:

Gate valves shall be heavy duty cast brass body and heavy cast iron handwheel, suitable for residential or commercial potable water applications, with screwed bonnet, non-rising stem, solid wedge disc and integral seats.

9-15.7 Control Valves

9-15.7(1) Manual Control Valves

(April 12, 2018 CFW GSP)

Section 9-15.7(1) is supplemented with the following:

Shut off valves upstream of automatic control valves shall be a heavy duty cast brass body gate valve with heavy cast iron handwheel, suitable for residential or commercial potable water applications, with screwed bonnet, non-rising stem, solid wedge disc and integral seats, size to fit line.

9-15.13 Pressure Regulating Valves

(April 12, 2018 CFW GSP)

Section 9-15.13 is supplemented with the following:

Pressure regulating valve shall be designed to reduce incoming water pressure from up to 400psi to a range of 25-75psi. Valve shall be all bronze body construction, with thermal expansion bypass, serviceable in line, with internal stainless steel strainer.

9-19 DETECTABLE WARNING SURFACE

9-19.2 Cast-in-Place Detectable Warning Surface

9-19.2(1) General Requirements

(October 3, 2022 WSDOT GSP, OPTION 1)

The first paragraph of Section 9-19.2(1) is revised to read:

The color of detectable warning surfaces shall be yellow and shall match SAE AMS Standard 595, color number 33538 unless otherwise shown on the plans. When used in areas between ramps to differentiate between travel paths, detectable warning surfaces shall be black.

Units shall provide the required contrast (light-on-dark or dark-on-light) with the adjacent curb ramp or other applicable walkway.

9-28 SIGNING MATERIALS AND FABRICATION

9-28.1 General

(September 20, 2024 CFW GSP)

Paragraph three is deleted and replaced with the following:

All regulatory (R series), school (S series), and warning (W and X series) signs, except for parking regulation, parking prohibition signing and signs of fluorescent yellow-green color shall be constructed with Type III or Type IV Glass Bead Retroreflective Element Material sheeting in accordance with Section 9-28.12. All street name (D-3) sign sheeting shall meet this specification. The reflectivity standard of supplemental plaques shall match that of the primary sign.

All overhead signing shall meet the specifications of Type IX sheeting, 3M 3990 series or approved equal. This sheeting has a retroreflection rating of 300 candelas per foot candle per square foot of material for white sheeting (250 for yellow sheeting) with an entrance angle of minus 5 degrees. This standard applies to all signs mounted above the roadway, on span wires, or on traffic signal standard mast arms.

All pedestrian / non-motorized-related warning signs (W-series) and all school warning signs (S-series) shall be of fluorescent yellow-green color and shall meet the specifications of Type IX sheeting, 3M 3983, or approved equivalent. This sheeting has a retroreflection rating of 325 candelas per foot candle per square foot of material for fluorescent yellow-green sheeting with an observation angle of 0.2 degrees and an entrance angle of minus 4 degrees. The reflectivity standard of supplemental plaques shall match that of the primary sign.

Motorist information and parking signing shall be constructed with Type I Glass Bead Retroreflective Element Material sheeting in accordance with Section 9-28.12. The reflectivity standard of supplemental plaques shall match that of the primary sign.

9-28.2 Manufacturer's Identification and Date

(October 23, 2014 CFW GSP)

Section 9-28.2 is deleted and replaced with the following:

All signs shall show the manufacturer's name and date of manufacture on the back.

9-28.8 Sheet Aluminum Signs

(September 20, 2024 CFW GSP)

Section 9-28.8 table is deleted and replaced with the following:

Sign sheet thickness and material shall be in accordance with City of Federal Way Standard Details.

9-28.9 Fiberglass Reinforced Plastic Signs

(December 18, 2009 CFW GSP)

Section 9-28.9 is deleted in its entirety.

9-28.12 Reflective Sheeting

(September 20, 2024 CFW GSP)

Section 9-28.12 is replaced with the following:

Reflective sheeting material shall conform to ASTM D4956 – *Standard Specification for Retroreflective Sheeting for Traffic Control*. The following standard reflective sheeting types have been modified to reflect City of Federal Way requirements:

Device Type	Use	Sheeting Color	Allowable Sheeting Types
Permanent Signs			
Permanent Signing	All	All	IV ¹
Object Markers	All	All	IV
Temporary Construction Signing			
Warning Signs	All	Fluorescent Orange	VIII, IX, X ² , XI
Regulatory Signs	All	White	IV
Regulatory Signs	Rural	White	II ³ , IV
Regulatory Signs	Urban/Rural	White	III ³ , IV
Regulatory Signs	All	Red	III, IV
Regulatory Signs	All	Green	II, IV
Regulatory Letters, Border or Symbols		Green	III ³ , IV ³
Temporary Construction Signs	All	All Other Background Colors	III ³ , IV
Other Devices			
Barricades	All	White or Orange	III ³ , IV
Barrier Delineators	All	White or Yellow	III, IV, V, XI
Bollards	All	All	IV
Flexible Guidepost	All	All	III, IV, V
Pedestrian Channelization Devices	All	White or Orange	III ³ , IV
Signal Backplates	Portable Signals		IV
Signal Backplates	Permanent Signals		See Section 9-29.16
Tall Channelization Devices 42-inch	All	Fluorescent Orange/White	III ⁴ , IV ⁴ , VIII, IX, XI ⁴
Traffic Cones 28- and 36-inch	All	White or Higher White	III ³ , IV
Traffic Safety Drums	All	Fluorescent Orange/White	III ⁴ , IV ⁴ , VIII, IX, XI ⁴
Transportable Attenuators	All	Yellow and Black Chevron	III ³ , IV
Transportable Attenuators	All	White and Red Chevron	IV

Utilities attached to Bridges	All		I, See Section 6-01.10
-------------------------------	-----	--	------------------------

Notes:

1. Except S Series signs with fluorescent yellow-green sheeting shall use Type IX. Overhead signs shall use Type IX.
2. Former Type X, not shown in ASTM D4956, however meets requirements of Types VII, IX and XI.
3. Only devices in inventory may be used, new fabrication shall use Type IV.
4. Type III and Type IV orange and white sheeting may be still used through December 31, 2026.

9-28.14 Sign Support Structures
(September 20, 2024 CFW GSP)

Section 9-28.14 is supplemented with the following:

Unless otherwise noted in the Plans or approved by the Engineer, all sign posts shall be steel sign posts. Sign post sizes will be shown on Plans or shall be sized in accordance with the WSDOT Design Manual. Sign supports (foundations) shall be in accordance with City of Federal Way Standard Details.

9-29.2(4) Cover Markings
(September 20, 2024 CFW GSP)

Section 9-29.2(4) is supplemented with the following:

Cover markings for cable vaults containing fiber optic cable or installed for future fiber optic cable shall be "TS", unless otherwise noted in the Plans.

9-34 PAVEMENT MARKING MATERIAL

9-34.2 Paint

9-34.2(5) Low VOC Waterborne Paint
(December 16, 2022 CFW GSP)

Section 9-34.2(5) is replaced with the following:

The City of Federal Way does not allow Low VOC Waterborne Paint.

9-34.3 Plastic

9-34.3(4) Type D – Liquid Cold Applied Methyl Methacrylate
(March 13, 2012 CFW GSP)

Section 9-34.3(4) is supplemented with the following:

The methyl methacrylate (MMA) material shall be formulated as a long-life durable pavement marking system capable of providing a minimum of two years of continuous performance. The material shall be a catalyzed methyl methacrylate (MMA), wet-continuous reflective product and placed shall have a dry time (cure) to the touch of no more than 30 minutes. The material shall be capable of retaining reflective glass beads and ceramic micro-crystalline elements of the drop-on or spray-on type as specified by the manufacturer. The binder shall be lead free and suitable for bituminous and concrete pavements.

9-34.4 Glass Beads for Pavement Marking Materials
(September 20, 2024 CFW GSP)

Section 9-34.4 is supplemented with the following:

Methyl Methacrylate Pavement Markings Optics

Both glass beads and reflective elements are required for MMA application, unless otherwise noted.

Glass Beads

Surface-drop glass beads shall be the Swarco SwarcoFlex bead that has a Methacrylate compatible coupling agent approved by the material manufacturer.

Glass beads shall be applied at a rate of 8 to 10 pounds per one hundred square feet.

Reflective Elements

Surface-drop ceramic elements shall be 3M Series 50M or 70M with a methacrylate-compatible coupling agent approved by the material manufacturer. Elements shall meet or exceed a minimum initial coefficients of retroreflected luminance value of 200 mcd/m²/lx for white and 150 mcd/m²/lx for yellow in accordance with ASTM E2832.

The reflective elements shall contain either clear or yellow tinted microcrystalline ceramic beads bonded to the opacified core. These elements shall not be manufactured using lead, chromate or arsenic. All “dry-performing” microcrystalline ceramic beads bonded to the core shall have a minimum index of refraction of 1.89 when tested using the liquid oil immersion method. All “wet performing” microcrystalline ceramic beads bonded to the core shall have a minimum index of refraction of 2.40 when tested using the liquid oil immersion method. The test method is described in ASTM E1967-98.

The gradation for the reflective elements shall be as follows:

US Mesh	Micron	Standard Elements
10	2000	95-100
14	1410	0-40
20	850	0-7

A sample of reflective elements supplied by the manufacturer shall show resistance to corrosion of their surface after exposure to a 1% solution (by weight) of sulfuric acid for 24 hours. After testing, no more than 15% of beads shall show a distinct opaque surface upon microscopic examination after the test.

The reflective elements are surface treated to optimize embedment and adhesion to the MMA binder. Elements treated for use with MMA shall have identification on packaging or label to indicate use with the MMA binder.

Reflectance

Typical initial retroreflectivity values are shown in the table below. Typical retroreflectivity is averaged over many readings. Minimum retroreflectivity results represent average performance for smooth pavement surfaces. Results may vary due to differences in pavement type and surface roughness. Increased element drop rate may be necessary to compensate for increased surface area characteristic of rough pavement surfaces.

Minimum Initial Retroreflectivity Values
--

	White	Yellow
Dry (ASTM E1710)	700	525
Wet recovery (ASTM E2177)	275	225
Wet continuous (ASTM E2176)	200	150

9-35 TEMPORARY TRAFFIC CONTROL MATERIALS

9-35.5 Portable Changeable Message Signs

(January 10, 2022, WSDOT GSP, Option 1.2023)

Section 9-35.5 is revised to read:

PCMS, mPCMS, and truck mounted PCMS shall meet the requirements of the MUTCD and the following general requirements:

1. Use light emitting diode (LED) technology capable of emitting a yellow or amber image when displayed with a flat black image matching the background when not activated.
2. Be capable of displaying 3 lines of at least 8 alphanumeric characters with a minimum of one pixel separation between each line.
3. Be capable of displaying 2 phases of messages at 2.0 second display each in addition to 3 phases of messages at 1.5 second display each.
4. PCMS characters shall be at least 18 inches in height.
5. mPCMS characters shall be at least 12 inches in height.
6. Truck-mounted PCMS characters shall be at least 10 inches in height.
7. The sign display shall be covered by a stable, impact resistant polycarbonate face. The sign face shall be non-glare from all angles and shall not degrade due to exposure to ultraviolet light.
8. Be capable of simultaneously activating all pixels for the purpose of pixel diagnostics. This feature shall not occur when the sign is displaying an active message.
9. The light source shall be energized only when the sign is displaying an active message.
10. Primary source of power shall be solar power with a battery backup to provide continuous operation when failure of the primary power source occurs.
11. The sign controller software shall be NTCIP compliant.

The PCMS panels and related equipment shall be permanently mounted on a trailer or truck with all needed controls and power generating equipment.

Standard Plans

(September 3, 2024 WSDOT)

The State of Washington Standard Plans for Road, Bridge and Municipal Construction M21-01, effective October 23, 2023, is made a part of this contract.

The Standard Plans are revised as follows:

A-10.30

RISER RING detail (Including SECTION view and RISER RING DIMENSIONS table): The RISER RING detail is deleted from the plan.

INSTALLATION detail, SECTION A: The "1/4" callout is revised to read "+/- 1/4" (SEE CONTRACT ~ Note: The + 1/4" installation is shown in the Section A view)"

A-40.20

Sheet 1, NOTES 1, 2, 3, and 4 are replaced with the following:

- (1) Use the 1/2 inch joint details for bridges with expansion length less than 100 feet and for bridges with L type abutments. Use the 1 inch joint details for other applications.
- (2) Use detail 5, 6, 7 on steel trusses and timber bridges with concrete bridge deck panels.
- (3) For details 1, 2, 3, and 4, the item "HMA Joint Seal at Bridge End" shall be used for payment. For details 5 and 6, the item "HMA Joint Seal at Bridge Deck Panel Joint" shall be used for payment. For detail 7, the item "Clean and Seal Bridge Deck Panel Joint" shall be used for payment.

Sheet 2, Detail 8 reference to "6-09.3(6)" is revised to read "6-21.3(7)".

A-50.40

Sheet 1, Plan View: The callout "BEAM GUARDRAIL TYPE 31 TRANSITION SECTION TYPE 21 OR TYPE 24 (SEE STANDARD PLAN C-25.20 OR C-25.30)" is revised to read "BEAM GUARDRAIL TYPE 31 TRANSITION SECTION TYPE 21, 24, OR 25 (SEE STANDARD PLAN C-25.20, C-25.30, OR C-25.32)"

A-60.40

Note 2 reference to "6-09.3(6)" is revised to read "6-21.3(7)".

B-90.40

Valve Detail – DELETED

C-2c

DELETED

C-4f

DELETED

C-20.42

DELETED

C-23.70

Sheet 2, ANCHOR BRACKET ASSEMBLY DETAIL, dimension, "R. 5/16" is revised to read; R. 15/16"

ANCHOR PLATE DETAIL, weld callout (fillet), 1/4" is revised to read; 3/16"

C-81.15

Sheet 1, General Notes, Add Note 7, to read; “7. The concrete class for the moment slab shall be class 4000 typically and class 4000A when the top of the slab is used as the roadway, or sidewalk, surface. The concrete class for the barrier is defined in Standard Specification Section 6-10.3.”

C-85.11

On Section B, the callout “3” EXPANDED POLYSTYRENE AROUND COLUMN (TYP.)” is revised to read “3” POLYSTYRENE OR POLYETHYLENE FOAM AROUND COLUMN (TYP.)”

D-3.09

Sheet 1, Geosynthetic Wall with 2 FT Traffic Surcharge detail, callout – “BARRIER ON WALL ~ SEE Standard Plan D-3.15 or D-3.16” is revised to read: “BARRIER ON WALL ~ SEE Standard Plan C-81.10 and/or C-81.15”

D-3.10

Sheet 1, Typical Section, callout – “FOR WALLS WITH SINGLE SLOPE TRAFFIC BARRIER. USE THE DETAILS ABOVE THE MATCH LINE ON STANDARD PLAN D-3.15” is revised to read; “FOR WALLS WITH SINGLE SLOPE TRAFFIC BARRIER, SEE CONTRACT PLANS”

Sheet 1, Typical Section, callout – “FOR WALLS WITH F-SHAPE TRAFFIC BARRIER. USE THE DETAILS ABOVE THE MATCH LINE ON STANDARD PLAN D-3.16” is revised to read; “FOR THE WALLS WITH F-SHAPE TRAFFIC BARRIER, SEE CONTRACT PLANS”

D-3.11

Sheet 1, Typical Section, callout – “”B” BRIDGE APPROACH SLAB (SEE BRIDGE PLANS) OR PERMANENT GEOSYNTHETIC WALL BARRIER ~ SEE STANDARD PLANS D-3.15 OR D-3.16” is revised to read; “B” BARRIER APPROACH SLAB OR MOMENT SLAB (SEE CONTRACT PLANS)

Sheet 1, Typical Section, callout – “TYPICAL BARRIER ON BRIDGE APPROACH SLAB (SEE BRIDGE PLANS) OR PERMANENT GEOSYNTHETIC WALL BARRIER ~ SEE STANDARD PLANS D-3.15 OR D-3.16” is revised to read; “TYPICAL BARRIER ON BRIDGE APPROACH SLAP OR MOMENT SLAB (SEE CONTRACT PLANS)

D-10.10

Note 7, “If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30” is revised to read “Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 1 and 1SW”.

D-10.15

Note 7, “If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30” is revised to read “Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 2 and 2SW”.

D-10.30

Wall Type 5 may be used in all cases.

D-10.35

Wall Type 6 may be used in all cases.

D-10.40

Note 5, "If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30" is revised to read "Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 7".

D-10.45

Note 5, "If Traffic Barriers are required, See Standard Plans D-15.10, D-15.20 and D-15.30" is revised to read "Traffic Barriers shall not be structurally connected to the Reinforced Concrete Retaining Wall Type 8".

F-10.18

General Note 1; "Construct curb joints at concrete pavement transverse joint locations. If all adjacent pavement is HMA, see Standard Plan F-30.10 for Curb Expansion and Contraction Joint Spacing." Is revised to read – "See Standard Plan F-30.10 and Standard Specification Section 8-04.3 for Curb Expansion and Contraction Joint details and spacing."

F-30.10

All five instances of the "2.0% MAX." are replaced with "2.1% MAX."

F-40.12

The one instance of "2.0% MAX." is replaced with "2.1% MAX."

Note 7 is replaced with the following:

7.The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement. When a ramp is constructed on a radius, the Curb Ramp length is measured on the inside radius along the back of the walkway.

Section B is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

Section C is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

F-40.14

The one instance of "2.0% MAX." is replaced with "2.1% MAX."

Note 7 is replaced with the following:

7.The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement. When a ramp is constructed on a radius, the Curb Ramp length is measured on the inside radius along the back of the walkway.

Section A is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

Section C is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

F-40.15

The one instance of "2.0% MAX." is replaced with "2.1% MAX."

Note 7 is replaced with the following:

7.The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement.

Section A is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

F-40.16

The one instance of "2.0% MAX." is replaced with "2.1% MAX."

Note 8 is replaced with the following:

7.The running slope of curb ramps shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the landing. Do not include the abutting landing in the Curb Ramp length measurement.

Section A is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

Section B is amended as follows:

Delete: "15'-0" MAX. (TYP.)"

F-80.10

The one instance of "2.0% MAX." is replaced with "2.1% MAX."

Note 6 is replaced with the following:

The running slope of the Pedestrian Ramp shall not exceed 8.3% maximum except as noted herein. If the 8.3% running slope creates a ramp that exceeds 15ft, see contract plans for details. Use a single constant slope from bottom of ramp to top of ramp to match into the sidewalk.

Section A is amended as follows:

Delete: "15" Max."

J-10.10

Sheet 4 of 6, "Foundation Size Reference Table", PAD WIDTH column, Type 33xD=6' – 3" is revised to read: 7' – 3". Type 342LX / NEMA P44=5' – 10" is revised to read: 6' – 10"
Sheet 5 of 6, Plan View, "FOR EXAMPLE PAD SHOWN HERE:", "first bullet" item, "-SPACE BETWEEN TYPE B MOD. CABINET AND 33x CABINET IS 6" (IN)" IS REVISED TO READ: "SPACE BETWEEN TYPE B MOD. CABINET (BACK OF ALL CHANNEL STEEL) AND 33x CABINET IS 6" (IN) (CHANNEL STEEL ADDS ABOUT 5" (IN))"

J-10.16

Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

J-10.17

Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

J-10.18

Key Note 1, Standard Plan J-10.30 revised to Standard Plan J-10.14

J-20.26

Add Note 1, "1. One accessible pedestrian pushbutton station per pedestrian pushbutton post."

Add General Note 2, to read: "Signs shown are for locations with pedestrian signal displays (Accessible Pedestrian Signals/APS). Accessible information device (AID) pushbuttons signs not shown."

Revise View Titles (Both Sheets) to read: "ACCESSIBLE PEDESTRIAN PUSHBUTTON ASSEMBLY"

J-20.16

View A, callout, was – LOCK NIPPLE, is revised to read; CHASE NIPPLE

J-21.10

Sheet 1, Anchor Bolt Template, callout; "9" (IN) BOLT CIRCLE" is revised to read: "9" (IN) DIA. BOLT CIRCLE"

Base Plate Detail, callout; "3/4" (IN) STEEL PLATE WITH HOLE = POLE BASE + 1/6" (IN)" IS REVISED TO READ; "3/4" (IN) STEEL PLATE WITH HOLE = POLE BASE + 1/16" (IN)"

Flat Foundation Detail – Elevation, callout; "ANCHOR BOLTS ~ 3/4" (IN) x 30" (IN) FULL THREAD ~ THREE REQ'D. PER ASSEMBLY" is revised to read; "ANCHOR BOLTS ~ 3/4" (IN) x 30" (IN) FULL THREAD ~ FOUR REQ'D PER ASSEMBLY"

Flat Foundation Detail – Elevation, dimension; 4'-0" is revised to read; "4'-0" ROUND OR 3'-0" SQUARE"

J-21.15

Partial View, callout, was – LOCK NIPPLE ~ 1 1/2" DIAM., is revised to read; CHASE NIPPLE ~ 1 1/2" (IN) DIAM.

J-40.10

Sheet 2 of 2, Detail F, callout, "12 – 13 x 1 1/2" S.S. PENTA HEAD BOLT AND 12" S. S. FLAT WASHER" is revised to read; "12 – 13 x 1 1/2" S.S. PENTA HEAD BOLT AND 1/2" (IN) S. S. FLAT WASHER"

J-40.36

Note 1, second sentence: "Finish shall be # 2B for backbox and # 4 for the cover." Is revised to read: "Finish shall be # 2B for barrier box and HRAP (Hot Rolled Annealed and Pickled) for the cover.

J-40.37

Note 1, second sentence: "Finish shall be # 2B for backbox and # 4 for the cover." Is revised to read: "Finish shall be # 2B for barrier box and HRAP (Hot Rolled Annealed and Pickled) for the cover.

J-75.20

Key Notes, note 16, second bullet point, was: "1/2" (IN) x 0.45" (IN) Stainless Steel Bands", add the following to the end of the note: "Alternate: Stainless steel cable with stainless steel ends, nuts, bolts, and washers may be used in place of stainless steel bands and associated hardware."

J-75.55

Notes, Note A1, Revise reference, was – G-90.29, should be -G-90.20.

M-40.10

Guide Post Type ~ Reflective Sheeting Applications Table, remove reference – “(SEE NOTE 5)”

The following are the Standard Plan numbers applicable at the time this project was advertised. The date shown with each plan number is the publication approval date shown in the lower right-hand corner of that plan. Standard Plans showing different dates shall not be used in this contract.

A-10.10-00.....8/7/07	A-30.35-00.....10/12/07	A-50.10-02.....7/18/24
A-10.20-00.....10/5/07	A-40.00-01.....7/6/22	A-50.40-01.....8/17/21
A-10.30-00.....10/5/07	A-40.10-04.....7/31/19	A-60.10-03.....12/23/14
A-20.10-00.....8/31/07	A-40.15-00.....8/11/09	A-60.20-03.....12/23/14
A-30.10-00.....11/8/07	A-40.20-04.....1/18/17	A-60.30-01.....6/28/18
A-30.30-01.....6/16/11	A-40.50-03.....9/12/23	A-60.40-00.....8/31/07
B-5.20-03.....9/9/20	B-30.50-03.....2/27/18	B-75.20-03.....8/17/21
B-5.40-02.....1/26/17	B-30.60-00.....9/9/20	B-75.50-02.....3/15/22
B-5.60-02.....1/26/17	B-30.70-04.....2/27/18	B-75.60-01.....1/26/17
B-10.20-03.....8/23/23	B-30.80-01.....2/27/18	B-80.20-00.....6/8/06
B-10.40-02.....8/17/21	B-30.90-02.....1/26/17	B-80.40-00.....6/1/06
B-10.70-03.....8/23/23	B-35.20-00.....6/8/06	B-85.10-01.....6/10/08
B-15.20-01.....2/7/12	B-35.40-01.....8/23/23	B-85.20-00.....6/1/06
B-15.40-01.....2/7/12	B-40.20-00.....6/1/06	B-85.30-00.....6/1/06
B-15.60-02.....1/26/17	B-40.40-02.....1/26/17	B-85.40-00.....6/8/06
B-20.20-02.....3/16/12	B-45.20-01.....7/11/17	B-85.50-01.....6/10/08
B-20.40-04.....2/27/18	B-45.40-01.....7/21/17	B-90.10-00.....6/8/06
B-20.60-03.....3/15/12	B-50.20-00.....6/1/06	B-90.20-00.....6/8/06
B-25.20-02.....2/27/18	B-55.20-03.....8/17/21	B-90.30-00.....6/8/06
B-25.60-03.....8/23/23	B-60.20-02.....9/9/20	B-90.40-01.....1/26/17
B-30.05-00.....9/9/20	B-60.40-01.....2/27/18	B-90.50-00.....6/8/06
B-30.10-03.....2/27/18	B-65.20-01.....4/26/12	B-95.20-02.....8/17/21
B-30.15-00.....2/27/18	B-65.40-00.....6/1/06	B-95.40-01.....6/28/18
B-30.20-04.....2/27/18	B-70.20-00.....3/15/22	
B-30.30-03.....2/27/18	B-70.60-01.....1/26/17	
C-1.....9/8/22	C-23.70-01.....10/16/23	C-70.15-01.....7/21/24
C-1b.....10/12/23	C.24.10-05.....7/21/24	C-70.10-04.....10/16/23
C-1d.....10/31/03	C-24.15-00.....3/15/22	C-75.10-02.....9/16/20
C-6a.....9/8/22	C-25.20-07.....8/20/21	C-75.20-03.....8/20/21
C-7.....9/8/22	C-25.22-06.....8/20/21	C-75.30-03.....8/20/21
C-7a.....9/8/22	C-25.26-05.....8/20/21	C-80.10-03.....10/16/23
C-20.10-09.....10/12/23	C-25.30-01.....8/20/21	C-80.20-01.....6/11/14
C-20.14-05.....9/8/22	C-25.32-00.....7/29/24	C-80.30-02.....8/20/21
C-20.15-03.....10/12/23	C-25.80-05.....8/12/19	C-80.40-01.....6/11/14
C-20.18-04.....9/8/22	C-60.10-04.....7/21/24	C-85.10-00.....4/8/12
C-20.40-10.....10/12/23	C-60.15-01.....7/21/24	C-85.11-01.....9/16/20
C-20.41-05.....7/18/24	C-60.20-01.....9/8/22	C-85.15-03.....10/17/23
C-20.43-01.....7/18/24	C-60.30-02.....7/21/24	C-85.18-03.....9/8/22
C-20.44-00.....8/13/24	C-60.40-01.....7/21/24	C-81.10-00.....9/12/23

C-20.45-03.....9/8/22	C-60.45-01.....7/21/24	C-81.15-00.....9/12/23
C-20.55-00.....7/30/24	C-60.50-01.....7/21/24	
C-22.16-08.....10/17/23	C-60.60-01.....7/21/24	
C-22.40-11.....7/21/24	C-60.70-01.....9/8/22	
C-22.45-07.....7/21/24	C-60.80-02.....7/21/24	
D-2.36-03.....6/11/14	D-4.....12/11/98	D-10.35-00.....7/8/08
D-2.46-02.....8/13/21	D-6.....6/19/98	D-10.40-01.....12/2/08
D-2.84-00.....11/10/05	D-10.10-01.....12/2/08	D-10.45-01.....12/2/08
D-2.92-01.....4/26/22	D-10.15-01.....12/2/08	D-20.10-00.....10/9/23
D-3.09-00.....5/17/12	D-10.20-01.....8/7/19	
D-3.10-01.....5/29/13	D-10.25-01.....8/7/19	
D-3.11-03.....6/11/14	D-10.30-00.....7/8/08	
E-1.....2/21/07	E-4.....8/27/03	E-20.10-00.....9/12/23
E-2.....5/29/98	E-4a.....8/27/03	E-20.20-00.....10/4/23
F-10.12-04.....9/24/20	F-10.62-02.....4/22/14	F-40.15-04.....9/25/20
F-10.16-00.....12/20/06	F-10.64-03.....4/22/14	F-40.16-03.....6/29/16
F-10.18-04.....6/28/24	F-30.10-04.....9/25/20	F-45.10-05.....6/4/24
F-10.40-04.....9/24/20	F-40.12-03.....6/29/16	F-80.10-04.....7/15/16
F-10.42-00.....1/23/07	F-40.14-03.....6/29/16	
G-10.10-00.....9/20/07	G-26.10-00.....7/31/19	
G-20.10-03.....8/20/21	G-30.10-04.....6/23/15	
G-22.10-04.....6/28/18	G-50.10-03.....6/28/18	
G-24.10-00.....11/8/07	G-90.10-03.....7/11/17	
G-24.20-01.....2/7/12	G-90.20-05.....7/11/17	
G-24.30-02.....6/28/18	G-90.30-04.....7/11/17	
G-24.40-07.....6/28/18	G-95.10-02.....6/28/18	
G-24.50-05.....8/7/19	G-95.20-03.....6/28/18	
G-24.60-05.....6/28/18	G-95.30-03.....6/28/18	
G-25.10-05.....9/16/20		
H-10.10-01.....6/2/24	H-30.10-00.....10/12/07	H-70.10-02.....8/17/21
H-10.11-00.....6/2/24	H-32.10-00.....9/20/07	H-70.20-02.....8/17/21
H-10.15-01.....6/2/24	H-60.10-01.....7/3/08	
H-10.16-00.....6/2/24	H-60.20-01.....7/3/08	
I-10.10-01.....8/11/09	I-30.20-00.....9/20/07	I-40.20-00.....9/20/07
I-30.10-02.....3/22/13	I-30.30-02.....6/12/19	I-50.20-01.....6/10/13
I-30.15-02.....3/22/13	I-30.40-02.....6/12/19	I-60.10-01.....6/10/13
I-30.16-01.....7/11/19	I-30.60-02.....6/12/19	I-60.20-01.....6/10/13
I-30.17-01.....6/12/19	I-40.10-00.....9/20/07	I-80.10-02.....7/15/16
J-05.50-00.....8/30/22	J-26.10-03.....7/21/16	J-50.05-00.....7/21/17
J-10.....7/18/97	J-26.15-01.....5/17/12	J-50.10-01.....7/31/19
J-10.10-04.....9/16/20	J-26.20-01.....6/28/18	J-50.11-02.....7/31/19
J-10.12-00.....9/16/20	J-27.10-01.....7/21/16	J-50.12-02.....8/7/19
J-10.14-00.....9/16/20	J-27.15-00.....3/15/12	J-50.13-01.....8/30/22
J-10.15-01.....6/11/14	J-28.01-00.....8/30/22	J-50.15-01.....7/21/17



J-10.16-02.....	8/18/21	J-28.10-02.....	8/7/19	J-50.16-01.....	3/22/13
J-10.17-02.....	8/18/21	J-28.22-00.....	8/07/07	J-50.18-00.....	8/7/19
J-10.18-02.....	8/18/21	J-28.24-02.....	9/16/20	J-50.19-00.....	8/7/19
J-10.20-04.....	8/18/21	J-28.26-01.....	12/02/08	J-50.20-00.....	6/3/11
J-10.21-02.....	8/18/21	J-28.30-04.....	6/18/24	J-50.25-00.....	6/3/11
J-10.22-03.....	10/4/23	J-28.40-02.....	6/11/14	J-50.30-00.....	6/3/11
J-10.25-01.....	6/21/24	J-28.42-01.....	6/11/14	J-60.05-01.....	7/21/16
J-10.26-00.....	8/30/22	J-28.43-01.....	6/28/18	J-60.11-00.....	5/20/13
J-12.15-00.....	6/28/18	J-28.45-03.....	7/21/16	J-60.12-00.....	5/20/13
J-12.16-00.....	6/28/18	J-28.50-03.....	7/21/16	J-60.13-00.....	6/16/10
J-15.10-01.....	6/11/14	J-28.60-03.....	8/27/21	J-60.14-01.....	7/31/19
J-15.15-02.....	7/10/15	J-28.70-04.....	8/30/22	J-75.10-02.....	7/10/15
J-20.01-01.....	6/21/24	J-29.10-02.....	8/26/22	J-75.20-01.....	7/10/15
J-20.05-00.....	6/21/24	J-29.15-01.....	7/21/16	J-75.30-02.....	7/10/15
J-20.10-05.....	10/4/23	J-29.16-02.....	7/21/16	J-75.50-00.....	8/30/22
J-20.11-03.....	7/31/19	J-30.10-01.....	8/26/22	J-75.55-00.....	8/30/22
J-20.15-04.....	6/21/24	J-40.01-00.....	8/30/22	J-80.05-00.....	8/30/22
J-20.16-02.....	6/30/14	J-40.05-00.....	7/21/16	J-80.10-01.....	8/18/21
J-20.20-02.....	5/20/13	J-40.10-04.....	4/28/16	J-80.12-00.....	8/18/21
J-20.26-01.....	7/12/12	J-40.20-03.....	4/28/16	J-80.15-00.....	6/28/18
J-21.10-05.....	6/21/24	J-40.30-04.....	4/28/16	J-81.10-02.....	8/18/21
J-21.15-01.....	6/10/13	J-40.35-01.....	5/29/13	J-81.12-00.....	9/3/21
J-21.16-02.....	6/21/24	J-40.36-02.....	7/21/17	J-84.05-00.....	8/30/22
J-21.17-01.....	6/10/13	J-40.37-02.....	7/21/17	J-86.10-00.....	6/28/18
J-21.20-01.....	6/10/13	J-40.38-01.....	5/20/13	J-90.10-03.....	6/28/18
J-22.15-03.....	6/21/24	J-40.39-00.....	5/20/13	J-90.20-03.....	6/28/18
J-22.16-03.....	7/10/15	J-40.40-02.....	7/31/19	J-90.21-02.....	6/28/18
J-22.17-00.....	6/21/24	J-45.36-00.....	7/21/17	J-90.50-00.....	6/28/18
K-70.20-01.....	6/1/16	K-80.32-00.....	8/17/21	K-80.35-01.....	9/16/20
K-80.10-02.....	9/25/20	K-80.34-00.....	8/17/21	K-80.37-01.....	9/16/20
L-5.10-02.....	6/5/24	L-20.10-03.....	7/14/15	L-40.20-02.....	6/21/12
L-5.15-00.....	9/19/22	L-30.10-02.....	6/11/14	L-70.10-01.....	5/21/08
L-10.10-02.....	6/21/12	L-40.15-01.....	6/16/11	L-70.20-01.....	5/21/08
M-1.20-04.....	9/25/20	M-9.60-00.....	2/10/09	M-24.66-00.....	7/11/17
M-1.40-03.....	9/25/20	M-11.10-04.....	8/2/22	M-40.10-04.....	10/17/23
M-1.60-03.....	9/25/20	M-12.10-04.....	6/28/24	M-40.20-00.....	10/12/07
M-1.80-03.....	6/3/11	M-15.10-02.....	7/17/23	M-40.30-01.....	7/11/17
M-2.20-03.....	7/10/15	M-17.10-02.....	7/3/08	M-40.40-00.....	9/20/07
M-2.21-00.....	7/10/15	M-20.10-04.....	8/2/22	M-40.50-00.....	9/20/07
M-3.10-04.....	9/25/20	M-20.20-02.....	4/20/15	M-40.60-00.....	9/20/07
M-3.20-04.....	8/2/22	M-20.30-05.....	6/28/24	M-60.10-01.....	6/3/11
M-3.30-04.....	9/25/20	M-20.40-03.....	6/24/14	M-60.20-03.....	8/17/21
M-3.40-04.....	9/25/20	M-20.50-02.....	6/3/11	M-65.10-03.....	8/17/21
M-3.50-03.....	9/25/20	M-24.20-02.....	4/20/15	M-80.10-01.....	6/3/11
M-5.10-03.....	9/25/20	M-24.40-02.....	4/20/15	M-80.20-00.....	6/10/08
M-7.50-01.....	1/30/07	M-24.60-04.....	6/24/14	M-80.30-00.....	6/10/08
M-9.50-02.....	6/24/14	M-24.65-00.....	7/11/17		

END DIVISION 9



NOTES:

1. CASTINGS SHALL BE GRAY IRON ASTM A48, AASHTO M 105, CLASS 30.
2. COVER AND SEAT SHALL BE MACHINED FOR PERFECT CONTACT AROUND CIRCUMFERENCE AND FULL WIDTH OF BEARING SURFACE.
3. APPROXIMATE WEIGHTS, STANDARD.

CASE	60 LBS
COVER	19 LBS
TOTAL	79 LBS
4. PAVEMENT SHALL BE ASPHALT CONCRETE OR APPROVED SUBSTITUTE.
5. CONCRETE SHALL BE CLASS 4000.
6. SEE SECTION 3.8.5.
7. COVER LETTERING MAY READ MONUMENT OR MON




PLAN OF MONUMENT



SECTION B-B




ESTABLISHMENT AND/OR RE-ALIGNMENT OF A ROADWAY/RIGHT-OF-WAY CENTERLINE REQUIRE THAT MONUMENTS BE SET PER SECTION 3.8.5 OF THE PUBLIC WORKS DEVELOPMENT STANDARDS. ALL NEW MONUMENTS SHALL BE DOCUMENTED WITH A RECORD OF SURVEY AND CITY OF FEDERAL WAY MONUMENT RECORD FORM (DETAIL 3-37). EXCEPTION: ROADWAY MONUMENTS THAT ARE SET/ESTABLISHED AS PART OF A RECORDED SUBDIVISION.

REV: JUN 2024




PLAN

NOTE:
ONLY THE ASSIGNED IDENTIFICATION NUMBERS ARE TO APPEAR ON THE BRASS DISC.




EDGE ROCK OR
CONCRETE INSTALLATION

NOTE:
EXCAVATION TO BE MADE LARGE ENOUGH TO CLEAR MARKER 1 1/2" AT ALL POINTS.



PLAN




GENERAL INSTALLATION

SECTION D-D

NOTES;


1. THE BRASS DISC SHALL BE CAST OF YELLOW BRASS SAE 41.
2. CONCRETE SHALL BE CLASS 4000.
3. THE HOLE SHALL BE 2.5' MIN. IN DEPTH OR 0.5' BELOW THE DEEPEST RECORDED FROST LINE. ALL LOOSE MATERIAL SHALL BE REMOVED FROM THE BOTTOM OF THE HOLE SO THAT THE CONCRETE IS ON FIRM, UNDISTURBED EARTH.
4. THE TOP OF THE CONCRETE SHALL BE TROWLED SMOOTH AND THE BRASS DISC SET IN THE CENTER WITH ITS TOP EDGE FLUSH AND LEVEL.
5. COORDINATES OR ELEVATIONS SHALL NOT BE PLACED ON THE BRASS DISCS.




BRASS DISC
ELEVATION

ESTABLISHMENT AND/OR RE-ALIGNMENT OF A ROADWAY/RIGHT-OF-WAY CENTERLINE REQUIRE THAT MONUMENTS BE SET PER SECTION 3.8.5 OF THE PUBLIC WORKS DEVELOPMENT STANDARDS. ALL NEW MONUMENTS SHALL BE DOCUMENTED WITH A RECORD OF SURVEY AND CITY OF FEDERAL WAY MONUMENT RECORD FORM (DETAIL 3-37).
EXCEPTION: ROADWAY MONUMENTS THAT ARE SET/ESTABLISHED AS PART OF A RECORDED SUBDIVISION.


REV: JUN 2024



PLAN



SECTION A-A




SECTION B-B


NOTES:

1. SET TO GRADE AND CONSTRUCT ROAD AND GUTTER TO BE FLUSH WITH FRAME.


REV: JUN 2024




PLAN



SECTION B-B




HOOD DETAIL



2 - 1" DIAM. HOLES FOR 3/4" BOLT, WASHER, & NUT, SEE NOTE 4.

SECTION C-C




SECTION A-A


NOTES:

1. MATERIAL IS CAST IRON ASTM A48 CLASS 30.
2. SEE STANDARD DETAIL FW.B30.30 FOR VANED GRATE.
3. PATTERN ON TOP SURFACE OF HOOD SHALL BE 3/16" NON-SKID DIAMOND.
4. BOLT, WASHER, AND NUT SHALL BE GALV. OR CORROSION RESISTANT.


REV: JUN 2024




PLAN



SECTION A-A



VERTICAL CURB




EXTRUDED CURB


NOTES:

1. DRILL AND TAP FOR, AND PROVIDE, TWO LOCKING BOLTS 5/8"-11 NC STAINLESS TYPE 304 STEEL SOCKET HEAD (ALLEN HEAD) CAP SCREWS 2" LONG WHEN USED WITH SOLID COVER (STANDARD DETAIL FW.B30.20) OR WHEN SPECIFIED BY ENGINEER.
2. FRAME MATERIAL IS CAST IRON PER ASTM A48 CLASS 30.
3. SET FRAME TO GRADE AND CONSTRUCT ROAD AND GUTTER TO BE FLUSH WITH FRAME.

REV: JUN 2024



PLAN COVER




SECTION A-A

NOTES:

1. USE WITH FRAME DRILLED AND TAPPED FOR LOCKING BOLTS.
2. USE WITH TWO LOCKING BOLTS 5/8"-11 NC STAINLESS STEEL TYPE 304 STEEL SOCKET HEAD (ALLEN HEAD) CAP SCREWS, 2" LONG.
3. MATERIAL IS CAST IRON PER ASTM A48 CLASS 30.
4. THE WORDS "CITY OF FEDERAL WAY" TO BE OMITTED IF COVER IS ON A PRIVATE SYSTEM.

REV: JUN 2024




FOR SLOT DETAIL SEE
STANDARD DETAIL FW.B30.50

NOTES:

1. SELF-LOCK VANED GRATE MANUFACTURER SUBJECT TO APPROVAL BY ENGINEER.
2. USE WITH TWO LOCKING BOLTS 5/8"-11 NC STAINLESS TYPE 304 STEEL SOCKET HEAD (ALLEN HEAD) CAP SCREWS 2" LONG. NOTE SLOT DETAIL.
3. MATERIAL IS DUCTILE IRON ASTM A536 GRADE 80-55-06.
4. "OUTFALL TO STREAM DUMP NO POLLUTANTS" SHALL BE LOCATED ON BORDER AREA.
5. INSTALL BI-DIRECTIONAL VANED GRATES AT SAG LOCATIONS.
6. THE WORDS "CITY OF FEDERAL WAY" SHALL BE OMITTED IF GRATE IS ON A PRIVATE SYSTEM.


PLAN

5' DRAFT



ELEVATION

REV: JUN 2024




FOR SLOT DETAIL SEE
STANDARD DETAIL FW.B30.50


NOTES:

1. SELF-LOCK VANED GRATE MANUFACTURER SUBJECT TO APPROVAL BY ENGINEER.
2. USE WITH TWO LOCKING BOLTS 5/8"-11 NC STAINLESS TYPE 304 STEEL SOCKET HEAD (ALLEN HEAD) CAP SCREWS 2" LONG. NOTE SLOT DETAIL.
3. MATERIAL IS DUCTILE IRON ASTM A536 GRADE 80-55-06.
4. "OUTFALL TO STREAM DUMP NO POLLUTANTS" MAY BE LOCATED ON BORDER AREA.
5. INSTALL BI-DIRECTIONAL VANED GRATES AT SAG LOCATIONS.
6. THE WORDS "CITY OF FEDERAL WAY" SHALL BE OMITTED IF GRATE IS ON A PRIVATE SYSTEM.

TOP





SECTION




ISOMETRIC

REV: JUN 2024



BOLT-DOWN DETAIL





COVER SKID DESIGN DETAIL


NOTES:

1. USE WITH THREE LOCKING BOLTS 5/8"-11 NC STAINLESS TYPE 304 STEEL SOCKET HEAD (ALLEN HEAD) CAP SCREWS 2" LONG. DRILL HOLES SPACED 120° AT 11 1/16" RADIUS.
2. MATERIAL IS DUCTILE IRON ASTM A536 GRADE 80-55-06
3. DRILL THREE 1 INCH HOLES SPACED AT 120° AND 9 1/2" RADIUS.
4. THE WORDS "CITY OF FEDERAL WAY" SHALL BE OMITTED IF COVER IS ON A PRIVATE SYSTEM.

REV: JUN 2024



BOLT-DOWN DETAIL




SECTION A-A

NOTES:

1. MATERIAL IS CAST IRON ASTM A48 CLASS 30.
2. DRILL AND TAP THREE 5/8"-11 NC HOLES THROUGH FRAME AT 120° AND 11 1/16" RADIUS.

REV: JUN 2024




SECTION THROUGH STRUCTURE

NTS

NOTES:

- PAVEMENT CUT SHALL BE CIRCULAR AND CENTERED ON THE CENTER OF THE MANHOLE OR CATCH BASIN LID. RECTANGULAR OR POLYGON CUTS NOT ALLOWED.
- CONVERT ALL RECTANGULAR FRAMES AND LIDS TO ROUND, USING CONCRETE CONVERSION RISER IN ACCORDANCE WITH CITY OF FEDERAL WAY STANDARD DETAIL FW.B30.74.
- RAISE OR LOWER STRUCTURE TO THE REQUIRED ELEVATION AND SLOPE USING ONLY INFRA-RISER AND/OR CONCRETE RINGS AND BRICKS AS NECESSARY. NO OTHER MATERIALS ARE ALLOWED. TO ACHIEVE WATER-TIGHT CONSTRUCTION, GROUT INSIDE AND OUTSIDE OF EACH JOINT USING A LAYER OF NON-SHRINK MORTAR NO MORE THAN 3/4" THICK, AND FINISHED SMOOTH.
- ON ALL STRUCTURES WITHIN THE ROADWAY TRAVEL LANES, INSTALL INFRA-RISER MULTI-PURPOSE RUBBER COMPOSITE ADJUSTMENT RISER, MANUFACTURED BY EAST JORDAN IRON WORKS. INFRA-RISER SHALL BE INSTALLED PER THE MANUFACTURER'S RECOMMENDATIONS. REMOVE EXISTING CONCRETE RISER IF NECESSARY TO MAKE ROOM FOR INFRA-RISER. STACKED INFRA-RISER SHALL NOT EXCEED 3" TOTAL HEIGHT. INFRA-RISER SHALL BE INSTALLED ON TOP OF ALL CONCRETE RISERS, DIRECTLY UNDER THE ERGO MANHOLE ASSEMBLY.
- ON ALL STRUCTURES, INSTALL NEW EAST JORDAN IRON WORKS ERGO 4"x24" CAM LOCKING HINGED MANHOLE ASSEMBLY (PRODUCT NO. 00104028L03), PER MANUFACTURER'S RECOMMENDATIONS. SET TOP OF ASSEMBLY TO BE FLUSH WITH EXISTING ROAD AND/OR GUTTER SURFACE. LOCATE HINGE SO THAT IT'S NEAREST TO ONCOMING TRAFFIC.
- HMA SHALL BE MECHANICALLY COMPACTED IN 3" (MAX.) LIFTS.

REV: JUN 2024




SECTION THROUGH STRUCTURE
(NOT TO SCALE)

NOTES:

- 1) THE EXISTING STRUCTURE SHALL BE RAISED OR LOWERED TO THE REQUIRED ELEVATION USING CONCRETE BLOCKS, BRICK, AND/OR CONCRETE RINGS. EACH JOINT SHALL BE GROUTED USING A $\frac{3}{4}$ INCH LAYER OF NON-SHRINK MORTAR, PLASTERED SMOOTH INSIDE AND OUT. COVERS SHALL BE SEATED ON A UNIFORM LAYER OF GROUT TO PREVENT ROCKING.
- 2) IF RISERS OR GRADE RINGS ARE LESS THAN 2" THICK, THEN THE DIG-OUT LIMITS (AND HMA DEPTH) SHALL BE EXTENDED TO 2" BELOW THE NEXT RING OR RISER THAT IS GREATER THAN 2" THICK.
- 3) HMA SHALL BE MECHANICALLY COMPACTED IN 3" MAXIMUM LIFTS.
- 4) SEE CITY OF FEDERAL WAY STANDARD DETAIL FW.A10.30-A FOR ADJUSTMENT OF SURVEY MONUMENT CASTINGS.

REV: JUN 2024




APPLY STENCIL TO PAVEMENT
DIRECTLY BELOW GRATE. TEXT
AND GRAPHIC FACE THE ROAD.

NOTES:

1. PICK UP EQUIPMENT (STENCILS, PAINT, SAFETY GEAR) AT THE PUBLIC WORKS DEPARTMENT.
2. INSTALL STENCIL AT EACH STORM DRAIN.
 - A. SAFETY FIRST! SET OUT CONES OR ORANGE FLAGS.
 - B. LINE UP TOP EDGE OF STENCIL AGAINST THE BOTTOM EDGE OF STORM DRAIN.
 - C. ORIENT STENCIL SO THAT TEXT AND GRAPHIC FACE THE STREET.
 - D. TAPE CORNERS OF STENCIL.
 - E. SPRAY PAINT IN A LIGHT AND EVEN COAT.
 - F. REMOVE STENCIL IN ONE MOTION TO AVOID SMUDGING.
3. STORE STENCIL FLAT (AND NOT ROLLED) WHEN NOT IN USE.

REV: JUN 2024




CEMENT CONCRETE CURB & GUTTER REPLACEMENT¹


NOTES:

1. EXISTING CURB REPLACEMENT WILL REQUIRE REMOVAL OF ASPHALT A MINIMUM OF 24" FROM FACE OF GUTTER.


REV: JUN 2024




A. CEMENT CONCRETE TRAFFIC CURB AND GUTTER, SIDEWALK TO ASPHALT CONCRETE EDGE WITH GRAVEL SHOULDER



B. CEMENT CONCRETE ROLLED CURB, SIDEWALK TO ASPHALT CONCRETE EDGE WITH GRAVEL SHOULDER





C. CEMENT CONCRETE TRAFFIC CURB AND GUTTER, SIDEWALK TO ASPHALT CONCRETE EDGE WITH GRAVEL SHOULDER



D. CEMENT CONCRETE TRAFFIC CURB AND GUTTER TO CEMENT CONCRETE ROLLED CURB TRANSITION

REV: JUN 2024





NOTES:

1. FOR JOINTS AND SCORING, SEE FEDERAL WAY STANDARD DETAIL FW.F30.20 FOR SIDEWALK SPACING, EXPANSION JOINTS, AND SCORE MARKS.
2. SEE WSDOT STANDARD DRAWING FOR MINIMUM DEPTH OF CONCRETE THROUGH DRIVEWAY SECTIONS.
3. WHEN CHECKED WITH A 10 FOOT STRAIGHTEDGE, GRADE SHALL NOT DEVIATE MORE THAN 1/8 INCH AND ALIGNMENT SHALL NOT VARY MORE THAN 1/4 INCH.
4. CONCRETE SHALL BE CLASS 5000, WSDOT STANDARD SPECIFICATION, SECTION 8-14.


REV: JUN 2024

NOTES:



1. AN EXPANSION JOINT CONSISTING OF 3/8" PRE-MOLDED JOINT MATERIAL SHALL BE PLACED FULL DEPTH AROUND HYDRANTS, POLES, JUNCTION BOX, POSTS, AND UTILITY CASTINGS. SEE DETAIL AT RIGHT.
2. AN EXPANSION JOINT CONSISTING OF 3/8" PRE-MOLDED JOINT MATERIAL SHALL BE PLACED IN THE UPPER 2 INCHES OF CURBS AND SIDEWALKS AT 10 FOOT INTERVALS AND AT SIDES OF DRAINAGE INLETS. (JOINT MATERIAL OF 2 1/2" DEPTH MAY BE USED IN LIEU OF 2" DEPTH).
3. EXPANSION JOINTS IN SIDEWALK SHALL BE LOCATED SO AS TO MATCH THE JOINTS IN THE CURB AND GUTTER, WHETHER THE SIDEWALK IS ADJACENT TO THE CURB OR SEPARATED BY A PLANTER STRIP.
4. TOOL MARKS, CONSISTING OF 1/4-INCH 'V'-GROOVES SHALL BE MADE IN THE SIDEWALK AT 5-FOOT INTERVALS, INTERMEDIATE TO THE EXPANSION JOINTS.
5. AN EXPANSION JOINT CONSISTING OF 3/8" PRE-MOLDED JOINT MATERIAL SHALL BE PLACED FULL-DEPTH BETWEEN THE CURB AND ADJACENT SIDEWALK.
6. EXPANSION JOINT MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF ASTM D1751 (AASHTO M 213).
7. MONOLITHIC POURS OF CURB AND SIDEWALK ARE NOT ALLOWED.
8. ALL UTILITY APPURTENANCES WITHIN THE SIDEWALK SHALL HAVE SLIP RESISTANT LIDS.




SEE NOTE 1




SECTION A-A




REV: JUN 2024



ACCEPTABLE
RAMP LOCATIONS
FOR RETROFIT OR ALTERATION



FOR ALTERATION
RETROFIT OR REBUILD





RAMP LOCATIONS
FOR NEW CONSTRUCTION
OR STANDARD RECONSTRUCTION

NOTES:

1. CATCH BASIN AND INLETS SHALL BE OUTSIDE THE CURB RAMP (24" MIN. CLEARANCE FROM RAMP).
2. CARE SHALL BE TAKEN TO KEEP THE RAMP FROM CONFLICTING WITH HYDRANTS, POLES, INLETS, AND OTHER UTILITIES.
3. CONSTRUCT RAMP IN ACCORDANCE WITH WSDOT STANDARD PLANS F-40.12-03, F-40.14-03, F-40.15-04, F-40.16-05 AND F-45.10-03
4. CROSSWALKS ARE NOT ALWAYS MARKED.
5. WHEN RAMPS ARE CONSTRUCTED ON ONE SIDE OF STREET, RAMPS SHALL BE CONSTRUCTED AT CORRESPONDING LOCATIONS ON OPPOSITE SIDE OF STREET.

REV: JUN 2024




SECTION A-A


NOTES:

1. REFER TO CITY OF FEDERAL WAY STANDARD DETAIL FW.F80.20 FOR COMMERCIAL, INDUSTRIAL, OR MULTI-FAMILY USE DRIVEWAYS.
2. SEE SEC. 4.0 AND CURB WSDOT STANDARD PLAN F-10.12.
3. CEMENT CONCRETE DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH CEMENT CONCRETE, CLASS 4000, WITH 4% TO 6% AIR ENTRAINMENT.
4. FULL DEPTH EXPANSION JOINT IF DRIVEWAY WIDTH IS 15' OR GREATER.
5. REFER TO SECTION 4.0 FOR DRIVEWAY SPACING.
6. LENGTH OF RAMP SHALL VARY AS NEEDED TO MEET ADA SLOPE REQUIREMENTS.

REV: JUN 2024



WIDTH: 30' 2-LANE,
40' 3-LANE




SECTION A-A

NOTES:

1. COMMERCIAL/INDUSTRIAL DRIVEWAYS WIDER THAN 40' MAY BE APPROVED BY THE ENGINEER CONSIDERING TRAFFIC SAFETY AND NEEDS OF THE ACTIVITY SERVED. ALL COMMERCIAL/INDUSTRIAL DRIVEWAYS SHALL HAVE AN EXPANSION JOINT LOCATED MID-WIDTH. SEE KING COUNTY ROAD STANDARDS SECTION 3.04.
2. SEE SEC. 4.0 AND CURB WSDOT STANDARD PLAN F-10.12.
3. CEMENT CONCRETE DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH CEMENT CONCRETE CLASS 4000 WITH 4% TO 6% AIR ENTRAINMENT.
4. FULL DEPTH EXPANSION JOINT IF DRIVEWAY WIDTH IS 15' OR GREATER.
5. LENGTH OF RAMP SHALL VARY AS NEEDED TO MEET ADA SLOPE REQUIREMENTS.
6. SEE CITY OF FEDERAL WAY STANDARD DETAIL FW.F80.10 FOR LIGHT STANDARD PLACEMENT.

REV: JUN 2024



NOTES:

1. A REVERSE SLOPE DRIVEWAY IS SUBJECT TO APPROVAL BY ENGINEER CONSIDERING NEED FOR AND COMPATIBILITY OF THIS FEATURE.
2. COMMERCIAL/INDUSTRIAL DRIVEWAYS WIDER THAN 40' MAY BE APPROVED CONSIDERING TRAFFIC SAFETY AND NEEDS OF THE ACTIVITY SERVED. ALL COMMERCIAL/INDUSTRIAL DRIVEWAYS SHALL HAVE AN EXPANSION JOINT LOCATED MID-WIDTH. SEE KING COUNTY ROAD STANDARDS SECTION 3.04.
3. A STORM SEWER INLET SHALL BE LOCATED WITHIN 20' BUT NO CLOSER THAN 10' UPGRADE FROM NEAREST EDGE OF CURB TAPER.
4. SEE SEC. 4.0 AND CURB DETAIL DRAWING WSDOT STANDARD PLAN F-10.12.
5. CEMENT CONCRETE DRIVEWAY APPROACHES SHALL BE CONSTRUCTED WITH CEMENT CONCRETE CLASS 4000 WITH 4% TO 6% AIR ENTRAINMENT.
6. FULL DEPTH EXPANSION JOINT IF DRIVEWAY WIDTH IS 15' OR GREATER.
7. SEE SECTION 4.0 FOR MAX CHANGE IN DRIVEWAY GRADE
8. LENGTH OF RAMP SHALL VARY AS NEEDED TO MEET ADA SLOPE REQUIREMENTS.

REV: JUN 2024

SIGN FACE MATERIALS

All permanent sign faces shall be constructed from aluminum sign blanks. Sign blanks shall be made from 6061-T6 aluminum alloy chemically conversion coated in accordance with ASTM B449-67 Class 3 (alodine). Sign blank minimum thickness, based on maximum dimensions, are as follows, except as noted below:

<u>Maximum Dimension</u>	<u>Sign Blank Thickness</u>
Less than 30 inches	0.080 inches
30 inches to less than 48 inches	0.100 inches
48 inches and larger	0.125 inches

All edges, corners, and holes shall be smooth and free of burrs and snags. All signs except Stop signs shall have rounded edges.

All street name signs shall have a silver legend on a green background. Do not include ordinals (th, st, etc.) on street name signs (i.e., S 320 St, not S 320th St).

All D-3 street name signs shall be constructed with 0.100-inch thick blanks. The Contractor shall install permanent signs which meet or exceed the minimum reflectivity standards. All sign face sheeting shall be applied to sign blanks with pressure-sensitive adhesives.

All regulatory (R-series), school (S-series), and warning (W- and X-series) signs, except for parking regulation and parking prohibition signing shall be constructed with Type III or Type IV sheeting, in accordance with Section 9-28.12 of the Standard Specifications. This high-intensity sheeting shall be 3M Series 3800 or its equivalent. All street name (D-3) sign sheeting shall meet this specification.

All overhead signing shall be constructed with Type IX sheeting. All fluorescent yellow-green signs (all pedestrian/non-motorized related W-series and all school warning signs) shall meet the following requirements of Type IX sheeting. This sheeting has a minimum retro-reflection rating of 800 candelas/lux/square foot for white-silver sheeting with a divergence angle of 0.2E and an incidence angle of -4E. This standard applies to all signs mounted above the roadway - on span wire or signal mast arms.

Motorist information and parking signs shall be constructed with Type I sheeting, in accordance with Section 9-28.12 of the Standard Specifications. These signs include guide signing (D-series, except D-3), corporate limit signing (I-series), and motorist information signing (K-series).

The reflectivity standard of supplemental plates shall match that of the primary sign.

SIGN INVENTORY

The City of Federal Way shall be contacted (253-835-2700) within two working days of completion of the permanent signing installation to inspect, inventory, and log all new and relocated signs. Any signs removed shall be returned to the King County Sign Shop in Renton.

OTHER SIGNS

Refer to the current adopted edition of the MUTCD or equivalent approved source. This includes pavement markings as a supplement to signing.

ADDITIONAL QUESTIONS/REQUESTS SHALL BE DIRECTED TO:

Design - City Traffic Engineer - 253-835-2740
Installation/Removal - Public Works Inspector - 253-835-2700
Sign Fabrication - King County Sign Shop - 253-477-8100
Street Addressing - Building Division - 253-835-2607

STREET NAME SIGN ABBREVIATIONS

ROADWAY DESIGNATIONS

Ave	-	AVENUE
St	-	STREET
Ct	-	COURT
Blvd	-	BOULEVARD
Dr	-	DRIVE
Hwy	-	HIGHWAY
Pkwy	-	PARKWAY
Pl	-	PLACE
Ln	-	LANE
Rd	-	ROAD
Way	-	WAY


GEOGRAPHICAL AREAS

S	-	SOUTH
SW	-	SOUTHWEST

REV: JUN 2024



NOTES

- 1) MOUNTING HEIGHT SHALL BE IN ACCORDANCE WITH THE CURRENT ADOPTED EDITION OF THE MUTCD.
- 2) FOR STEEL POST INSTALLATIONS, USE A NYLON WASHER AND AN ALUMINUM DRIVE RIVET TO INSTALL THE SIGN TO THE POST.
- 3) VERIFY AND STAKE LOCATIONS OF TRAFFIC SIGNS FOR ENGINEER APPROVAL AND ADJUSTMENT PRIOR TO INSTALLATION.




GALVANIZED SIGN POST DETAIL

REV: JUN 2024




NOTES

1. THIS METHOD OF INSTALLATION SHALL ONLY BE USED IN CITY CENTER UNLESS OTHERWISE APPROVED.
2. PREGALVANIZED PERFORATED SQUARE TUBING SHALL BE COLD-FORMED TO SIZE FROM LOW-CARBON 12 GAUGE, ASTM A653 GRADE 33.
3. PLAIN STEEL BOTTOM PLATE; ASTM A1011 SS GRADE 33.
4. FINAL ASSEMBLED PIECE SHALL BE PAINTED GRAY FOR WEATHER RESISTANCE.
5. LOCATE SIGN IN ACCORDANCE WITH PLAN OR AS DIRECTED BY CITY TRAFFIC ENGINEER. IN CITY CENTER, THIS IS TYPICALLY ALIGNED WITH TREE WELLS AND STREET LIGHTS, NEAR THE STREET.
6. LOCATE BASE PLATE TO MAINTAIN ACCESSIBLE PATH ON SIDEWALK (MIN. 4-FOOT PASSAGE WIDTH).



REV: JUN 2024




NOTES:

1. SEE APPROPRIATE STREET CROSS-SECTION FOR DIMENSIONS.

REV: JUN 2024

BICYCLE DETECTOR LOOP 4
 SERIES CONNECTED LOOP 2-3
 COUNT DETECTOR LOOP 1



POSTED SPEED (MPH)	* S1 (FT)	* S2 (FT)	** S3 (FT)
25	--	105	260
30	--	140	310
35	--	185	360
40	115	230	410
45	155	285	465
50	195	340	515

* ADVANCE LOOPS ARE NOT REQUIRED FOR TURNING LANES AND NON-COORDINATED THROUGH LANES


** S3 IS USED ON COORDINATED LANES FOR ADAPTIVE SYSTEM DETECTION. FOR TURN LANES, S3 IS AT THE BEGINNING OF TURN LANE.

NOTES

1. USE XYZ LOOP NUMBERING SCHEMATIC, WHERE:
 X IS THE PHASE #
 Y IS LANE # FROM INSIDE
 Z IS LOOP # FROM STOP LINE
2. USE 3-FOOT LOOP FOR BIKE LANES, LOCATED AT 50 FEET FROM STOP LINE
3. PHASE 2 IS ALWAYS NORTHBOUND THROUGH DIRECTION
4. ALL LOOPS SHALL BE CIRCULAR

(NOT TO SCALE)

REV: JUN 2024




NOTES

1. THE FIRST TYPE 2L ARROW IS INSTALLED 50 FEET BACK OF STOP LINE OR CROSSWALK. THE SECOND ARROW IS LOCATED 100 FEET BACK OR AT THE END OF WIDE SOLID LANE LINE.
2. "S" = 140 FT. FOR POSTED SPEED < 50 MPH.
"S" = 170 FT. FOR POSTED SPEED >= 50 MPH.
3. STOPPING POINT SHALL BE MARKED WITH STOP LINE ONLY WHEN MAINLINE MOVEMENT IS CONTROLLED BY A STOP SIGN OR TRAFFIC SIGNAL.
4. RAISED PAVEMENT MARKERS SHALL BE INSTALLED WITH ALL STRIPING, MEDIANS, AND CURBING USED AS CHANNELIZATION.

WHERE:

- W₁ = APPROACHING THROUGH LANE
- W₂ = DEPARTING LANE
- T₁ = WIDTH OF LEFT TURN LANE ON APPROACH SIDE OF
- T₂ = WIDTH OF LEFT TURN LANE ON DEPARTURE SIDE OF
- W_T = TOTAL WIDTH OF CHANNELIZATION (W₁ + W₂ + T₁ + T₂)

LEFT-TURN LANE




TWO-WAY LEFT-TURN LANE

(FOR END OF TWLTL, SEE DETAIL B, STD. DETAIL FW.M20.41)

SEE STANDARD DETAIL FW.M20.10 FOR STRIPING PATTERN NOTES.
SEE STANDARD DETAIL FW.M15.10 FOR NOTES ON ARROWS AND STOP LINE.
SEE STANDARD DETAILS FW.M20.30 AND FW.M20.40 FOR RPM DETAILS AND NOTES.

TABLE 1		TABLE 2		TABLE 3	
POSTED SPEED	TAPER RATE	POSTED SPEED	DECEL. TAPER LENGTH	POSTED SPEED	NO PASS LENGTH (MINIMUM)
55 MPH	55 : 1	55 MPH	165'	55 MPH	725'
50 MPH	50 : 1	50 MPH	150'	50 MPH	660'
45 MPH	45 : 1	45 MPH	135'	45 MPH	590'
40 MPH	40 : 1	40 MPH	120'	40 MPH	360'
35 MPH	35 : 1	35 MPH	105'	35 MPH	260'
30 MPH	30 : 1	30 MPH	90'	30 MPH	200'
25 MPH	25 : 1	25 MPH	75'	25 MPH	150'

REV: JUN 2024



CROSSWALK LINE DETAIL

NOTES

1. CROSSWALK LINE SHALL CONSIST OF TWO 8-INCH WIDE LINES, SEPARATED BY AN 8-INCH GAP - SEE DETAIL ABOVE.
2. CROSSWALK LINE SHALL NOT BE INSTALLED ON CONCRETE GUTTER PAN. USE OF SINGLE 8-INCH LINES NEAR THE GUTTER IS ALLOWED.
3. PROVIDE A MINIMUM OF 4 FEET BETWEEN FACE OF STOP LINE AND BOTTOM OF CROSSWALK. PROVIDE ADDITIONAL SPACE IF INDICATED BY TURNING MOVEMENT ANALYSIS.
4. CROSSWALK LINE SHALL TYPICALLY BE ALIGNED WITH CENTER LINE AND LANE LINE MARKINGS. OTHER CROSSWALK LINE SHALL BE CENTERED BETWEEN THESE.
5. STOP LINE USE CASES - SEE STANDARD DETAIL FW.M3.10
6. TRAFFIC ARROWS TYPE 1S, 2SL, 2ST, 3SL, 3SR, 4S, AND 7S - SEE WSDOT STANDARD PLAN M-24.40 AND STANDARD DETAIL FW.M3.10
7. YIELD LINE SYMBOL - SEE WSDOT STANDARD PLAN M-24.60 - TYPE 2, UNLESS APPROVED BY THE CITY TRAFFIC ENGINEER
8. ACCESS PARKING SPACE SYMBOL - SEE WSDOT STANDARD PLAN M-24.60
9. BICYCLE LANE SYMBOL - SEE WSDOT STANDARD PLAN M-9.50
10. HIGH OCCUPANCY VEHICLE (HOV) LANE SYMBOL - SEE WSDOT STANDARD PLAN M-7.50
11. SPEED BUMP SYMBOL - SEE WSDOT STANDARD PLAN M-24.60


REV: JUN 2024

NOTES


1. LONGITUDINAL STRIPING PATTERNS SHALL BE IN ACCORDANCE WITH WSDOT STANDARD PLAN M-20.10. FOR DOUBLE CENTER LINE STRIPING, THE DISTANCE BETWEEN THE LINES SHALL BE 4 INCHES.
2. LONGITUDINAL STRIPING ON ARTERIALS SHALL BE PLASTIC TYPE D METHYLMETHACRYLATE (MMA). TRANSVERSE MARKINGS SHALL BE PLASTIC TYPE A. ALL OTHER STRIPING SHALL BE PAINT, EXCEPT AS CALLED OUT IN NOTE 3 BELOW.
3. FOR ROUNDABOUTS, REGARDLESS OF STREET CLASSIFICATION, LONGITUDINAL STRIPING SHALL BE PLASTIC TYPE D AND TRANSVERSE MARKINGS SHALL BE PLASTIC TYPE A. THIS INCLUDES LONGITUDINAL STRIPING TO THE END OF STRIPING TAPER AT EACH SPLITTER ISLAND.
4. ALL STRIPING WITHIN INTERSECTIONS SHALL BE PLASTIC TYPE A OR D.
5. TRANSVERSE MARKINGS SHALL INCLUDE STOP LINE, CROSSWALK LINE, YIELD LINE, ARROWS, BICYCLE LANE MARKINGS, SHARROWS, HOV MARKINGS, SPEED BUMP SYMBOLS, ETC. FOR ANY MARKING NOT LISTED HERE, COORDINATE WITH THE TRAFFIC DIVISION.
6. WHERE MMA IS USED FOR CENTER LINE (ALL PATTERNS), LANE LINE, REVERSIBLE LANE LINE, YELLOW EDGE LINE, DOTTED EXTENSION LINE, OR WIDE LANE LINE (SOLID, DOTTED, AND HOV), THE MMA SHALL BE PROFILED. WHITE EDGE LINE SHALL NOT BE PROFILED. FOR ALL OTHER LONGITUDINAL STRIPING PATTERNS, COORDINATE WITH THE TRAFFIC DIVISION.

REV: JUN 2024


CENTER LINE




DOUBLE CENTER LINE




WHITE EDGE LINE



YELLOW EDGE LINE



DOTTED EXTENSION LINE



NOTES


1. FOR PAVEMENT MARKING PATTERNS AND DETAILS, SEE STANDARD DETAIL FW.M20.10.
2. FOR RPM TYPES, SEE STANDARD DETAIL FW.20.40.
3. ALL RPMS SHALL BE LOCATED TO PROVIDE 4 INCHES BETWEEN STRIPING AND RPMS.
4. TYPE 2 RPMS SHALL BE USED ON ALL ARTERIALS AND COLLECTORS, IF STRIPED.
5. WHERE CURBING IS USED IN PLACE OF STRIPING, USE THE RPM PATTERN APPLICABLE TO THE STRIPING BEING REPLACED.
6. WHERE RAISED MEDIAN OR YELLOW CURBING IS USED IN PLACE OF STRIPING, USE TYPE 2YR RPMS, WITH RED FACING OPPOSITE THE DIRECTION OF TRAFFIC.
7. WHERE RAISED MEDIAN OR WHITE CURBING IS USED IN PLACE OF STRIPING, USE TYPE 2WR RPMS, WITH RED FACING OPPOSITE THE DIRECTION OF TRAFFIC.

LEGEND


- ◀■ MONO-DIRECTIONAL RPM TYPE 2
- ◊ BI-DIRECTIONAL RPM TYPE 2

REV: JUN 2024


LANE LINE




CENTER LINE WITH NO PASS LINE




WIDE SOLID LANE LINE




TWO-WAY LEFT-TURN CENTER LINE



WIDE DOTTED LANE LINE



WIDE DOTTED EXTENSION LINE (FOR HOV LANE USE)




RAISED PAVEMENT MARKER (RPM) TYPES

TYPE 1	NON-REFLECTIVE	NOT USED
TYPE 2W	REFLECTIVE FACE ONE SIDE	WHITE
TYPE 2WR	REFLECTIVE FACE BOTH SIDES	WHITE / RED
TYPE 2Y	REFLECTIVE FACE ONE SIDE	YELLOW
TYPE 2YY	REFLECTIVE FACE BOTH SIDES	YELLOW / YELLOW
TYPE 2YR	REFLECTIVE FACE BOTH SIDES	YELLOW / RED

**SEE STANDARD DETAIL FW.M20.30 FOR RPM DETAILS AND NOTES.
SEE STANDARD DETAIL FW.M20.10 FOR STRIPING PATTERN NOTES.**


REV: JUN 2024




DETAIL A

WHERE:

- T₁ = WIDTH OF LEFT-TURN LANE ON APPROACH SIDE OF STREET CENTERLINE
- T₂ = WIDTH OF LEFT-TURN LANE ON DEPARTURE SIDE OF STREET CENTERLINE



DETAIL B



TWO-WAY LEFT-TURN LANE
TERMINATION AT TEE INTERSECTION
OR WHERE LEFT TURNS LANE ARE NOT
PERMITTED AND TWO-WAY LEFT-TURN
LANE IS NOT CONTINUED BEYOND
INTERSECTION.

END TWO-WAY LEFT-TURN LANE

**SEE STANDARD DETAILS FW.M20.30 AND FW.M20.40 FOR RPM DETAILS AND NOTES.
SEE STANDARD DETAIL FW.M20.10 FOR STRIPING PATTERN NOTES.**

REV: JUN 2024

Benefit Code Key – Effective 8/31/2024 thru 3/4/2025

Overtime Codes

Overtime calculations are based on the hourly rate actually paid to the worker. On public works projects, the hourly rate must be not less than the prevailing rate of wage minus the hourly rate of the cost of fringe benefits actually provided for the worker.

1. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.
 - B. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - C. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - D. The first two (2) hours before or after a five-eight (8) hour workweek day or a four-ten (10) hour workweek day and the first eight (8) hours worked the next day after either workweek shall be paid at one and one-half times the hourly rate of wage. All additional hours worked and all worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.
 - G. The first ten (10) hours worked on Saturdays and the first ten (10) hours worked on a fifth calendar weekday in a four-ten hour schedule, shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - H. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions or equipment breakdown) shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - I. All hours worked on Sundays and holidays shall also be paid at double the hourly rate of wage.
 - J. The first two (2) hours after eight (8) regular hours Monday through Friday and the first ten (10) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage.
 - K. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.
 - M. All hours worked on Saturdays (except makeup days if work is lost due to inclement weather conditions) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Overtime Codes Continued

- 1. N. All hours worked on Saturdays (except makeup days) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- O. The first ten (10) hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays, holidays and after twelve (12) hours, Monday through Friday and after ten (10) hours on Saturday shall be paid at double the hourly rate of wage.
- P. All hours worked on Saturdays (except makeup days if circumstances warrant) and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.
- Q. The first two (2) hours after eight (8) regular hours Monday through Friday and up to ten (10) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of ten (10) hours per day Monday through Saturday and all hours worked on Sundays and holidays (except Christmas day) shall be paid at double the hourly rate of wage. All hours worked on Christmas day shall be paid at two and one-half times the hourly rate of wage.
- R. All hours worked on Sundays and holidays shall be paid at two times the hourly rate of wage.
- U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays (except Labor Day) shall be paid at two times the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage.
- V. All hours worked on Sundays and holidays (except Thanksgiving Day and Christmas day) shall be paid at one and one-half times the hourly rate of wage. All hours worked on Thanksgiving Day and Christmas day shall be paid at double the hourly rate of wage.
- W. All hours worked on Saturdays and Sundays (except make-up days due to conditions beyond the control of the employer) shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at double the hourly rate of wage.
- X. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked over twelve (12) hours Monday through Saturday, Sundays and holidays shall be paid at double the hourly rate of wage. When holiday falls on Saturday or Sunday, the day before Saturday, Friday, and the day after Sunday, Monday, shall be considered the holiday and all work performed shall be paid at double the hourly rate of wage.
- Y. All hours worked outside the hours of 5:00 am and 5:00 pm (or such other hours as may be agreed upon by any employer and the employee) and all hours worked in excess of eight (8) hours per day (10 hours per day for a 4 x 10 workweek) and on Saturdays and holidays (except labor day) shall be paid at one and one-half times the hourly rate of wage. (except for employees who are absent from work without prior approval on a scheduled workday during the workweek shall be paid at the straight-time rate until they have worked 8 hours in a day (10 in a 4 x 10 workweek) or 40 hours during that workweek.) All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and Labor Day shall be paid at double the hourly rate of wage.
- Z. All hours worked on Saturdays and Sundays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid the straight time rate of pay in addition to holiday pay.

Overtime Codes Continued

2. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.
- B. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.
 - F. The first eight (8) hours worked on holidays shall be paid at the straight hourly rate of wage in addition to the holiday pay. All hours worked in excess of eight (8) hours on holidays shall be paid at double the hourly rate of wage.
 - M. This code appears to be missing. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage.
 - R. All hours worked on Sundays and holidays and all hours worked over sixty (60) in one week shall be paid at double the hourly rate of wage.
 - U. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked over 12 hours in a day or on Sundays and holidays shall be paid at double the hourly rate of wage.

3. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.
- F. All hours worked on Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sunday shall be paid at two times the hourly rate of wage. All hours worked on paid holidays shall be paid at two and one-half times the hourly rate of wage including holiday pay.
 - H. All work performed on Sundays between March 16th and October 14th and all Holidays shall be compensated for at two (2) times the regular rate of pay. Work performed on Sundays between October 15th and March 15th shall be compensated at one and one half (1-1/2) times the regular rate of pay.
 - J. All hours worked between the hours of 10:00 pm and 5:00 am, Monday through Friday, and all hours worked on Saturdays shall be paid at a one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
 - K. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more. When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the eight (8) hours rest period.

Overtime Codes Continued

4. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

- A. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturdays, Sundays and holidays shall be paid at double the hourly rate of wage
- C. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay. On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay. All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.
- D. All hours worked in excess of eight (8) hours per day or forty (40) hours per week shall be paid at double the hourly rate of wage. All hours worked on Saturday, Sundays and holidays shall be paid at double the hourly rate of pay. Rates include all members of the assigned crew.

EXCEPTION:

On all multipole structures and steel transmission lines, switching stations, regulating, capacitor stations, generating plants, industrial plants, associated installations and substations, except those substations whose primary function is to feed a distribution system, will be paid overtime under the following rates:

The first two (2) hours after eight (8) regular hours Monday through Friday of overtime on a regular workday, shall be paid at one and one-half times the hourly rate of wage. All hours in excess of ten (10) hours will be at two (2) times the hourly rate of wage. The first eight (8) hours worked on Saturday will be paid at one and one-half (1-1/2) times the hourly rate of wage. All hours worked in excess of eight (8) hours on Saturday, and all hours worked on Sundays and holidays will be at the double the hourly rate of wage.

All overtime eligible hours performed on the above described work that is energized, shall be paid at the double the hourly rate of wage.

- E. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal four-day, ten hour work week, and Saturday shall be paid at one and one half (1½) times the regular shift rate for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- G. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- I. The First eight (8) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of eight (8) per day on Saturdays shall be paid at double the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Overtime Codes Continued

4. J. The first eight (8) hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked in excess of eight (8) hours on a Saturday shall be paid at double the hourly rate of wage. All hours worked over twelve (12) in a day, and all hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.
- K. All hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage, so long as Saturday is the sixth consecutive day worked. All hours worked over twelve (12) in a day Monday through Saturday, and all hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.
- L. The first twelve (12) hours worked on a Saturday shall be paid at one and one-half times the hourly rate of wage. All hours worked on a Saturday in excess of twelve (12) hours shall be paid at double the hourly rate of pay. All hours worked over twelve (12) in a day Monday through Friday, and all hours worked on Sundays shall be paid at double the hourly rate of wage. All hours worked on a holiday shall be paid at one and one-half times the hourly rate of wage, except that all hours worked on Labor Day shall be paid at double the hourly rate of pay.
- S. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, work performed in excess of (10) hours shall be paid at one and one half (1-1/2) times the hourly rate of pay. On Monday through Friday, work performed outside the normal work hours of 6:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations).
- All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All work performed on Sundays and holidays shall be paid at double the hourly rate of wage. When an employee returns to work without at least eight (8) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.
- Multiple Shift Operations: When the first shift of a multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. Special Shifts: The Special Shift Premium is the basic hourly rate of pay plus \$2.00 an hour. When due to conditions beyond the control of the employer or when an owner (not acting as the contractor), a government agency or the contract specifications require more than four (4) hours of a special shift can only be performed outside the normal 6am to 6pm shift then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they shall be paid the special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday).
- U. The first four (4) hours after eight (8) regular hours Monday through Friday and the first twelve (12) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. (Except on makeup days if work is lost due to inclement weather, then the first eight (8) hours on Saturday may be paid the regular rate.) All hours worked over twelve (12) hours Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.

Overtime Codes Continued

4. X. All hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays and holidays shall be paid at double the hourly rate of wage. Work performed outside the normal shift of 6 am to 6pm shall be paid at one and one-half the straight time rate, (except for special shifts or three shift operations). All work performed on Sundays and holidays shall be paid at double the hourly rate of wage. Shifts may be established when considered necessary by the Employer.

The Employer may establish shifts consisting of eight (8) or ten (10) hours of work (subject to WAC 296-127-022), that shall constitute a normal forty (40) hour work week. The Employer can change from a 5-eight to a 4-ten hour schedule or back to the other. All hours of work on these shifts shall be paid for at the straight time hourly rate. Work performed in excess of eight hours (or ten hours per day (subject to WAC 296-127-022) shall be paid at one and one-half the straight time rate.

When due to conditions beyond the control of the Employer, or when contract specifications require that work can only be performed outside the regular day shift, then by mutual agreement a special shift may be worked at the straight time rate, eight (8) hours work for eight (8) hours pay. The starting time shall be arranged to fit such conditions of work.

When an employee returns to work without at a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Overtime Codes Continued

11. ALL HOURS WORKED IN EXCESS OF EIGHT (8) HOURS PER DAY OR FORTY (40) HOURS PER WEEK SHALL BE PAID AT ONE AND ONE-HALF TIMES THE HOURLY RATE OF WAGE.

B After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

C The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other overtime hours worked, except Labor Day, and all hours on Sunday shall be paid at double the hourly rate of wage. All hours worked on Labor Day shall be paid at three times the hourly rate of wage. All non-overtime and non-holiday hours worked between 4:00 pm and 5:00 am, Monday through Friday, shall be paid at a premium rate of 15% over the hourly rate of wage.

D. All hours worked on Saturdays and holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked on Sundays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

E. The first two (2) hours after eight (8) regular hours Monday through Friday, the first ten (10) hours on Saturday, and the first ten (10) hours worked on Holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked over ten (10) hours Monday through Saturday, and Sundays shall be paid at double the hourly rate of wage.

After an employee has worked eight (8) hours, all additional hours worked shall be paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours or more.

Overtime Codes Continued

11. F. The first two (2) hours after eight (8) regular hours Monday through Friday and the first eight (8) hours on Saturday shall be paid at one and one-half times the hourly rate of wage. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- On a four-day, ten-hour weekly schedule, either Monday thru Thursday or Tuesday thru Friday schedule, all hours worked after ten shall be paid at double the hourly rate of wage. The Monday or Friday not utilized in the normal four-day, ten hour work week, and Saturday shall be paid at one-half times the hourly rate of wage for the first eight (8) hours. All other hours worked Monday through Saturday, and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- G. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage.
- All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.
- After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of nine (9) hours or more. When an employee returns to work without at least nine (9) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the nine (9) hours rest period.
- H. Work performed in excess of eight (8) hours of straight time per day, or ten (10) hours of straight time per day when four ten (10) hour shifts are established, or forty (40) hours of straight time per week, Monday through Friday, or outside the normal 5 am to 6pm shift, and all work on Saturdays shall be paid at one and one-half times the hourly rate of wage.
- All work performed after 6:00 pm Saturday to 5:00 am Monday and Holidays, and all hours worked in excess of twelve (12) hours in a single shift shall be paid at double the hourly rate of wage.
- After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of ten (10) hours or more. When an employee returns to work without at least ten (10) hours time off since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until he/she shall have the ten (10) hours rest period.
- J. All hours worked on holidays shall be paid at double the hourly rate of wage.
- K. On Monday through Friday hours worked outside 4:00 am and 5:00 pm, and the first two (2) hours after eight (8) hours worked shall be paid at one and one-half times the hourly rate. All hours worked over 10 hours per day Monday through Friday, and all hours worked on Saturdays, Sundays, and Holidays worked shall be paid at double the hourly rate of wage.
- L. An employee working outside 5:00 am and 5:00 pm shall receive an additional two dollar (\$2.00) per hour for all hours worked that shift. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage. All hours worked on holidays shall be paid at one and one-half times the hourly rate of wage.

Overtime Codes Continued

11. M. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.
- Work performed outside the normal work hours of 5:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations). When the first shift of a multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. When due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift of 5:00 am to 6:00 pm, then a special shift may be worked at the straight time rate, plus the shift pay premium when applicable. The starting time of work will be arranged to fit such conditions of work. Such shift shall consist of eight (8) hours work for eight (8) hours pay or ten (10) hours work for ten (10) hours pay for four ten shifts.
- On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay. All work performed after 6:00 pm Saturday to 5:00 am Monday, all work performed over twelve (12) hours, and all work performed on holidays shall be paid at double the straight time rate of pay.
- Shift Pay Premium: In an addition to any overtime already required, all hours worked between the hours of 6:00 pm and 5:00 am shall receive an additional two dollars (\$2.00) per hour.
- N. All work performed over twelve hours in a shift and all work performed on Sundays and Holidays shall be paid at double the straight time rate.
- Any time worked over eight (8) hours on Saturday shall be paid double the straight time rate, except employees assigned to work six 10-hour shifts per week shall be paid double the straight time rate for any time worked on Saturday over 10 hours.
- O. All work performed on Saturdays, Sundays, and Holidays shall be paid at one and one half (1-1/2) times the straight time rate of pay.

Overtime Codes Continued

11. P. Work performed in excess of ten (10) hours of straight time per day when four ten (10) hour shifts are established and all work on Saturdays, except for make-up days shall be paid at time and one-half (1 ½) the straight time rate.
- Work performed outside the normal work hours of 5:00 a.m. and 6:00 p.m. shall be paid at one and one-half (1-1/2) times the straight time rate, (except for special shifts or multiple shift operations). When the first shift of multiple shift (a two or three shift) operation is started at the basic straight time rate or at a specific overtime rate, all shifts of that day's operation shall be completed at that rate. When due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift of 5:00 a.m. to 6:00 p.m., then a special shift may be worked at the straight time rate, plus the shift pay premium when applicable. The starting time of work will be arranged to fit such conditions of work. Such shifts shall consist of eight (8) hours work for eight (8) hours pay or ten (10) hours work for ten (10) hours pay for four ten-hour shifts.
- In the event the job is down due to weather conditions, then Saturday may, be worked as a voluntary make-up day at the straight time rate. However, Saturday shall not be utilized as a make-up day when a holiday falls on Friday. All work performed on Sundays and holidays and work in excess of twelve (12) hours per day shall be paid at double (2x) the straight time rate of pay.
- After an employee has worked eight (8) hours at an applicable overtime rate, all additional hours shall be at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.
- When an employee returns to work without a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.
- Q. All hours worked between the hours of 6:00 pm and 6:00 am, Monday through Saturday, shall be paid at a premium rate of 35% over the hourly rate of wage. Work performed on Sundays shall be paid at double time. All hours worked on holidays shall be paid at double the hourly rate of wage.
- R. On Monday through Saturday hours worked outside 6:00 am and 7:00 pm, and all hours after eight (8) hours worked shall be paid at one and one-half times the hourly rate. All hours worked on Sundays and Holidays shall be paid at double the hourly rate of wage.
- When a holiday falls on a Saturday, the Friday before shall be the observed holiday. When a holiday falls on a Sunday, the following Monday shall be the observed holiday.
- S. The first ten (10) hours worked on Saturdays shall be paid at one and one-half times the hourly rate of wage. In the event the job is down due to weather conditions, or other conditions beyond the control of the Employer, then Saturday may be worked at the straight time rate, for the first eight (8) hours, or the first ten (10) hours when a four day ten hour workweek has been established.
- All hours worked Monday through Saturday over twelve (12) hours and all hours worked on Sundays and holidays shall be paid at double the hourly rate of wage.
- When an employee returns to work without a break of eight (8) hours since their previous shift, all such time shall be a continuation of shift and paid at the applicable overtime rate until such time as the employee has had a break of eight (8) hours.

Benefit Code Key – Effective 8/31/2024 thru 3/4/2025

11. T. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.
- On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay.
- All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.
- U. On Monday through Friday, the first four (4) hours of overtime after eight (8) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay, unless a four (4) day ten (10) hour workweek has been established. On a four (4) day ten (10) hour workweek scheduled Monday through Thursday, or Tuesday through Friday, the first two (2) hours of overtime after ten (10) hours of straight time work shall be paid at one and one half (1-1/2) times the straight time rate of pay.
- On Saturday, the first twelve (12) hours of work shall be paid at one and one half (1-1/2) times the straight time rate of pay, except that if the job is down on Monday through Friday due to weather conditions or other conditions outside the control of the employer, the first ten (10) hours on Saturday may be worked at the straight time rate of pay.
- All hours worked over twelve (12) hours in a day and all hours worked on Sunday and Holidays shall be paid at two (2) times the straight time rate of pay.
- If, due to conditions beyond the control of the Employer or when contract specifications require that work can only be performed outside the regular day shift, then a Special Shift may be worked, Monday through Friday, at the straight-time rate. The starting time of work for the Special Shift will be arranged to fit such conditions of work. Such Special Shift shall consist of eight (8) hours of work for eight (8) hours of pay or ten (10) hours of work for ten(10) hours of pay on a four-ten workday schedule.

Holiday Codes

5. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, and Christmas Day (7).
- B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, the day before Christmas, and Christmas Day (8).
- C. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).
- D. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8).
- H. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Day after Thanksgiving Day, And Christmas (6).

Holiday Codes Continued

- 5. I. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).
- K. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9).
- L. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (8).
- N. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, The Friday After Thanksgiving Day, And Christmas Day (9).
- P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday And Saturday After Thanksgiving Day, The Day Before Christmas, And Christmas Day (9). If A Holiday Falls On Sunday, The Following Monday Shall Be Considered As A Holiday.
- Q. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6).
- R. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Day After Thanksgiving Day, One-Half Day Before Christmas Day, And Christmas Day. (7 1/2).
- S. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, And Christmas Day (7).
- Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veterans Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8).

Holiday Codes Continued

- 6. G. Paid Holidays: New Year's Day, Martin Luther King Jr. Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Veterans' Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and Christmas Eve Day (11).
- H. Paid Holidays: New Year's Day, New Year's Eve Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday After Thanksgiving Day, Christmas Day, The Day After Christmas, And A Floating Holiday (10).
- T. Paid Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Last Working Day Before Christmas Day, And Christmas Day (9).
- Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). If a holiday falls on Saturday, the preceding Friday shall be considered as the holiday. If a holiday falls on Sunday, the following Monday shall be considered as the holiday.

Holiday Codes Continued

7. A. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any Holiday Which Falls On A Sunday Shall Be Observed As A Holiday On The Following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
- B. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- C. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- D. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (8). Unpaid Holidays: President's Day. Any paid holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any paid holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- E. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- F. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the last working day before Christmas day and Christmas day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

Holiday Codes Continued

7. G. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.
- H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- J. Holidays: New Year's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day and Christmas Day (6). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.

Holiday Codes Continued

7. K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- L. Holidays: New Year's Day, Memorial Day, Labor Day, Independence Day, Thanksgiving Day, the Last Work Day before Christmas Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- N. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. When Christmas falls on a Saturday, the preceding Friday shall be observed as a holiday.
- P. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, And Christmas Day (7). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.
- Q. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
- S. Paid Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, Friday after Thanksgiving Day, Christmas Day, the Day after Christmas, and A Floating Holiday (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.
- V. Holidays: New Year's Day, President's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, the day before or after Christmas, and the day before or after New Year's Day. If any of the above listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.
- W. Holidays: New Year's Day, Day After New Year's, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Eve Day, Christmas Day, the day after Christmas, the day before New Year's Day, and a Floating Holiday.
- X. Holidays: New Year's Day, Day before or after New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Day, and the day before or after Christmas day. If a holiday falls on a Saturday or on a Friday that is the normal day off, then the holiday will be taken on the last normal workday. If the holiday falls on a Monday that is the normal day off or on a Sunday, then the holiday will be taken on the next normal workday.
- Y. Holidays: New Year's Day, Presidents' Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day. (8) If the holiday falls on a Sunday, then the day observed by the federal government shall be considered a holiday and compensated accordingly.
- Z. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, Christmas Eve, and Christmas Day (9). Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday. Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

Holiday Codes Continued

15. G. New Year's Day, Washington's Birthday, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, the last scheduled workday before Christmas, and Christmas Day (9). If any of the listed holidays falls on a Sunday, the day observed by the Nation shall be considered a holiday and compensated accordingly.
- H. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, the Last Working Day before Christmas Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- I. Holidays: New Year's Day, President's Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, The Friday After Thanksgiving Day, The Day Before Christmas Day And Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- J. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
- K. Holidays: New Year's Day, Memorial Day, Independence Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, And Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. Any holiday which falls on a Saturday shall be observed as a holiday on the preceding Friday.
- L. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
- M. Holidays: New Year's Day, Martin Luther King Jr. Day, Independence Day, Memorial Day, Labor Day, Thanksgiving Day, the Friday after Thanksgiving Day, Christmas Eve Day and Christmas Day (9). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday. If any of the listed holidays falls on a Saturday, the preceding Friday shall be a regular work day.
- N. Holidays: New Year's Day, Memorial Day, Independence Day, Labor Day, Veteran's Day, Thanksgiving Day, the Friday after Thanksgiving Day, and Christmas Day (8). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.
- O. Holidays: New Year's Day, Martin Luther King Jr. Day, Memorial Day, Independence Day, Labor Day, Thanksgiving Day, the Friday and Saturday after Thanksgiving Day, the day before Christmas day, and Christmas Day (10). Any holiday which falls on a Sunday shall be observed as a holiday on the following Monday.

Benefit Code Key – Effective 8/31/2024 thru 3/4/2025

Note Codes

8. D. Workers working with supplied air on hazmat projects receive an additional \$1.00 per hour.
- L. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$0.75, Level B: \$0.50, And Level C: \$0.25.
- M. Workers on hazmat projects receive additional hourly premiums as follows: Levels A & B: \$1.00, Levels C & D: \$0.50.
- N. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$1.00, Level B: \$0.75, Level C: \$0.50, And Level D: \$0.25.
- S. Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.
- T. Effective August 31, 2012 – A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. This classification is only effective on or after August 31, 2012.
- U. Workers on hazmat projects receive additional hourly premiums as follows – Class A Suit: \$2.00, Class B Suit: \$1.50, And Class C Suit: \$1.00. Workers performing underground work receive an additional \$0.40 per hour for any and all work performed underground, including operating, servicing and repairing of equipment. The premium for underground work shall be paid for the entire shift worked. Workers who work suspended by a rope or cable receive an additional \$0.50 per hour. The premium for work suspended shall be paid for the entire shift worked. Workers who do “pioneer” work (break open a cut, build road, etc.) more than one hundred fifty (150) feet above grade elevation receive an additional \$0.50 per hour.
8. V. In addition to the hourly wage and fringe benefits, the following depth and enclosure premiums shall be paid. The premiums are to be calculated for the maximum depth and distance into an enclosure that a diver reaches in a day. The premiums are to be paid one time for the day and are not used in calculating overtime pay.
- Depth premiums apply to depths of fifty feet or more. Over 50' to 100' - \$2.00 per foot for each foot over 50 feet. Over 101' to 150' - \$3.00 per foot for each foot over 101 feet. Over 151' to 220' - \$4.00 per foot for each foot over 220 feet. Over 221' - \$5.00 per foot for each foot over 221 feet.
- Enclosure premiums apply when divers enter enclosures (such as pipes or tunnels) where there is no vertical ascent and is measured by the distance travelled from the entrance. 25' to 300' - \$1.00 per foot from entrance. 300' to 600' - \$1.50 per foot beginning at 300'. Over 600' - \$2.00 per foot beginning at 600'.
- W. Meter Installers work on single phase 120/240V self-contained residential meters. The Lineman/Groundmen rates would apply to meters not fitting this description.

Note Codes Continued

- X. Workers on hazmat projects receive additional hourly premiums as follows - Class A Suit: \$2.00, Class B Suit: \$1.50, Class C Suit: \$1.00, and Class D Suit: \$0.50. Special Shift Premium: Basic hourly rate plus \$2.00 per hour.

When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications requires that work can only be performed outside the normal 5 am to 6pm shift, then the special shift premium will be applied to the basic hourly rate. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in OT or Double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

- Y. Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay.

Swinging Stage/Boatswains Chair: Employees working on a swinging state or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

- Z. Workers working with supplied air on hazmat projects receive an additional \$1.00 per hour.

Special Shift Premium: Basic hourly rate plus \$2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as a contractor), a government agency or the contract specifications require that more than (4) hours of a special shift can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they will be paid a special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Note Codes Continued

9. A. Workers working with supplied air on hazmat projects receive an additional \$1.00 per hour.

Special Shift Premium: Basic hourly rate plus \$2.00 per hour. When due to conditions beyond the control of the Employer or when an owner (not acting as the contractor), a government agency or the contract specifications require that more than four (4) hours of a special shift can only be performed outside the normal 6 am to 6pm shift, then the special shift premium will be applied to the basic straight time for the entire shift. When an employee works on a special shift, they shall be paid a special shift premium for each hour worked unless they are in overtime or double-time status. (For example, the special shift premium does not waive the overtime requirements for work performed on Saturday or Sunday.)

Certified Crane Operator Premium: Crane operators requiring certifications shall be paid \$0.50 per hour above their classification rate.

Boom Pay Premium: All cranes including tower shall be paid as follows based on boom length:

- (A) – 130’ to 199’ – \$0.50 per hour over their classification rate.
- (B) – 200’ to 299’ – \$0.80 per hour over their classification rate.
- (C) – 300’ and over – \$1.00 per hour over their classification rate.

Note Codes Continued

9. B. The highest pressure registered on the gauge for an accumulated time of more than fifteen (15) minutes during the shift shall be used in determining the scale paid.

Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay. Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

- C. Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay. Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

Effective August 31, 2012 – A Traffic Control Supervisor shall be present on the project whenever flagging or spotting or other traffic control labor is being utilized. A Traffic Control Laborer performs the setup, maintenance and removal of all temporary traffic control devices and construction signs necessary to control vehicular, bicycle, and pedestrian traffic during construction operations. Flaggers and Spotters shall be posted where shown on approved Traffic Control Plans or where directed by the Engineer. All flaggers and spotters shall possess a current flagging card issued by the State of Washington, Oregon, Montana, or Idaho. These classifications are only effective on or after August 31, 2012.

- D. Industrial Painter wages are required for painting within industrial facilities such as treatment plants, pipelines, towers, dams, bridges, power generation facilities and manufacturing facilities such as chemical plants, etc., or anywhere abrasive blasting is necessary to prepare surfaces, or hazardous materials encapsulation is required.
- E. Heavy Construction includes construction, repair, alteration or additions to the production, fabrication or manufacturing portions of industrial or manufacturing plants, hydroelectric or nuclear power plants and atomic reactor construction. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$1.00, Level B: \$0.75, Level C: \$0.50, And Level D: \$0.25.
- F. Industrial Painter wages are required for painting within industrial facilities such as treatment plants, pipelines, towers, dams, power generation facilities and manufacturing facilities such as chemical plants, etc., or anywhere abrasive blasting is necessary to prepare surfaces, or hazardous materials encapsulation is required.
- H. One (1) person crew shall consist of a Party Chief. (Total Station or similar one (1) person survey system). Two (2) person survey party shall consist of a least a Party Chief and a Chain Person. Three (3) person survey party shall consist of at least a Party Chief, an Instrument Person, and a Chain Person.

Benefit Code Key – Effective 8/31/2024 thru 3/4/2025

9. I. In addition to the hourly wage and fringe benefits, the following depth and enclosure premiums shall be paid. The premiums are to be calculated for the maximum depth and distance into an enclosure that a diver reaches in a day. The premiums are to be paid one time for the day and are not used in calculating overtime pay.

Depth premiums apply to depths of fifty feet or more. Over 50' to 100' - \$2.00 per foot for each foot over 50 feet. Over 101' to 150' - \$3.00 per foot for each foot over 101 feet. Over 151' to 220' - \$4.00 per foot for each foot over 220 feet. Over 221' - \$5.00 per foot for each foot over 221 feet.

Enclosure premiums apply when divers enter enclosures (such as pipes or tunnels) where there is no vertical ascent and is measured by the distance travelled from the entrance. 25' to 300' - \$1.00 per foot from entrance. 300' to 600' - \$1.50 per foot beginning at 300'. Over 600' - \$2.00 per foot beginning at 600'.

Employees may be required to perform any combination of work within the Diving team/crew, (with the exception of dive Supervisor) provided they are paid at the highest rate at which he/she has worked for the shift.

- L. Workers on hazmat projects receive additional hourly premiums as follows -Level A: \$0.75, Level B: \$0.50, And Level C: \$0.25.

Tide Work: When employees are called out between the hours of 6:00 p.m. and 6:00 a.m. to work on tide work (work located in the tide plane) all time worked shall be at one and one-half times the hourly rate of pay.

Swinging Stage/Boatswains Chair: Employees working on a swinging stage or boatswains chair or under conditions that require them to be tied off to allow their hands to be free shall receive seventy-five cents (\$0.75) per hour above the classification rate.

State of Washington
 Department of Labor & Industries
 Prevailing Wage Section - Telephone 360-902-5335
 PO Box 44540, Olympia, WA 98504-4540

Washington State Prevailing Wage

The PREVAILING WAGES listed here include both the hourly wage rate and the hourly rate of fringe benefits. On public works projects, worker's wage and benefit rates must add to not less than this total. A brief description of overtime calculation requirements are provided on the Benefit Code Key.

Journey Level Prevailing Wage Rates for the Effective Date: 2/14/2025

King County

Trade [^]	Job Classification	Wage	Holiday	Overtime	Note
<u>Asbestos Abatement Workers</u>	Journey Level	\$63.87	5D	1H	
<u>Boilermakers</u>	Journey Level	\$76.89	5N	1C	
<u>Brick Mason</u>	Journey Level	\$71.82	7E	1N	
<u>Brick Mason</u>	Pointer-Caulker-Cleaner	\$71.82	7E	1N	
<u>Building Service Employees</u>	Janitor	\$30.33	5S	2F	
<u>Building Service Employees</u>	Traveling Waxer/Shampooer	\$30.78	5S	2F	

<u>Building Service Employees</u>	Window Cleaner (Non-Scaffold)	\$32.93	5S	2F	
<u>Building Service Employees</u>	Window Cleaner (Scaffold)	\$33.93	5S	2F	
<u>Cabinet Makers (In Shop)</u>	Journey Level	\$22.74		1	
<u>Carpenters</u>	Acoustical Worker	\$78.96	15J	11U	
<u>Carpenters</u>	Bridge Dock and Wharf Carpenter	\$80.50	15J	11U	9L
<u>Carpenters</u>	Floor Layer & Floor Finisher	\$78.96	15J	11U	
<u>Carpenters</u>	General Carpenter	\$78.96	15J	11U	
<u>Carpenters</u>	Scaffold Erector	\$78.96	15J	11U	
<u>Cement Masons</u>	Application of all Composition Mastic	\$77.30	15J	4U	
<u>Cement Masons</u>	Application of all Epoxy Material	\$76.78	15J	4U	
<u>Cement Masons</u>	Application of all Plastic Material	\$77.30	15J	4U	
<u>Cement Masons</u>	Application of Sealing Compound	\$76.78	15J	4U	
<u>Cement Masons</u>	Application of Underlayment	\$77.30	15J	4U	
<u>Cement Masons</u>	Building General	\$76.78	15J	4U	

<u>Cement Masons</u>	Composition or Kalman Floors	\$77.30	15J	4U
<u>Cement Masons</u>	Concrete Paving	\$76.78	15J	4U
<u>Cement Masons</u>	Curb & Gutter Machine	\$77.30	15J	4U
<u>Cement Masons</u>	Curb & Gutter, Sidewalks	\$76.78	15J	4U
<u>Cement Masons</u>	Curing Concrete	\$76.78	15J	4U
<u>Cement Masons</u>	Finish Colored Concrete	\$77.30	15J	4U
<u>Cement Masons</u>	Floor Grinding	\$77.30	15J	4U
<u>Cement Masons</u>	Floor Grinding/Polisher	\$76.78	15J	4U
<u>Cement Masons</u>	Green Concrete Saw, self- powered	\$77.30	15J	4U
<u>Cement Masons</u>	Grouting of all Plates	\$76.78	15J	4U
<u>Cement Masons</u>	Grouting of all Tilt-up Panels	\$76.78	15J	4U
<u>Cement Masons</u>	Guniting Nozzleman	\$77.30	15J	4U
<u>Cement Masons</u>	Hand Powered Grinder	\$77.30	15J	4U
<u>Cement Masons</u>	Journey Level	\$76.78	15J	4U
<u>Cement Masons</u>	Patching Concrete	\$76.78	15J	4U
<u>Cement Masons</u>	Pneumatic Power Tools	\$77.30	15J	4U

<u>Cement Masons</u>	Power Chipping & Brushing	\$77.30	15J	4U	
<u>Cement Masons</u>	Sand Blasting Architectural Finish	\$77.30	15J	4U	
<u>Cement Masons</u>	Screed & Rodding Machine	\$77.30	15J	4U	
<u>Cement Masons</u>	Spackling or Skim Coat Concrete	\$76.78	15J	4U	
<u>Cement Masons</u>	Troweling Machine Operator	\$77.30	15J	4U	
<u>Cement Masons</u>	Troweling Machine Operator on Colored Slabs	\$77.30	15J	4U	
<u>Cement Masons</u>	Tunnel Workers	\$77.30	15J	4U	
<u>Divers & Tenders</u>	Bell/Vehicle/Submersible Operator (not under pressure)	\$156.25	15J	11T	9I
<u>Divers & Tenders</u>	Dive Supervisor	\$157.75	15J	11T	9I
<u>Divers & Tenders</u>	Diver	\$156.25	15J	11T	9I
<u>Divers & Tenders</u>	Diver Tender	\$86.86	15J	11T	9I
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker 0-30.00 PSI	\$109.76	15J	11U	
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$118.99	15J	11U	

31.01-44.00 PSI

<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$128.22	15J	11U	
	44.01 - 54.00 PSI				
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$137.45	15J	11U	
	54.01 - 60.00 PSI				
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$146.67	15J	11U	
	60.01 - 64.00 PSI				
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$155.90	15J	11U	
	64.01 - 68.00 PSI				
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$165.13	15J	11U	
	68.01 - 70.00 PSI				
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$174.36	15J	11U	
	70.01 - 72.00 PSI				
<u>Divers & Tenders</u>	Hyperbaric Worker - Compressed Air Worker	\$183.59	15J	11U	
	72.01 - 74.00 PSI				
<u>Divers & Tenders</u>	Lead Diver (Dive Master)	\$101.32	15J	11T	9I
<u>Divers & Tenders</u>	Manifold Operator (Life Support Technician)	\$86.86	15J	11T	9I

<u>Divers & Tenders</u>	Remote Operated Vehicle Operator/Technician	\$86.86	15J	11T	9I
<u>Divers & Tenders</u>	Remote Operated Vehicle Operator/Technician	\$86.86	15J	11T	9I
<u>Divers & Tenders</u>	Remote Operated Vehicle Tender	\$80.55	15J	11T	9I
<u>Divers & Tenders</u>	Stand-by Diver	\$96.32	15J	11T	9I
Dredge Workers	Assistant Engineer	\$83.92	5D	3F	
Dredge Workers	Assistant Mate (Deckhand)	\$83.28	5D	3F	
Dredge Workers	Boatmen	\$83.92	5D	3F	
Dredge Workers	Engineer Welder	\$85.53	5D	3F	
Dredge Workers	Leverman, Hydraulic	\$87.24	5D	3F	
Dredge Workers	Mates	\$83.92	5D	3F	
Dredge Workers	Oiler	\$83.28	5D	3F	
<u>Drywall Applicator</u>	Journey Level	\$78.76	150	11S	
<u>Drywall Tapers</u>	Journey Level	\$78.76	150	11S	
<u>Electrical Fixture Maintenance Workers</u>	Journey Level	\$38.69	5L	1E	
<u>Electricians - Inside</u>	Cable Splicer	\$112.00	7C	4E	

<u>Electricians - Inside</u>	Cable Splicer (tunnel)	\$120.33	7C	4E
<u>Electricians - Inside</u>	Certified Welder	\$110.21	7C	4E
<u>Electricians - Inside</u>	Certified Welder (tunnel)	\$116.17	7C	4E
<u>Electricians - Inside</u>	Construction Stock Person	\$51.53	7C	4E
<u>Electricians - Inside</u>	Journey Level	\$104.42	7C	4E
<u>Electricians - Inside</u>	Journey Level (tunnel)	\$112.00	7C	4E
<u>Electricians - Motor Shop</u>	Journey Level	\$48.68	5A	1B
<u>Electricians - Powerline Construction</u>	Cable Splicer	\$97.76	5A	4D
<u>Electricians - Powerline Construction</u>	Certified Line Welder	\$89.71	5A	4D
<u>Electricians - Powerline Construction</u>	Groundperson	\$56.79	5A	4D
<u>Electricians - Powerline Construction</u>	Heavy Line Equipment Operator	\$89.71	5A	4D
<u>Electricians - Powerline Construction</u>	Journey Level Lineperson	\$89.71	5A	4D
<u>Electricians - Powerline Construction</u>	Line Equipment Operator	\$77.13	5A	4D
<u>Electricians - Powerline Construction</u>	Meter Installer	\$56.79	5A	4D 8W

<u>Electricians - Powerline Construction</u>	Pole Sprayer	\$89.71	5A	4D	
<u>Electricians - Powerline Construction</u>	Powderperson	\$66.84	5A	4D	
<u>Electronic Technicians</u>	Journey Level	\$67.16	7E	1E	
<u>Elevator Constructors</u>	Mechanic	\$111.26	7D	4A	
<u>Elevator Constructors</u>	Mechanic In Charge	\$120.27	7D	4A	
<u>Fabricated Precast Concrete Products</u>	All Classifications - In-Factory Work Only	\$21.34	5B	1R	
<u>Fence Erectors</u>	Fence Erector	\$54.65	15J	11P	8Y
<u>Fence Erectors</u>	Fence Laborer	\$54.65	15J	11P	8Y
<u>Flaggers</u>	Journey Level	\$54.65	15J	11P	8Y
<u>Glaziers</u>	Journey Level	\$82.16	7L	1Y	
<u>Heat & Frost Insulators And Asbestos Workers</u>	Journey Level	\$91.81	15H	11C	
<u>Heating Equipment Mechanics</u>	Journey Level	\$99.92	7F	1E	
<u>Hod Carriers & Mason Tenders</u>	Journey Level	\$67.38	15J	11P	8Y
<u>Industrial Power Vacuum Cleaner</u>	Journey Level	\$16.66		1	
<u>Inland Boatmen</u>	Boat Operator	\$61.41	5B	1K	

<u>Inland Boatmen</u>	Cook	\$56.48	5B	1K
<u>Inland Boatmen</u>	Deckhand	\$57.48	5B	1K
<u>Inland Boatmen</u>	Deckhand Engineer	\$58.81	5B	1K
<u>Inland Boatmen</u>	Launch Operator	\$58.89	5B	1K
<u>Inland Boatmen</u>	Mate	\$57.31	5B	1K
<u>Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control</u>	Cleaner Operator	\$51.27	15M	110
<u>Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control</u>	Foamer Operator	\$51.27	15M	110
<u>Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control</u>	Grout Truck Operator	\$51.27	15M	110
<u>Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control</u>	Head Operator	\$49.20	15M	110
<u>Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control</u>	Technician	\$42.99	15M	110
<u>Inspection/Cleaning/Sealing Of Sewer & Water Systems By Remote Control</u>	TV Truck Operator	\$46.10	15M	110
<u>Insulation Applicators</u>	Journey Level	\$78.96	15J	11U

<u>Ironworkers</u>	Journeyman	\$90.82	15K	11N	
<u>Laborers</u>	Air, Gas Or Electric Vibrating Screed	\$63.87	15J	11P	8Y
<u>Laborers</u>	Airtrac Drill Operator	\$65.75	15J	11P	8Y
<u>Laborers</u>	Ballast Regular Machine	\$63.87	15J	11P	8Y
<u>Laborers</u>	Batch Weighman	\$54.65	15J	11P	8Y
<u>Laborers</u>	Brick Pavers	\$63.87	15J	11P	8Y
<u>Laborers</u>	Brush Cutter	\$63.87	15J	11P	8Y
<u>Laborers</u>	Brush Hog Feeder	\$63.87	15J	11P	8Y
<u>Laborers</u>	Burner	\$63.87	15J	11P	8Y
<u>Laborers</u>	Caisson Worker	\$65.75	15J	11P	8Y
<u>Laborers</u>	Carpenter Tender	\$63.87	15J	11P	8Y
<u>Laborers</u>	Cement Dumper-paving	\$64.98	15J	11P	8Y
<u>Laborers</u>	Cement Finisher Tender	\$63.87	15J	11P	8Y
<u>Laborers</u>	Change House Or Dry Shack	\$63.87	15J	11P	8Y
<u>Laborers</u>	Chipping Gun (30 Lbs. And Over)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Chipping Gun (Under 30 Lbs.)	\$63.87	15J	11P	8Y

<u>Laborers</u>	Choker Setter	\$63.87	15J	11P	8Y
<u>Laborers</u>	Chuck Tender	\$63.87	15J	11P	8Y
<u>Laborers</u>	Clary Power Spreader	\$64.98	15J	11P	8Y
<u>Laborers</u>	Clean-up Laborer	\$63.87	15J	11P	8Y
<u>Laborers</u>	Concrete Dumper/Chute Operator	\$64.98	15J	11P	8Y
<u>Laborers</u>	Concrete Form Stripper	\$63.87	15J	11P	8Y
<u>Laborers</u>	Concrete Placement Crew	\$64.98	15J	11P	8Y
<u>Laborers</u>	Concrete Saw Operator/Core Driller	\$64.98	15J	11P	8Y
<u>Laborers</u>	Crusher Feeder	\$54.65	15J	11P	8Y
<u>Laborers</u>	Curing Laborer	\$63.87	15J	11P	8Y
<u>Laborers</u>	Demolition: Wrecking & Moving (Incl. Charred Material)	\$63.87	15J	11P	8Y
<u>Laborers</u>	Ditch Digger	\$63.87	15J	11P	8Y
<u>Laborers</u>	Diver	\$65.75	15J	11P	8Y
<u>Laborers</u>	Drill Operator (Hydraulic, Diamond)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Dry Stack Walls	\$63.87	15J	11P	8Y

<u>Laborers</u>	Dump Person	\$63.87	15J	11P	8Y
<u>Laborers</u>	Epoxy Technician	\$63.87	15J	11P	8Y
<u>Laborers</u>	Erosion Control Worker	\$63.87	15J	11P	8Y
<u>Laborers</u>	Faller & Bucker Chain Saw	\$64.98	15J	11P	8Y
<u>Laborers</u>	Fine Graders	\$63.87	15J	11P	8Y
<u>Laborers</u>	Firewatch	\$54.65	15J	11P	8Y
<u>Laborers</u>	Form Setter	\$64.98	15J	11P	8Y
<u>Laborers</u>	Gabian Basket Builders	\$63.87	15J	11P	8Y
<u>Laborers</u>	General Laborer	\$63.87	15J	11P	8Y
<u>Laborers</u>	Grade Checker & Transit Person	\$67.38	15J	11P	8Y
<u>Laborers</u>	Grinders	\$63.87	15J	11P	8Y
<u>Laborers</u>	Grout Machine Tender	\$63.87	15J	11P	8Y
<u>Laborers</u>	Groutmen (Pressure) Including Post Tension Beams	\$64.98	15J	11P	8Y
<u>Laborers</u>	Guardrail Erector	\$63.87	15J	11P	8Y
<u>Laborers</u>	Hazardous Waste Worker (Level A)	\$65.75	15J	11P	8Y

<u>Laborers</u>	Hazardous Waste Worker (Level B)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Hazardous Waste Worker (Level C)	\$63.87	15J	11P	8Y
<u>Laborers</u>	High Scaler	\$65.75	15J	11P	8Y
<u>Laborers</u>	Jackhammer	\$64.98	15J	11P	8Y
<u>Laborers</u>	Laserbeam Operator	\$64.98	15J	11P	8Y
<u>Laborers</u>	Maintenance Person	\$63.87	15J	11P	8Y
<u>Laborers</u>	Manhole Builder-Mudman	\$64.98	15J	11P	8Y
<u>Laborers</u>	Material Yard Person	\$63.87	15J	11P	8Y
<u>Laborers</u>	Mold Abatement Worker	\$63.87	15J	11P	8Y
<u>Laborers</u>	Motorman-Dinky Locomotive	\$67.48	15J	11P	8Y
<u>Laborers</u>	nozzleman (concrete pump, green cutter when using combination of high pressure air & water on concrete & rock, sandblast, gunite, shotcrete, water blaster, vacuum blaster)	\$67.38	15J	11P	8Y
<u>Laborers</u>	Pavement Breaker	\$64.98	15J	11P	8Y

<u>Laborers</u>	Pilot Car	\$54.65	15J	11P	8Y
<u>Laborers</u>	Pipe Layer (Lead)	\$67.38	15J	11P	8Y
<u>Laborers</u>	Pipe Layer/Tailor	\$64.98	15J	11P	8Y
<u>Laborers</u>	Pipe Pot Tender	\$64.98	15J	11P	8Y
<u>Laborers</u>	Pipe Reliner	\$64.98	15J	11P	8Y
<u>Laborers</u>	Pipe Wrapper	\$64.98	15J	11P	8Y
<u>Laborers</u>	Pot Tender	\$63.87	15J	11P	8Y
<u>Laborers</u>	Powderman	\$65.75	15J	11P	8Y
<u>Laborers</u>	Powderman's Helper	\$63.87	15J	11P	8Y
<u>Laborers</u>	Power Jacks	\$64.98	15J	11P	8Y
<u>Laborers</u>	Railroad Spike Puller - Power	\$64.98	15J	11P	8Y
<u>Laborers</u>	Raker - Asphalt	\$67.38	15J	11P	8Y
<u>Laborers</u>	Re-timberman	\$65.75	15J	11P	8Y
<u>Laborers</u>	Remote Equipment Operator	\$64.98	15J	11P	8Y
<u>Laborers</u>	Rigger/Signal Person	\$64.98	15J	11P	8Y
<u>Laborers</u>	Rip Rap Person	\$63.87	15J	11P	8Y

<u>Laborers</u>	Rivet Buster	\$64.98	15J	11P	8Y
<u>Laborers</u>	Rodder	\$64.98	15J	11P	8Y
<u>Laborers</u>	Scaffold Erector	\$63.87	15J	11P	8Y
<u>Laborers</u>	Scale Person	\$63.87	15J	11P	8Y
<u>Laborers</u>	Sloper (Over 20")	\$64.98	15J	11P	8Y
<u>Laborers</u>	Sloper Sprayer	\$63.87	15J	11P	8Y
<u>Laborers</u>	Spreader (Concrete)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Stake Hopper	\$63.87	15J	11P	8Y
<u>Laborers</u>	Stock Piler	\$63.87	15J	11P	8Y
<u>Laborers</u>	Swinging Stage/Boatswain Chair	\$54.65	15J	11P	8Y
<u>Laborers</u>	Tamper & Similar Electric, Air & Gas Operated Tools	\$64.98	15J	11P	8Y
<u>Laborers</u>	Tamper (Multiple & Self- propelled)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Timber Person - Sewer (Lagger, Shorer & Cribber)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Toolroom Person (at Jobsite)	\$63.87	15J	11P	8Y
<u>Laborers</u>	Topper	\$63.87	15J	11P	8Y

<u>Laborers</u>	Track Laborer	\$63.87	15J	11P	8Y
<u>Laborers</u>	Track Liner (Power)	\$64.98	15J	11P	8Y
<u>Laborers</u>	Traffic Control Laborer	\$58.20	15J	11P	9C
<u>Laborers</u>	Traffic Control Supervisor	\$61.47	15J	11P	9C
<u>Laborers</u>	Truck Spotter	\$63.87	15J	11P	8Y
<u>Laborers</u>	Tugger Operator	\$64.98	15J	11P	8Y
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 0-30 psi	\$200.40	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 30.01-44.00 psi	\$205.43	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 44.01-54.00 psi	\$209.11	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 54.01-60.00 psi	\$214.81	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 60.01-64.00 psi	\$216.93	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 64.01-68.00 psi	\$222.03	15J	11P	9B

<u>Laborers</u>	Tunnel Work-Compressed Air Worker 68.01-70.00 psi	\$223.93	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 70.01-72.00 psi	\$225.93	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Compressed Air Worker 72.01-74.00 psi	\$227.93	15J	11P	9B
<u>Laborers</u>	Tunnel Work-Guage and Lock Tender	\$67.48	15J	11P	8Y
<u>Laborers</u>	Tunnel Work-Miner	\$67.48	15J	11P	8Y
<u>Laborers</u>	Vibrator	\$64.98	15J	11P	8Y
<u>Laborers</u>	Vinyl Seamer	\$63.87	15J	11P	8Y
<u>Laborers</u>	Watchman	\$49.97	15J	11P	8Y
<u>Laborers</u>	Welder	\$64.98	15J	11P	8Y
<u>Laborers</u>	Well Point Laborer	\$64.98	15J	11P	8Y
<u>Laborers</u>	Window Washer/Cleaner	\$49.97	15J	11P	8Y
<u>Laborers - Underground Sewer & Water</u>	General Laborer & Topman	\$63.87	15J	11P	8Y
<u>Laborers - Underground Sewer & Water</u>	Pipe Layer	\$64.98	15J	11P	8Y

	Landscape				
<u>Landscape Construction</u>	Construction/Landscaping Or Planting Laborers	\$49.97	15J	11P	8Y
<u>Landscape Construction</u>	Landscape Operator	\$86.05	15J	11G	8X
<u>Landscape Maintenance</u>	Groundskeeper	\$17.87		1	
<u>Lathers</u>	Journey Level	\$78.76	15O	11S	
<u>Marble Setters</u>	Journey Level	\$71.82	7E	1N	
<u>Metal Fabrication (In Shop)</u>	Fitter/Certified Welder	\$42.17	15I	11E	
<u>Metal Fabrication (In Shop)</u>	General Laborer	\$30.07	15I	11E	
<u>Metal Fabrication (In Shop)</u>	Mechanic	\$43.63	15I	11E	
<u>Metal Fabrication (In Shop)</u>	Welder/Burner	\$39.28	15I	11E	
<u>Millwright</u>	Journey Level	\$80.28	5A	1B	
Modular Buildings	Cabinet Assembly	\$16.66		1	
Modular Buildings	Electrician	\$16.66		1	
Modular Buildings	Equipment Maintenance	\$16.66		1	
Modular Buildings	Plumber	\$16.66		1	
Modular Buildings	Production Worker	\$16.66		1	
Modular Buildings	Tool Maintenance	\$16.66		1	

Modular Buildings	Utility Person	\$16.66		1	
Modular Buildings	Welder	\$16.66		1	
<u>Painters</u>	Journey Level	\$54.71	6Z	11J	
<u>Pile Driver</u>	Crew Tender	\$86.81	15J	11U	9L
<u>Pile Driver</u>	Journey Level	\$80.50	15J	11U	9L
<u>Plasterers</u>	Journey Level	\$73.54	7Q	1R	
<u>Plasterers</u>	Nozzleman	\$77.54	7Q	1R	
<u>Playground & Park Equipment Installers</u>	Journey Level	\$16.66		1	
<u>Plumbers & Pipefitters</u>	Journey Level	\$105.59	6Z	1G	
<u>Power Equipment Operators</u>	Asphalt Plant Operators	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Assistant Engineer	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Barrier Machine (zipper)	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Batch Plant Operator: concrete	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Boat Operator	\$87.82	7A	11H	8X
<u>Power Equipment Operators</u>	Bobcat	\$82.29	15J	11G	8X

<u>Power Equipment Operators</u>	Brokk - Remote Demolition Equipment	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Brooms	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Bump Cutter	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Cableways	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Chipper	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Compressor	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Concrete Finish Machine - Laser Screed	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Concrete Pump - Mounted Or Trailer High Pressure Line Pump, Pump High Pressure	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Concrete Pump: Truck Mount With Boom Attachment Over 42 M	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Concrete Pump: Truck Mount With Boom Attachment Up To 42m	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Conveyors	\$86.05	15J	11G	8X

<u>Power Equipment Operators</u>	Cranes Friction: 200 tons and over	\$90.46	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes, A-frame: 10 tons and under	\$82.59	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: 100 tons through 199 tons, or 150' of boom (including jib with attachments)	\$88.67	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: 20 tons through 44 tons with attachments	\$87.03	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: 200 tons- 299 tons, or 250' of boom including jib with attachments	\$89.60	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: 300 tons and over or 300' of boom including jib with attachments	\$90.46	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: 45 tons through 99 tons, under 150' of boom(including jib with attachments)	\$87.82	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: Friction cranes through 199 tons	\$89.60	7A	11H	8X
<u>Power Equipment Operators</u>	Cranes: through 19 tons with attachments, a-frame over 10 tons	\$86.36	7A	11H	8X

<u>Power Equipment Operators</u>	Crusher	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Deck Engineer/Deck Winches (power)	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Derricks, On Building Work	\$87.82	7A	11H	8X
<u>Power Equipment Operators</u>	Dozers D-9 & Under	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Drill Oilers: Auger Type, Truck Or Crane Mount	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Drilling Machine	\$88.36	15J	11G	8X
<u>Power Equipment Operators</u>	Elevator and man-lift: permanent and shaft type	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Finishing Machine, Bidwell And Gamaco & Similar Equipment	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Forklift: 3000 lbs and over with attachments	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Forklifts: under 3000 lbs. with attachments	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Grade Engineer: Using Blue Prints, Cut Sheets, Etc	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Gradechecker/Stakeman	\$82.29	15J	11G	8X

<u>Power Equipment Operators</u>	Guardrail Punch	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Hard Tail End Dump Articulating Off- Road Equipment 45 Yards. & Over	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Hard Tail End Dump Articulating Off-road Equipment Under 45 Yards	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Horizontal/Directional Drill Locator	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Horizontal/Directional Drill Operator	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Hydralifts/Boom Trucks Over 10 Tons	\$86.36	7A	11H	8X
<u>Power Equipment Operators</u>	Hydralifts/boom trucks: 10 tons and under	\$82.59	7A	11H	8X
<u>Power Equipment Operators</u>	Leverman	\$89.27	15J	11G	8X
<u>Power Equipment Operators</u>	Loader, Overhead, 6 Yards. But Not Including 8 Yards	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Loaders, Overhead Under 6 Yards	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Loaders, Plant Feed	\$86.71	15J	11G	8X

<u>Power Equipment Operators</u>	Loaders: Elevating Type Belt	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Locomotives, All	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Material Transfer Device	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Mechanics: All (Leadmen - \$0.50 per hour over mechanic)	\$88.36	15J	11G	8X
<u>Power Equipment Operators</u>	Motor Patrol Graders	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Mucking Machine, Mole, Tunnel Drill, Boring, Road Header And/or Shield	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Oil Distributors, Blower Distribution & Mulch Seeding Operator	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Outside Hoists (Elevators and Manlifts), Air Tuggers, Strato	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Overhead, bridge type Crane: 20 tons through 44 tons	\$87.03	7A	11H	8X
<u>Power Equipment Operators</u>	Overhead, bridge type: 100 tons and over	\$88.67	7A	11H	8X

<u>Power Equipment Operators</u>	Overhead, bridge type: 45 tons through 99 tons	\$87.82	7A	11H	8X
<u>Power Equipment Operators</u>	Pavement Breaker	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Pile Driver (other Than Crane Mount)	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Plant Oiler - Asphalt, Crusher	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Posthole Digger, Mechanical	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Power Plant	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Pumps - Water	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Quad 9, Hd 41, D10 And Over	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Quick Tower: no cab, under 100 feet in height base to boom	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Remote Control Operator On Rubber Tired Earth Moving Equipment	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Rigger and Bellman	\$82.59	7A	11H	8X
<u>Power Equipment Operators</u>	Rigger/Signal Person, Bellman(Certified)	\$86.36	7A	11H	8X

<u>Power Equipment Operators</u>	Rollagon	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Roller, Other Than Plant Mix	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Roller, Plant Mix Or Multi-lift Materials	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Roto-mill, Roto-grinder	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Saws - Concrete	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Scraper, Self Propelled Under 45 Yards	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Scrapers - Concrete & Carry All	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Scrapers, Self-propelled: 45 Yards And Over	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Service Engineers: Equipment	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Shotcrete/Gunite Equipment	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Shovel, Excavator, Backhoe, Tractors Under 15 Metric Tons	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Shovel, Excavator, Backhoe: Over 30 Metric Tons To 50 Metric Tons	\$87.49	15J	11G	8X

<u>Power Equipment Operators</u>	Shovel, Excavator, Backhoes, Tractors: 15 To 30 Metric Tons	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Shovel, Excavator, Backhoes: Over 50 Metric Tons To 90 Metric Tons	\$88.36	15J	11G	8X
<u>Power Equipment Operators</u>	Shovel, Excavator, Backhoes: Over 90 Metric Tons	\$89.27	15J	11G	8X
<u>Power Equipment Operators</u>	Slipform Pavers	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Spreader, Topsider & Screedman	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Subgrader Trimmer	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Tower Bucket Elevators	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Tower Crane: over 175' through 250' in height, base to boom	\$89.60	7A	11H	8X
<u>Power Equipment Operators</u>	Tower crane: up to 175' in height base to boom	\$88.67	7A	11H	8X
<u>Power Equipment Operators</u>	Tower Cranes: over 250' in height from base to boom	\$90.46	7A	11H	8X
<u>Power Equipment Operators</u>	Transporters, All Track Or Truck Type	\$87.49	15J	11G	8X

<u>Power Equipment Operators</u>	Trenching Machines	\$86.05	15J	11G	8X
<u>Power Equipment Operators</u>	Truck Crane Oiler/Driver: 100 tons and over	\$87.03	7A	11H	8X
<u>Power Equipment Operators</u>	Truck crane oiler/driver: under 100 tons	\$86.36	7A	11H	8X
<u>Power Equipment Operators</u>	Truck Mount Portable Conveyor	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Vac Truck (Vactor Guzzler, Hydro Excavator)	\$86.71	15J	11G	8X
<u>Power Equipment Operators</u>	Welder	\$87.49	15J	11G	8X
<u>Power Equipment Operators</u>	Wheel Tractors, Farmall Type	\$82.29	15J	11G	8X
<u>Power Equipment Operators</u>	Yo Yo Pay Dozer	\$86.71	15J	11G	8X
<u>Power Equipment Operators- Underground Sewer & Water</u>	Asphalt Plant Operators	\$87.49	15J	11G	8X
<u>Power Equipment Operators- Underground Sewer & Water</u>	Assistant Engineer	\$82.29	15J	11G	8X
<u>Power Equipment Operators- Underground Sewer & Water</u>	Barrier Machine (zipper)	\$86.71	15J	11G	8X

<u>Power Equipment</u>	Batch Plant Operator,				
<u>Operators- Underground</u>	Concrete	\$86.71	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Boat Operator	\$87.82	7A	11H	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Bobcat	\$82.29	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Brokk - Remote	\$82.29	15J	11G	8X
<u>Operators- Underground</u>	Demolition Equipment				
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Brooms	\$82.29	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Bump Cutter	\$86.71	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Cableways	\$87.49	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Chipper	\$86.71	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Compressor	\$82.29	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					

<u>Power Equipment</u>	Concrete Finish Machine -				
<u>Operators- Underground</u>	Laser Screed	\$82.29	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Concrete Pump - Mounted				
<u>Operators- Underground</u>	Or Trailer High Pressure	\$86.05	15J	11G	8X
<u>Sewer & Water</u>	Line Pump, Pump High Pressure				
<u>Power Equipment</u>	Concrete Pump: Truck				
<u>Operators- Underground</u>	Mount With Boom	\$87.49	15J	11G	8X
<u>Sewer & Water</u>	Attachment Over 42 M				
<u>Power Equipment</u>	Concrete Pump: Truck				
<u>Operators- Underground</u>	Mount With Boom	\$86.71	15J	11G	8X
<u>Sewer & Water</u>	Attachment Up To 42m				
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Conveyors	\$86.05	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Cranes Friction: 200 tons and over	\$90.46	7A	11H	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Cranes, A-frame: 10 tons and under	\$82.59	7A	11H	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Cranes: 100 tons through 199 tons, or 150' of boom (including jib with attachments)	\$88.67	7A	11H	8X
<u>Sewer & Water</u>					

<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Cranes: 20 tons through 44 tons with attachments	\$87.03	7A	11H	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Cranes: 200 tons- 299 tons, or 250' of boom including jib with attachments	\$89.60	7A	11H	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Cranes: 300 tons and over or 300' of boom including jib with attachments	\$90.46	7A	11H	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Cranes: 45 tons through 99 tons, under 150' of boom(including jib with attachments)	\$87.82	7A	11H	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Cranes: Friction cranes through 199 tons	\$89.60	7A	11H	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Cranes: through 19 tons with attachments, a-frame over 10 tons	\$86.36	7A	11H	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Crusher	\$86.71	15J	11G	8X
<u>Power Equipment</u> <u>Operators- Underground</u> <u>Sewer & Water</u>	Deck Engineer/Deck Winches (power)	\$86.71	15J	11G	8X

<u>Power Equipment</u>	Derricks, On Building Work	\$87.82	7A	11H	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Dozers D-9 & Under	\$86.05	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Drill Oilers: Auger Type, Truck Or Crane Mount	\$86.05	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Drilling Machine	\$88.36	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Elevator and man-lift: permanent and shaft type	\$82.29	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Finishing Machine, Bidwell And Gamaco & Similar Equipment	\$86.71	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Forklift: 3000 lbs and over with attachments	\$86.05	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Forklifts: under 3000 lbs. with attachments	\$82.29	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Grade Engineer: Using Blue Prints, Cut Sheets, Etc	\$86.71	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					

<u>Power Equipment</u>					
<u>Operators- Underground</u>	Gradechecker/Stakeman	\$82.29	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Guardrail Punch	\$86.71	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Hard Tail End Dump				
<u>Operators- Underground</u>	Articulating Off- Road	\$87.49	15J	11G	8X
<u>Sewer & Water</u>	Equipment 45 Yards. & Over				
<u>Power Equipment</u>	Hard Tail End Dump				
<u>Operators- Underground</u>	Articulating Off-road	\$86.71	15J	11G	8X
<u>Sewer & Water</u>	Equipment Under 45 Yards				
<u>Power Equipment</u>	Horizontal/Directional Drill				
<u>Operators- Underground</u>	Locator	\$86.05	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Horizontal/Directional Drill				
<u>Operators- Underground</u>	Operator	\$86.71	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Hydralifts/boom trucks: 10				
<u>Operators- Underground</u>	tons and under	\$82.59	7A	11H	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Hydralifts/boom trucks:				
<u>Operators- Underground</u>	over 10 tons	\$86.36	7A	11H	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Leverman	\$89.27	15J	11G	8X
<u>Operators- Underground</u>					

Sewer & WaterPower EquipmentOperators- UndergroundSewer & Water

Loader, Overhead, 6 Yards.
But Not Including 8 Yards

\$87.49

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Loaders, Overhead Under
6 Yards

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Loaders, Plant Feed

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Loaders: Elevating Type
Belt

\$86.05

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Locomotives, All

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Material Transfer Device

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Mechanics: All (Leadmen -
\$0.50 per hour over
mechanic)

\$88.36

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Motor Patrol Graders

\$87.49

15J**11G****8X**Power EquipmentOperators- Underground

Mucking Machine, Mole,
Tunnel Drill, Boring, Road

\$87.49

15J**11G****8X**

<u>Sewer & Water</u>	Header And/or Shield				
<u>Power Equipment</u>	Oil Distributors, Blower				
<u>Operators- Underground</u>	Distribution & Mulch	\$82.29	15J	11G	8X
<u>Sewer & Water</u>	Seeding Operator				
<u>Power Equipment</u>	Outside Hoists (Elevators				
<u>Operators- Underground</u>	and Manlifts), Air Tuggers,	\$86.05	15J	11G	8X
<u>Sewer & Water</u>	Strato				
<u>Power Equipment</u>	Overhead, bridge type				
<u>Operators- Underground</u>	Crane: 20 tons through 44	\$87.03	7A	11H	8X
<u>Sewer & Water</u>	tons				
<u>Power Equipment</u>	Overhead, bridge type:				
<u>Operators- Underground</u>	100 tons and over	\$88.67	7A	11H	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Overhead, bridge type: 45				
<u>Operators- Underground</u>	tons through 99 tons	\$87.82	7A	11H	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Pavement Breaker	\$82.29	15J	11G	8X
<u>Operators- Underground</u>					
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Pile Driver (other Than				
<u>Operators- Underground</u>	Crane Mount)	\$86.71	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Plant Oiler - Asphalt,				
<u>Operators- Underground</u>	Crusher	\$86.05	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>	Posthole Digger,	\$82.29	15J	11G	8X
<u>Operators- Underground</u>	Mechanical				

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Power Plant	\$82.29	15J	11G	8X
-------------------------------	-------------	---------	------------	------------	-----------

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Pumps - Water	\$82.29	15J	11G	8X
-------------------------------	---------------	---------	------------	------------	-----------

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Quad 9, Hd 41, D10 And Over	\$87.49	15J	11G	8X
-------------------------------	--------------------------------	---------	------------	------------	-----------

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Quick Tower: no cab, under 100 feet in height	\$86.71	15J	11G	8X
-------------------------------	--	---------	------------	------------	-----------

Sewer & Water

base to boom

Power Equipment

<u>Operators- Underground</u>	Remote Control Operator On Rubber Tired Earth	\$87.49	15J	11G	8X
-------------------------------	--	---------	------------	------------	-----------

Sewer & Water

Moving Equipment

Power Equipment

<u>Operators- Underground</u>	Rigger and Bellman	\$82.59	7A	11H	8X
-------------------------------	--------------------	---------	-----------	------------	-----------

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Rigger/Signal Person, Bellman(Certified)	\$86.36	7A	11H	8X
-------------------------------	---	---------	-----------	------------	-----------

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Rollagon	\$87.49	15J	11G	8X
-------------------------------	----------	---------	------------	------------	-----------

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Roller, Other Than Plant Mix	\$82.29	15J	11G	8X
-------------------------------	---------------------------------	---------	------------	------------	-----------

Sewer & WaterPower EquipmentOperators- UndergroundSewer & WaterRoller, Plant Mix Or Multi-
lift Materials

\$86.05

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Roto-mill, Roto-grinder

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Saws - Concrete

\$86.05

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterScraper, Self Propelled
Under 45 Yards

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterScrapers - Concrete &
Carry All

\$86.05

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterScrapers, Self-propelled:
45 Yards And Over

\$87.49

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterShotcrete/Gunite
Equipment

\$82.29

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterShovel, Excavator,
Backhoe, Tractors Under
15 Metric Tons

\$86.05

15J**11G****8X**Power EquipmentOperators- UndergroundShovel, Excavator,
Backhoe: Over 30 Metric

\$87.49

15J**11G****8X**

<u>Sewer & Water</u>	Tons To 50 Metric Tons				
<u>Power Equipment</u>	Shovel, Excavator,				
<u>Operators- Underground</u>	Backhoes, Tractors: 15 To	\$86.71	15J	11G	8X
<u>Sewer & Water</u>	30 Metric Tons				
<u>Power Equipment</u>	Shovel, Excavator,				
<u>Operators- Underground</u>	Backhoes: Over 50 Metric	\$88.36	15J	11G	8X
<u>Sewer & Water</u>	Tons To 90 Metric Tons				
<u>Power Equipment</u>	Shovel, Excavator,				
<u>Operators- Underground</u>	Backhoes: Over 90 Metric	\$89.27	15J	11G	8X
<u>Sewer & Water</u>	Tons				
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Slipform Pavers	\$87.49	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Spreader, Topsider &	\$87.49	15J	11G	8X
<u>Sewer & Water</u>	Screedman				
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Subgrader Trimmer	\$86.71	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Tower Bucket Elevators	\$86.05	15J	11G	8X
<u>Sewer & Water</u>					
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Tower Crane: over 175'	\$89.60	7A	11H	8X
<u>Sewer & Water</u>	through 250' in height, base to boom				
<u>Power Equipment</u>					
<u>Operators- Underground</u>	Tower crane: up to 175' in	\$88.67	7A	11H	8X
<u>Sewer & Water</u>	height base to boom				

Sewer & WaterPower EquipmentOperators- UndergroundSewer & WaterTower Cranes: over 250' in
height from base to boom

\$90.46

7A**11H****8X**Power EquipmentOperators- UndergroundSewer & WaterTransporters, All Track Or
Truck Type

\$87.49

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Trenching Machines

\$86.05

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterTruck Crane Oiler/Driver:
100 tons and over

\$87.03

7A**11H****8X**Power EquipmentOperators- UndergroundSewer & WaterTruck crane oiler/driver:
under 100 tons

\$86.36

7A**11H****8X**Power EquipmentOperators- UndergroundSewer & WaterTruck Mount Portable
Conveyor

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & WaterVac Truck (Vactor Guzzler,
Hydro Excavator)

\$86.71

15J**11G****8X**Power EquipmentOperators- UndergroundSewer & Water

Welder

\$87.49

15J**11G****8X**Power EquipmentOperators- UndergroundWheel Tractors, Farmall
Type

\$82.29

15J**11G****8X**

Sewer & WaterPower Equipment

<u>Operators- Underground</u>	Yo Yo Pay Dozer	\$86.71	15J	11G	8X
-------------------------------	-----------------	---------	------------	------------	-----------

Sewer & Water

<u>Power Line Clearance Tree Trimmers</u>	Journey Level In Charge	\$61.73	5A	4A	
---	-------------------------	---------	-----------	-----------	--

<u>Power Line Clearance Tree Trimmers</u>	Spray Person	\$58.44	5A	4A	
---	--------------	---------	-----------	-----------	--

<u>Power Line Clearance Tree Trimmers</u>	Tree Equipment Operator	\$61.73	5A	4A	
---	-------------------------	---------	-----------	-----------	--

<u>Power Line Clearance Tree Trimmers</u>	Tree Trimmer	\$55.14	5A	4A	
---	--------------	---------	-----------	-----------	--

<u>Power Line Clearance Tree Trimmers</u>	Tree Trimmer Groundperson	\$41.68	5A	4A	
---	------------------------------	---------	-----------	-----------	--

<u>Refrigeration & Air Conditioning Mechanics</u>	Journey Level	\$98.07	6Z	1G	
---	---------------	---------	-----------	-----------	--

Residential Brick Mason	Journey Level	\$71.82	7E	1N	
-------------------------	---------------	---------	-----------	-----------	--

Residential Carpenters	Journey Level	\$36.44		1	
------------------------	---------------	---------	--	----------	--

Residential Cement Masons	Journey Level	\$46.64		1	
---------------------------	---------------	---------	--	----------	--

Residential Drywall Applicators	Journey Level	\$78.76	15J	4C	
---------------------------------	---------------	---------	------------	-----------	--

Residential Drywall Tapers	Journey Level	\$36.36		1	
----------------------------	---------------	---------	--	----------	--

Residential Electricians	Journey Level	\$48.80		1	
--------------------------	---------------	---------	--	----------	--

Residential Glaziers	Journey Level	\$28.93		1
Residential Insulation Applicators	Journey Level	\$28.18		1
Residential Laborers	Journey Level	\$29.73		1
Residential Marble Setters	Journey Level	\$27.38		1
Residential Painters	Journey Level	\$23.47		1
Residential Plumbers & Pipefitters	Journey Level	\$45.40		1
Residential Refrigeration & Air Conditioning Mechanics	Journey Level	\$99.92	7F	1E
Residential Sheet Metal Workers	Journey Level	\$99.92	7F	1E
Residential Soft Floor Layers	Journey Level	\$59.52	5A	3J
Residential Sprinkler Fitters (Fire Protection)	Journey Level	\$63.61		1
Residential Stone Masons	Journey Level	\$71.82	7E	1N
Residential Terrazzo Workers	Journey Level	\$67.51	7E	1N
Residential Terrazzo/Tile Finishers	Journey Level	\$24.39		1
Residential Tile Setters	Journey Level	\$21.04		1

<u>Roofers</u>	Journey Level	\$64.45	5A	3H
<u>Roofers</u>	Using Irritable Bituminous Materials	\$67.39	5A	3H
<u>Sheet Metal Workers</u>	Journey Level (Field or Shop)	\$99.92	7F	1E
Shipbuilding & Ship Repair	New Construction Boilermaker	\$58.93	7X	4J
Shipbuilding & Ship Repair	New Construction Carpenter	\$51.85	7X	4J
Shipbuilding & Ship Repair	New Construction Crane Operator	\$43.00	7V	1
Shipbuilding & Ship Repair	New Construction Electrician	\$58.98	7X	4J
Shipbuilding & Ship Repair	New Construction Heat & Frost Insulator	\$91.81	15H	11C
Shipbuilding & Ship Repair	New Construction Laborer	\$58.60	7X	4J
Shipbuilding & Ship Repair	New Construction Machinist	\$58.79	7X	4J
Shipbuilding & Ship Repair	New Construction Operating Engineer	\$43.00	7V	1
Shipbuilding & Ship Repair	New Construction Painter	\$58.72	7X	4J
Shipbuilding & Ship Repair	New Construction Pipefitter	\$59.07	7X	4J

Shipbuilding & Ship Repair	New Construction Rigger	\$58.93	7X	4J
Shipbuilding & Ship Repair	New Construction Sheet Metal	\$58.68	7X	4J
Shipbuilding & Ship Repair	New Construction Shipwright	\$51.85	7X	4J
Shipbuilding & Ship Repair	New Construction Warehouse/Teamster	\$43.00	7V	1
Shipbuilding & Ship Repair	New Construction Welder / Burner	\$58.93	7X	4J
Shipbuilding & Ship Repair	Ship Repair Boilermaker	\$58.93	7X	4J
Shipbuilding & Ship Repair	Ship Repair Carpenter	\$51.85	7X	4J
Shipbuilding & Ship Repair	Ship Repair Crane Operator	\$45.06	7Y	4K
Shipbuilding & Ship Repair	Ship Repair Electrician	\$58.98	7X	4J
Shipbuilding & Ship Repair	Ship Repair Heat & Frost Insulator	\$91.81	15H	11C
Shipbuilding & Ship Repair	Ship Repair Laborer	\$58.60	7X	4J
Shipbuilding & Ship Repair	Ship Repair Machinist	\$58.79	7X	4J
Shipbuilding & Ship Repair	Ship Repair Operating Engineer	\$45.06	7Y	4K
Shipbuilding & Ship Repair	Ship Repair Painter	\$58.72	7X	4J
Shipbuilding & Ship Repair	Ship Repair Pipefitter	\$59.07	7X	4J

Shipbuilding & Ship Repair	Ship Repair Rigger	\$58.93	7X	4J
Shipbuilding & Ship Repair	Ship Repair Sheet Metal	\$58.68	7X	4J
Shipbuilding & Ship Repair	Ship Repair Shipwright	\$51.85	7X	4J
Shipbuilding & Ship Repair	Ship Repair Warehouse / Teamster	\$45.06	7Y	4K
<u>Sign Makers & Installers</u> (Electrical)	Journey Level	\$58.04	0	1
<u>Sign Makers & Installers</u> (Non-Electrical)	Journey Level	\$37.08	0	1
<u>Soft Floor Layers</u>	Journey Level	\$63.29	15J	4C
<u>Solar Controls For Windows</u>	Journey Level	\$16.66		1
<u>Sprinkler Fitters (Fire Protection)</u>	Journey Level	\$96.99	5C	1X
<u>Stage Rigging Mechanics</u> (Non Structural)	Journey Level	\$16.66		1
<u>Stone Masons</u>	Journey Level	\$71.82	7E	1N
<u>Street And Parking Lot Sweeper Workers</u>	Journey Level	\$19.09		1
<u>Surveyors</u>	Assistant Construction Site Surveyor	\$86.36	7A	11H 8X
<u>Surveyors</u>	Chainman	\$82.59	7A	11H 8X

<u>Surveyors</u>	Construction Site Surveyor	\$87.82	7A	11H	8X
<u>Surveyors</u>	Drone Operator (when used in conjunction with survey work only)	\$82.59	7A	11H	8X
<u>Surveyors</u>	Ground Penetrating Radar Operator	\$82.59	7A	11H	8X
<u>Telecommunication Technicians</u>	Journey Level	\$67.16	7E	1E	
<u>Telephone Line Construction - Outside</u>	Cable Splicer	\$41.35	5A	2B	
<u>Telephone Line Construction - Outside</u>	Hole Digger/Ground Person	\$27.31	5A	2B	
<u>Telephone Line Construction - Outside</u>	Telephone Equipment Operator (Light)	\$34.53	5A	2B	
<u>Telephone Line Construction - Outside</u>	Telephone Lineperson	\$39.07	5A	2B	
<u>Terrazzo Workers</u>	Journey Level	\$67.51	7E	1N	
<u>Tile Setters</u>	Journey Level	\$65.51	7E	1N	
<u>Tile, Marble & Terrazzo Finishers</u>	Finisher	\$56.34	7E	1N	
<u>Traffic Control Stripers</u>	Journey Level	\$92.44	15L	1K	
<u>Truck Drivers</u>	Asphalt Mix Over 16 Yards	\$79.40	15J	11M	8L

<u>Truck Drivers</u>	Asphalt Mix To 16 Yards	\$78.56	15J	11M	8L
<u>Truck Drivers</u>	Dump Truck	\$78.56	15J	11M	8L
<u>Truck Drivers</u>	Dump Truck & Trailer	\$79.40	15J	11M	8L
<u>Truck Drivers</u>	Other Trucks	\$79.40	15J	11M	8L
<u>Truck Drivers - Ready Mix</u>	Transit Mix	\$79.40	15J	11M	8L
<u>Well Drillers & Irrigation Pump Installers</u>	Irrigation Pump Installer	\$17.71		1	
<u>Well Drillers & Irrigation Pump Installers</u>	Oiler	\$16.66		1	
<u>Well Drillers & Irrigation Pump Installers</u>	Well Driller	\$18.00		1	