

ADDENDUM NO. 2

**Citywide Adaptive Signal Control System – ITS Improvements – Phase 1 & 2 and Phase 3
RFB # 19-011**

ATTENTION: All Bidders and Planholders

You are hereby notified that in Addendum No. 2, the Bid and Contract Documents are amended as follows:

A) PLANS

(1) Sheet 1, ITSN01:

DELETE this page and REPLACE with the attached revised Sheet ITSN01.

This change provides clarification to the general notes that cable labels and non-slip lids/frames are only intended for new cables/junction boxes/cable vaults that are being installed.

B) CONTRACT DOCUMENTS

(1) Request for Bids, Advertisement for Bids (Page RFB-3):

REVISE the last sentence of the third paragraph to read:

Regardless of the date of award or Notice to Proceed, the Contractor must complete all work within 100 working days.

(2) Special Provisions, 1-08.5 Time for Completion (Page SP-51):

REVISE the first sentence to read:

This project shall be physically complete within 100 working days.

(3) Special Provisions, 8-20.3(1) General (Page SP-62):

REVISE the second subsection to read:

(*****)

8-20.3(1) is supplemented with the following:

The Contractor shall remove and relocate existing video detection cameras for re-use on other parts of the project as shown in the Plans.

The following table regarding detection quantities is approximate and is provided for the Contractor's reference only:

Sheet Name	Re-Orient Existing Video Detection Camera	Remove Existing Video Detection Camera for Re-Use at Other Locations	Install Re-Located Video Detection Camera	Install New Video Detection Camera	Install New Video Detection Rack	Install New Hybrid Radar/Video Detection Camera	Install New Hybrid Radar/Video Detection Cabinet Interface Unit	Install New Loop Detector	Re-Splice Existing Loop Detector
ITS01			1					1	
ITS02								1	2
ITS03	1	3				4	1		
ITS04				2	1			1	
ITS05		3				3	1		
ITS06	2	2				4	1		
ITS07		1	1			1	1	2	
ITS08		2				2	1	1	
ITS09	3	1				4	1		
ITS10						1	1	1	
ITS11				1	1			2	
ITS12			2		1			1	
ITS13		2				2	1	1	
ITS14									
ITS15				2	1*	2	1	1	2
ITS16				1	1*	1	1		3
ITS17									
ITS18									
ITS19									
ITS20									
ITS21									
ITS22									
ITS23									
ITS24									
ITS25									
ITS26	2					2	1	2	
ITS27		1	2			1	1	2	
ITS28		1	2			1	1	6	
ITS29	1		2			1	1	2	
ITS30			3					3	
ITS31		3				3	1	2	
ITS32	1					1	1	1	
ITS33									
ITS34	1	1	2			2	1	7	
ITS35				3	1*	1	1	3	2
ITS36		1	1			1	1	2	
ITS37			3		1			2	
ITS38									
ITS39									

Sheet Name	Re-Orient Existing Video Detection Camera	Remove Existing Video Detection Camera for Re-Use at Other Locations	Install Re-Located Video Detection Camera	Install New Video Detection Camera	Install New Video Detection Rack	Install New Hybrid Radar/Video Detection Camera	Install New Hybrid Radar/Video Detection Cabinet Interface Unit	Install New Loop Detector	Re-Splice Existing Loop Detector
ITS40									
ITS41						2	1		
ITS42	1			1		1	1		
ITS43				2	1*	1	1	8	
ITS44				1	1*	1	1		
ITS45				1	1*	1	1		2
ITS46			1					3	2
ITS47			2			1	1	1	
ITS48						2	1		4
ITS49		2		3	1*	2	1	1	
ITS50		2	2			2	1	2	
ITS51		2	2			2	1	2	
ITS52				1	1*	1	1		
ITS53						2	1	2	
ITS54						2	1	2	
ITS55			1		1			2	2
ITS56						3	1	1	
ITS57				2	1*	2	1		
TOTAL	12	27	27	20	14	62	34	68	19

* Contractor may evaluate the potential to reduce the number of new video detection racks needed, per the Special Provisions.

(4) Special Provisions, 8-20.3 Construction Requirements (Page SP-63):

SUPPLEMENT this section with the following:

(*****)

8-20.3(1) is supplemented with the following:

The Contractor shall construct the improvements in segments based on the following list, prioritized from highest priority to lowest priority. The Contractor shall complete all work associated with one segment, of higher priority, prior to constructing improvements associated with the next segment, of lower priority.

1. S 320th St, from S 320th St & 11th Pls S to S Peasley Canyon Rd & S 321st St (11 intersections – Plan Sheets ITS1, ITS2, ITS3, ITS4, ITS5, ITS6, ITS11, ITS12, ITS13, ITS15, and ITS16).
2. S 348th St, from SR 99 & S 348th St to SR 18 & I-5 SB (3 intersections – Plan Sheets ITS28, ITS34, and ITS41).
3. SR 99, from SR 99 & S 276th St to SR 99 & S 356th St, including S 312th St & 14th Ave S (15 intersections – Plan Sheets ITS7, ITS8, ITS9, ITS10, ITS26, ITS27, ITS29, ITS30, ITS31, ITS32, ITS47, ITS48, ITS49, ITS50, and ITS51).
4. Enchanted Pkwy S (SR 161)/16th Ave S, from S 344th St & 16th Ave S to Enchanted Pkwy S (SR 161) & 19th Way S (6 intersections – Plan Sheets ITS35, ITS36, ITS37, ITS42, ITS43, and ITS44).
5. Dash Pt Rd (SR 509), from Dash Pt Rd & 11th Pl S to Dash Pt Rd & 16th Ave S (2 intersections – Plan Sheets ITS45 and ITS46).
6. S 288th St, from S 288th St & 18th Ave S to Military Rd S & S 288th St (2 intersections – Plan Sheets ITS52 and ITS56).
7. Military Rd S, from Military Rd S & S Star Lake Rd to Military Rd S & 31st Ave S, including S 304th St & 28th Ave S (4 intersections – Plan Sheets ITS53, ITS54, ITS55, and ITS57).

(5) Special Provisions, 9-29.18(3) Video Detection System (Page SP-99):

REVISE this section to read:

All video detection system items and materials furnished shall be new, unused, current production models installed and operational in a user environment and shall be items currently in distribution. Contractor shall provide Econolite AutoScope Vision video detection system, or equivalent approved equal that limits the amount of new in-cabinet equipment and additional inventory management needed.

C) BID OPENING

The bid opening date **has not** changed.

All bidders are required to acknowledge receipt of this addendum on page RFB-14 of the Bid Form. Failure to do so may cause rejection of the bid.

CITY OF FEDERAL WAY

Naveen G. Chandra, P.E.
Senior Capital Engineer