

EXHIBIT A

**REQUEST FOR QUOTE
CITY OF FEDERAL WAY
2016-17 Neighborhood Traffic Safety (NTS) Program**

Vendor Name:
Date Prepared:

Exhibit A, Schedule A Notes:

- 1 All items shall include in the price any required layout, mobilization, traffic control, roadside cleanup, or any other incidentals.
- 2 All permanent pavement markings for traffic calming devices shall be done by others.
- 3 All permanent signs for traffic calming devices are done by others.
- 4 Any removal of pavement markings will be done by others.
- 5 Unit Price is per Each for a Traffic Circle Island, Complete within the circle diameter range, in feet.

SCHEDULE A, (Example of a "Typical" Project As Described Under Section VI-1)

Item	"Typical" Project Quantity	Unit	Unit Price	Multiplier	Total
B-7 Speed Hump, Complete (includes toe grind and temporary markings. Permanent signing and markings by others.) COFW Development Standard 3-26, COFW SP 8-32	2	EA		2	\$0.00
B-9 Raised Crosswalk, Complete (includes toe grind and temporary markings. Permanent signing and markings by others.) COFW Development Standard 3-27, COFW SP 8-33	1	EA		1	\$0.00
B-16⁵ Traffic Circle Island, Complete (includes painted pre-cast curb, pavement removal, monument case & valve box adjustment, topsoil. Each (1) island by Circle Diameter range in feet) COFW Development Standard 3-59, COFW SP 8-04	32-foot Diameter Circle 1	EA		1	\$0.00
Total of Schedule A			=		\$0.00

Must be the same as Schedule B Price

SCHEDULE B, (Discretionary Work Orders As Described Under Section VI-2)

Item	Quantity Range	Unit	Unit Price	Multiplier	Total ⁶
B-1 Pre-Cast Traffic Curb, Painted WSDOT Standard Specification Section 8-07 COFW Special Provision 8-07	50 100	LF		50	\$0.00
	101 500	LF		101	\$0.00
	501 +	LF		501	\$0.00
B-2 Block Traffic Curb, Painted COFW Development Standard 3-4 COFW Special Provision 8-07	50 100	LF		50	\$0.00
	101 500	LF		101	\$0.00
	501 +	LF		501	\$0.00
B-3 Extruded Curb, Painted WSDOT Standard Specification Section 8-07 (except no rebar) COFW Development Standard 3-4A, COFW SP 8-07	50 100	LF		50	\$0.00
	101 500	LF		101	\$0.00
	501 +	LF		501	\$0.00
B-4 Remove Pre-Cast, Block, or Extruded Curb (include asphalt patching if necessary) WSDOT Standard Specification Section 2-02.3(3), COFW SP 8-07	50 100	LF		50	\$0.00
	101 500	LF		101	\$0.00
	501 +	LF		501	\$0.00
B-5 Crushed Surfacing Top Course, Include Haul WSDOT Standard Specification Section 4-04, 9-03 COFW Special Provision 4-04	1 5	TON		1	\$0.00
	6 15	TON		6	\$0.00
	15 +	TON		15	\$0.00
B-6 HMA Class 1/2" PG 64-22 WSDOT Standard Specification Section 5-04 COFW Special Provision 5-04	1 5	TON		1	\$0.00
	6 15	TON		6	\$0.00
	15 +	TON		15	\$0.00
B-7 Speed Hump, Complete (includes toe grind and temporary markings. Permanent signing and markings by others.) COFW Development Standard 3-26, COFW SP 8-32	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-8 Speed Table, Complete (includes toe grind and temporary markings. Permanent signing and markings by others.) COFW Development Standard 3-27A, COFW SP 8-33	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-9 Raised Crosswalk, Complete (includes toe grind and temporary markings. Permanent signing and markings by others.) COFW Development Standard 3-27, COFW SP 8-33	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-10 Remove Speed Hump, Speed Table, or Raised Crosswalk (include asphalt patching if necessary) COFW SP 8-04 WSDOT Standard Specification Section 2-02.3(3)	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-11 Pedestrian Refuge Island, Complete (includes detectable warning strips) COFW SP 8-04 COFW Development Standard 3-58	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-12 Remove Pedestrian Refuge Islands, Complete (include asphalt patching if necessary) COFW SP 8-04 WSDOT Standard Specification Section 2-02.3(3)	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-13 Remove & Replace Concrete Curb Ramp, Complete COFW Development Standard 3-8, 3-8A, 3-8B, 3-10, 3-10A, 3-11, WSDOT Std Plan F-40.14 (Up to 25 ft.) COFW SP 8-04, 8-14	1	EA		1	\$0.00
	2 3	EA		2	\$0.00
	4 +	EA		4	\$0.00
B-14 Remove & Replace Concrete Sidewalk, Complete COFW Development Standard 3-3 & 3-12 COFW Special Provision 8-04, 8-14	5 10	SY		5	\$0.00
	11 50	SY		11	\$0.00
	51 +	SY		51	\$0.00
B-15 Remove & Replace Concrete Curb & Gutter, Complete (includes sawcutting, disposal, asphalt patching) COFW Dwg 3-4, 3-4A & WSDOT Stnd. Spec. 5-04.3(14), COFW SP 8-04	10 30	LF		10	\$0.00
	31 100	LF		31	\$0.00
	101 +	LF		101	\$0.00
B-16⁷ Traffic Circle Island, Complete (includes painted pre-cast curb, pavement removal, monument case & valve box adjustment, topsoil. Each (1) island by Circle Diameter range in feet) COFW Development Standard 3-59, COFW SP 8-04	Diam.(ft) Quantity				
	10' - 16' 1	EA		1	\$0.00
	17' - 24' 1	EA		1	\$0.00
	25' - 32' 1	EA		1	\$0.00
Total of Schedule B				=	\$0.00
Adjusted Total of Schedule B⁸			X	0.10	\$0.00
Total (Total of Schedule A + Adjusted Total of Schedule B)					\$0.00

Exhibit A, Schedule B Notes:

- 6 Line Item Total for Schedule B are calculated by multiplying the quantity range minimum by the unit price, except for item B-16.
- 7 Unit Price is per Each for a Traffic Circle Island, Complete within the circle diameter range, in feet.
- 8 Adjusted (weighted) Total reflects likelihood that only 10% of discretionary work in Schedule B will be requested.

Note: The contract resulting from this RFQ is mainly for future discretionary work orders; exact quantities and locations are unknown. The City's recent historical average for this work is approximately \$25,000 per year. Discretionary work orders are typically issued multiple times throughout the calendar year.